DocuSign Envelope ID: F628CEDE-11E1-47E7-AC47-A605CA743511

TIP NO.	SHEET NO.
17BP.14.R.149	PMP-2

APPROVED: Lloyd D. Brown (DocuSigned by: 339D4DF17F5746B...)

DATE: 7/15/2021

NORTH CAROLINA PROFESSIONAL SEAL 20119 ENGINEER LLOYD D. BROWN

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PAVEMENT MARKING DETAIL AND SCHEDULE



PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	QUANTITY BREAKDOWN	PAY ITEM	TOTAL QUANTITY
P1	WHITE EDGELINE	750 FT	PAINT (4", 2 COATS)	1,500 FT
P13	YELLOW DOUBLE CENTER	750 FT	PAINT (4", 2 COATS)	1,500 FT

7/1/2021 11:49:08 AM
V:\Asheville\transportation\3163-06 Jackson 185 - 17BP.14.R.149\Traffic\TrafficControl\TCP\490185_PMP-2.dgn
User: mfitzpatrick