

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

ROY COOPER J. ERIC BOYETTE GOVERNOR

SECRETARY

November 4, 2020

ADDENDUM #2

To: Plan Holders

W1

From: Wes Jamison

Project Manager

RE: Revised Summary of Quantities sheets to reflect Typical

Section corrections and questions and answers

Contract ID: DN00669 County: Macon

Letting Date: November 10, 2020

The above contract has experienced the following revisions:

- 1. Plan sheet 8, the Summary of Quantities has been revised to correctly associate each typical section with its corresponding map. See attached.
- 2. The following questions were posed by a potential bidder and the associated response has been provided by NCDOT.

Question 1. "According to the Lenscradle Snowplowable Marker specification, there are (2) reflective markers in each groove at each location. So would each location be paid as a quantity of 2 Ea. or 1 Ea.?"

Answer 1. The groove, epoxy, and 2 markers are paid as 1 each.

Question 2. "Are the temporary Pavement Markings paid for by the LF or are they part of the Lump Sum Temporary Traffic Control?"

Answer 2. On DN00669, after milling, the paint will serve as the temporary marking until such time as the temperatures are warm enough to complete paving operations and laying thermo.

Question 3. Is it the intention of the Department to use S9.5B on all of the Maps listed in the DN00669 – Macon contract?

Answer 3. Yes. The ADT for the route dictated the S9.5B.

The ebsx addendum file is accessible on Bid Express $\$ (bidx.com website).

Thank you for your attention to this matter.

PROJECT NO.	SHEET NO.	TOTAL NO.
2020CPT.14.05.10561,		
2020CPT.14.05.20561	°	

SUMMARY OF QUANTITIES

												1245000000-E	1297000000-E	1519000000-E	1520000000-E	1575000000-E	1704000000-E	2815000000-N	2845000000-N	4898000000-N	7444000000-E
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE	FINAL	WARM MIX	LENGTH	WIDTH	SHOULDER	1½" MILLING	SURFACE	LEVELING	ASPHALT	PATCHING	ADJ. OF DROP	ADJ. OF METER	GENERIC	INDUCTIVE
							TYPE	SURFACE TESTING REQUIRED	REQUIRED			RECONSTRUCTI ON		COURSE, S9.5B	COURSE, S9.5B	BINDER FOR PLANT MIX	EXISTING PAVEMENT	INLET	OR VALVE BOX	PAVEMENT MARKING ITEM (SNOWPLOWAB LE PAVEMENT MARKERS WITH	LOOP
																				NON-METALLIC HOUSINGS)	
										MI	FT	SMI	SY	TONS	TONS	TONS	TONS	EA	EA	EA	LF
2020CPT.14.05.10561		1	US-64 (N. 4TH STREET)	FROM NC-106 TO NC-28	1	2	2WU	YES	NO	0.35	54		11,088	1,009		68	177				268
TOTAL FOR MAP NO. 1										0.35			11,088	1,009		68	177				268
2020CPT.14.05.10561	Macon	2	US-64 (N.4TH STREET)	FROM NC-28 TO SR-1538	1	2	2WU	YES	NO	2.67	24		42,401	3,429		230	839			185	
TOTAL FOR MAP NO. 2		D. 2							2.67			42,401	3,429		230	839			185		
				FROM SR-1613 TO BEGIN OF CURB																	
2020CPT.14.05.10561	Macon	3	NC-28 (S.4TH STREET	AND GUTTER	2	2	2WU	YES	NO	1.7	22	3.40		2,002	1,211	215	281				
	TOTAL FOR MAP NO. 3		D. 3							1.7		3.40		2,002	1,211	215	281				
				FROM BEGIN OF CURB AND GUTTER																	
2020CPT.14.05.10561	Macon	4	NC-28 (S.4TH STREET)	TO US-64	1	2	2WU	NO	NO	0.43	22		7,025	507		34	86				80
	TOTAL FOR MAP NO. 4								0.43			7,025	507		34	86				80	
TOTAL F	OR PROJ N	O. 2020CP1	Г.14.05.10561							5.15		3.40	60,514	6,947	1,211	547	1,383			185	348
2020CPT.14.05.20561	Macon	5	SR-1001(ELIJAY RD)	FROM SR-1528 TO US64/NC28	2	2	2WU	NO	NO	4.4	18	8.10		3,273	1,923	348	27				
	TOTAL F	OR MAP NO	D. 5							4.4		8.10		3,273	1,923	348	27				
2020CPT.14.05.20561	Macon	6	SR-1603 (MAIN STREET)	FROM US 64/NC 28 TO SR-1689	1	2		NO	NO	0.11	84		5,421	493		33		4	4		
TOTAL FOR MAP NO. 6									0.11			5,421	493		33		4	4			
2020CPT.14.05.20561	Macon	7	SR-1600 (WHITESIDE MTN)	FROM US 64 TO END OF MAINT	3	2	2WU	NO	NO	1.41	16				1,055	71	235				
TOTAL FOR MAP NO. 7									1.41					1,055	71	235					
TOTAL F	OR PROJ N	O. 2020CP1	Г.14.05.20561							5.92		8.10	5,421	3,766	2,978	452	262	4	4		
	GRA	ND TOTAL								11.07		11.50	65,935	10,713	4,189	999	1,645	4	4	185	348

THERMOPLASTIC AND PAINT QUANTITIES

					,					4413000000-E	4457000000-N	4702000000-E	4710000000-E	47250	00000-E	481000000-E		4825000000-E	4835000000-E	484500	0000-N	000-N 489000000-E	
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	WORK ZONE ADVANCE/GENE RAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	-	24" X 120 M WHITE THERMO			4" WHITE PAINT	4" YELLOW PAINT	12" WHITE PAINT	24" WHITE PAINT	PAINT LT ARROW	PAINT STR & RT ARROW	GENERIC PAVE. MARK ITEM 4" X 50 MIL WHITE THERMO	1
								MI	FT	SF	LS	LF	LF	EA	EA	LF	LF	LF	LF	EA	EA	LF	LF
2020CPT.14.05.10561	Macon	1	US-64 (N. 4TH STREET)	FROM NC-106 TO NC-28	1	2	2WU	0.35	54	38	1.00	316	264	2	2	7,317	7,317	316	264			3,658	3,658
	TOTAL FOR MAP NO. 1							0.35		38	1	316	264	2	2	7,317	7,317	316	264			3,658	3,658
2020CPT.14.05.10561	2020CPT.14.05.10561 Macon 2 US-64 (N.4TH STREET)		FROM NC-28 TO SR-1538	1	2	2WU	2.67	24	299			380	6	2	57,458	57,458		380	6	2	28,195	28,195	
	TOTAL FOR MAP NO. 2							2.67		299			380	6	2	57,458	57,458		380	6	2	28,195	28,195
2020CPT.14.05.10561	Macon	3	NC-28 (S.4TH STREET	FROM SR-1613 TO BEGIN OF CURB AND GUTTER	2	2	2WU	1.7	22	190						36,584	36,584					18,292	18,292
TOTAL FOR MAP NO. 3							1.7		190						36,584	36,584					18,292	18,292	
2020CPT.14.05.10561	Macon	4	NC-28 (S.4TH STREET)	FROM BEGIN OF CURB AND GUTTER TO US-64	1	2	2WU	0.43	22	48				1		2,000	4,528			1		2,264	1,000
	TOTAL F	OR MAP NO	0. 4					0.43		48				1		2,000	4,528			1		2,264	1,000
TOTAL		0 202000						5.15		575	1	316	644	9	4	103,359	105,887	316	644	7	2	52,409	51,145
TOTAL	-OK PROJ N	U. 2020CP	Г.14.05.10561											1	13	209	,246				9	103,5	554
2020CPT.14.05.20561	Macon	5	SR-1001(ELIJAY RD)	FROM SR-1528 TO US64/NC28	2	2	2WU	4.4	18	454		1				87,156	87,156			Γ			$\overline{}$
		OR MAP NO					1	4.4		454						87,156	87,156						1
2020CPT.14.05.20561	Macon	6	SR-1603 (MAIN STREET)	FROM US 64/NC 28 TO SR-1689	1	2		0.11	84	64						4.646	,						1
		OR MAP NO		,				0.11		64						4,646							1
2020CPT.14.05.20561	Macon	7	SR-1600 (WHITESIDE MTN)	FROM US 64 TO END OF MAINT	3	2	2WU	1.41	16	96						30,343	30,366						
	TOTAL F	OR MAP NO	0.7					1.41		96						30,343	30,366						
TOTAL		0 202000						5.92		614						122,145	117,522						
TOTAL FOR PROJ NO. 2020CPT.14.05.20561			1.14.05.20561												239,6		239,667						
					1	_	Т	44.07	T	1 1100		346	CAA			225 504	222.400	246	C44			F2 400	F4.445
	GRA	ND TOTAL			-	1	-	11.07		1,189	1	316	644	9	4	225,504	223,409	316	644	7	<u> </u>	52,409 103,5	51,145
								l						13		448,913					7	103,5	J34