



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

November 4, 2020

**ADDENDUM # 2**

To: Plan Holders

From: Wes Jamison  
Project Manager



RE: **Revised Summary of Quantities sheets to reflect Typical  
Section corrections and questions and answers**  
Contract ID: DN00727  
County: Jackson  
Letting Date: November 10, 2020

The above contract has experienced the following revisions:

1. Plan sheet 3, the Summary of Quantities has been revised to correctly associate each typical section with its corresponding map. See attached.
2. The following questions were posed by a potential bidder and the associated response has been provided by NCDOT.

**Question 1.** “According to the Lenscradle Snowplowable Marker specification, there are (2) reflective markers in each groove at each location. So would each location be paid as a quantity of 2 Ea. or 1 Ea.?”

**Answer 1. The groove, epoxy, and 2 markers are paid as 1 each.**

**Question 2.** “Are the temporary Pavement Markings paid for by the LF or are they part of the Lump Sum Temporary Traffic Control?”

**Answer 2. On DN00727 the milling, paving, and pavement marking operations are expected to be completed without the need for temporary paint.**

**Question 3.** Is the intention of the Department to use S9.5B on Map 1 – US 64 on the DN00727 – Jackson contract?

**Answer 3. Yes. The ADT for the route dictated the S9.5B.**

The ebsx addendum file is accessible on Bid Express® (bidx.com website).

Thank you for your attention to this matter.

PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.14.05.10501	3	

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	1220000000-E	1245000000-E	1330000000-E	1519000000-E	1520000000-E	1575000000-E	1704000000-E	4898000000-N		
										INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	INCIDENTAL MILLING	SURFACE COURSE, S9.5B	LEVELING COURSE, S9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	GENERIC PAVEMENT MARKING ITEM (SNOWPLOWABLE PAVEMENT MARKERS WITH NON-METALLIC HOUSINGS)		
										MI	FT	TONS	SMI	SY	TONS	TONS	TONS	EA	
2021CPT.14.05.10501	Jackson	1	US 64 (SAFPPIRE AND CASHIERS AERA)	FROM TRANSYLVANIA LINE TO .01 MILES WEST OF SR-1120	1	2	2WU	NO	NO	5.5	24	60	11.00	533	7,193	600	522	1,670	624
<b>TOTAL FOR MAP NO. 1</b>										5.5		60	11.00	533	7,193	600	522	1,670	624
<b>TOTAL FOR PROJ NO. 2021CPT.14.05.10501</b>										5.5		60	11.00	533	7,193	600	522	1,670	624
<b>GRAND TOTAL</b>										5.5		60	11.00	533	7,193	600	522	1,670	624

### THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	4405000000-E	4413000000-E	4457000000-N	4710000000-E	4810000000-E		4890000000-E			
								PORTABLE WORK ZONE SIGN	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	24" X 120 M WHITE THERMO	4" WHITE PAINT	4" YELLOW PAINT	GENERIC PAVE. MARK ITEM 4" X 60 MIL WHITE THERMO	GENERIC PAVE. MARK ITEM 4" X 60 MIL YELLOW THERMO.		
								MI	FT	SF	SF	LS	LF	LF	LF	LF	
2021CPT.14.05.10501	Jackson	1	US 64 (SAFPPIRE AND CASHIERS AERA)	FROM TRANSYLVANIA LINE TO .01 MILES WEST OF SR-1120	1	2	2WU	5.5	24	96	564	1.00	200	5,000	5,000	59,180	59,180
<b>TOTAL FOR MAP NO. 1</b>								5.5		96	564	1	200	5,000	5,000	59,180	59,180
<b>TOTAL FOR PROJ NO. 2021CPT.14.05.10501</b>								5.5		96	564	1	200	5,000	5,000	59,180	59,180
<b>GRAND TOTAL</b>								5.5		96	564	1	200	5,000	5,000	59,180	59,180
													10,000		118,360		