PROJECT REFERENCE NO.	SHEET NO.
EB-5964	1-A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

INDEX OF SHEETS

1	TITLE SHEET
1A	INDEX OF SHEETS, GENERAL NOTES AND LIST OF STANDARDS
1B	CONVENTIONAL SYMBOLS
2-2A	TYPICAL SECTIONS
3	SUMMARY SHEET
W1	STANDARD CIP GRAVITY RETAINING WALL DETAIL
RW02C1 - RW02C4	SURVEY CONTROL SHEETS
4-5	PLAN SHEETS
6-7	PROFILE SHEETS
EC1-EC5	EROSION CONTROL SHEETS
X1-X78	CROSS SECTIONS

GENERAL NOTES

GENERAL NOTES: 2024 SPECIFICATIONS
EFFECTIVE: 01-16-2024

1 CARE SHALL BE TAKEN TO PREVENT DAMAGE TO EXISTING UTILITIES DURING CONSTRUCTION. ANY DAMAGE TO THESE UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

2 THE CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY.

3 CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III

4 DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. 848.02 USING 3 FOOT RADII OR RADII AS SHOWN ON THE PLANS. LOCATIONS OF DRIVES WILL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

5 NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

6 CURB RAMPS ARE SHOWN ON THE PLANS AT APPROXIMATE LOCATIONS. CONSTRUCT ALL CURB RAMPS ACCORDANCE WITH STD 848.06.

UTILITY OWNERS:

-TOCCOA NATURAL GAS
-BALSAM WEST
-DUKE ENERGY
-FRONTIER COMMUNICATIONS
-TOWN OF FRANKLIN

LIST OF ROADWAY STANDARDS

2024 ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" - Highway Design Branch - N.C. Department of Transportation - Raleigh, N.C., dated January 16, 2024 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

STD. NO.	TITLE
DIVISION 2 - EARTHWORK	
200.03	Method of Clearing Modified Method - III
DIVISION 3 - PIPE CULVERTS	
300.01	Method of Pipe Installation Flexible and Rigid Pipes
DIVISION 8 - INCIDENTALS	
840.01	Brick Catch Basin 12" Thru 54" Pipe
840.03	Frame, Grates, and Hood for Use on Standard Catch Basin
840.31	Concrete Junction Box 12" Thru 66" Pipe
840.32	Brick Junction Box 12" Thru 66" Pipe
840.54	Manhole Frame and Cover
840.66	Drainage Structure Steps
840.71	Concrete and Brick Pipe Plug
846.01	Concrete Curb, Gutter and Curb and Gutter
848.01	Concrete Sidewalk
848.03	Driveway Turnout Drop Curb Style
848.06	Curb Ramp Directional Ramp, Island Ramp and Notes
DIVISION 11 - WORK ZONE TRAFFIC CONTROL	
1101.01	Work Zone Advance Warning Signs
1101.02	Temporary Lane Closures
1101.04	Temporary Shoulder Closures
1101.11	Traffic Control Design Tables
1110.01	Stationary Work Zone Signs
1110.02	Portable Work Zone Signs
1130.01	Drum
1135.01	Cones
1150.01	Flagging Devices
1180.01	Skinny Drum