LEGEND	
	EXIST. STREET LIGHT
	EXIST. POST TOP LIGHT

NOTES

ALL LIGHT POLES TO BE SANDED, CLEANED AND PRIMED BEFORE APPLYING 2 COATS OF OIL BASED EXTERIOR GRADE PAINT.

SEE ALSO SITE ELECTRICAL DRAWING FOR FURTHER INFORMATION

The Rest Area is located in the Floodway of the Valley River as identified on panel 5556 of FEMA maps. All finished floor elevations of the existing and proposed structure are above the 100-year base flood elevation of 1743.5 by more than the required 2 feet. The finished floor of the existing and proposed structure is at elevation 1749.0 or 5.5 feet above the base flood elevation. No additional foot print will be established in the floodway for the structure. The net number of piers will be reduced. The work in the floodway and floodplain will be completed by small equipment (ex. supermini excavator) and removed from the floodway when not in use. The equipment will be stored in the truck parking area during construction and will be removed if the threat of flooding is imminent.

1 **SITE PLAN**
SCALE: 1" = 20'-0"

0' 20' 40' 60'

WEEKS TURNER ARCHITECTURE

WEEKS TURNER ARCHITECTURE, PA
3305-109 Durham Drive
Raleigh, North Carolina 27603
919.779.9797 fax: 919.779.0826
www.weeksturner.com

GINGER S. ANDERSON
REGISTERED ARCHITECT
11075
NORTH CAROLINA
RALEIGH, NC

DocuSigned by:
E9D2834562C422...
10/19/2016

STATE ID# 16-16033-01A
WBS ELEMENT 51213.011

PROJECT TITLE
CHEROKEE COUNTY REST AREA
US 19 AND COVER STREET
ANDREWS, NORTH CAROLINA

PROJECT NO.
1504a

DRAWING TITLE
SITE PLAN-REVISED

SHEET 4 OF 22

A0.4

PLOT DATE 10/18/16
REVISION 00/00/08

This original sheet is 22" x 34"; other dimensions indicate it has been altered.

All information on this sheet is the property of Weeks Turner Architecture and may not be duplicated in whole or in part without written authorization from Weeks Turner Architecture. 2008 ©