DocuSign Envelope ID: 3CEA61FA-3231-4E2C-9F4B-E5E30E582E33

1 / S1 BUILDING FOUNDATION PLAN

SCALE 1/8" = 1'-0"

2 / S1 PIER FOOTING

SCALE: 1" = 1'-0"

NOTE: ALL HARDWARE AND/OR FASTENERS THAT COME IN CONTACT WITH ANY TREATED LUMBER SHALL BE HOT-DIPPED GALVANIZED, STAINLESS STEEL, OR APPROVED CORRISION RESISTANT.

FOOTING SCHEDULE

MARK	SIZE	REINFORCING
a	3'-0" x 3'-0" X12" FOOTING	4 #5's EACH WAY

ALL FOOTINGS BASED ON
2000 PSF BEARING CAPACITY.
CONTRACTOR RESPONSIBLE
FOR MEETING THIS REQUIREMENT.

3 / S1 FRAMING @ ADDITION

SCALE: 1" = 1'-0"

WEEKS TURNER ARCHITECTURE

WEEKS TURNER ARCHITECTURE, PA
3305-109 Durham Drive
Raleigh, North Carolina 27603
919.779.9797 fax: 919.779.0826
www.weeksturner.com

ENGINEER
W.E. RATTERREE, P.E.
Structural Engineer
1150 W. Dodson Mill Rd.
Pilot Mt., NC
(919) 210-1839
billratt1984@gmail.com

SEAL:

DocuSigned by:
Bill Ratterree
B7718FDF7A41440...
10/12/2016

STATE ID# 16-16033-01A
WBS ELEMENT 51213.011

PROJECT TITLE
CHEROKEE COUNTY REST AREA
US 19 AND COVER STREET
ANDREWS, NORTH CAROLINA

PROJECT NO.
1504a

DRAWING TITLE
FOUNDATION

SHEET 1 OF 4

S1

PLOT DATE	10/11/16
REVISION	00/00/08

This original sheet is 22" x 34"; other dimensions indicate it has been altered.

All information on this sheet is the property of Weeks Turner Architecture and may not be duplicated in whole or in part without written authorization from Weeks Turner Architecture. 2008 ©