PROJ. REFERENCE NO.	SHEET NO.
HB-0030	X-1

Note: Approximate quantities only. Clearing and Grubbing, Unclassified Excavation, Fine Grading, and Removal of Existing Asphalt Pavement will be paid for at the contract lump sum price for grading.

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Note: Quantities are approximate only. The Resident Engineer will use methods including but not limited to recross-sectioning, truck measurements, and aerial surveys to compute final quantities which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+50.00	23	2
14+00.00	35	55
14+50.00	26	169
15+00.00	25	309
15+50.00	27	208

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+00.00	23	108
17+50.00	48	327
18+00.00	44	467
18+50.00	19	248

Station DW1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+25.00	2	15
11+50.00	6	1