DocuSign Envelope ID: 176C124D-2C1B-41D2-A403-8BF19F44DC0E

PROJ. REFERENCE NO.	SHEET NO.
17BP.14.R.87	PMP-1

PAVEMENT MARKING SCHEDULE
TIP PROJECT # 17BP.14.R.87

SYMBOL	DESCRIPTION	FINAL PAVEMENT MARKINGS	PAY ITEM QUANTITY BREAKDOWN	TOTAL QUANTITY
PI	YELLOW DOUBLE CENTER	PAINT (4", 2 COATS)	1250 LF	2500 LF
PA	WHITE EDGELINE	PAINT (4", 2 COATS)	1166 LF	2332 LF
P8	2FT – 6FT /SP WHITE MINISKIP	PAINT (4", 2 COATS)	82 LF	41 LF

GENERAL NOTES / LOCAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

PAVEMENT MARKINGS AND MARKERS

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
Hiawassee Dam Access Road	Paint	None

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C) REMOVE /REPLACE ANY CONFLICTING /DAMAGED PAVEMENT MARKINGS AND MARKERS BY THE END OF EACH DAY'S OPERATION.

D) ALL PAVEMENT MARKINGS ARE EXISTING UNLESS OTHERWISE NOTED.

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS SHOWN IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANAUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO LANE AND MULTILANE ROADWAYS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

WSP USA Inc.
1001 MOREHEAD SQUARE DRIVE
SUITE 610
CHARLOTTE, NC 28203
TEL:L704-342-5401

WSP.COM

LICENSE NO. F-0165

APPROVED: DocuSigned by: 6E04DD32FEE4460... DATE: 11/3/2017

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 037467 ENGINEER RICHARD A. ODYNSKI

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION WORK ZONE TRAFFIC CONTROL

PAVEMENT MARKING PLAN

6/14/2017
T:\NCDOT_Div 14 LIBR\Group 1\Cherokee 126\17BP.14.R.87_TC_PMP.dgn
odynski.a