DocuSign Envelope ID: 2006BE60-5D85-40A1-8986-9B828F5FE6DF

PROJ. REFERENCE NO.	SHEET NO.
17BP.14.R.91	PMP-1

PAVEMENT MARKING SCHEDULE

PA PAINT WHITE EDGELINE (4″, 90 MILS, 2 COATS)
PI PAINT YELLOW DOUBLE CENTER LINE (4″, 120 MILS, 2 COATS)

PAVEMENT MARKING QUANTITIES

PA PAY ITEM LENGTH = 900 LF TOTAL QUANTITY = 1,800 LF
PI PAY ITEM LENGTH = 450 LF TOTAL QUANTITY = 1,800 LF

ROADWAY STANDARD DRAWINGS

1205.01 PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02 PAVEMENT MARKINGS - DIVIDED AND UNDIVIDED ROADWAYS
1261.01 GUARDRAIL AND BARRIER DELINEATOR SPACING
1261.02 GUARDRAIL AND BARRIER DELINEATOR TYPES
1262.01 GUARDRAIL END DELINEATION
1264.01 OBJECT MARKERS
1264.02 PLACEMENT OF OBJECT MARKERS



GENERAL NOTES

THE FOLLOWING NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD	MARKING	MARKER
SR 1103	PAINT	NONE

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.
D) STOP BAR LOCATIONS AT NON-SIGNALIZED INTERSECTIONS MAY BE ADJUSTED AS DIRECTED BY THE ENGINEER.
E) ALL PAVEMENT MARKINGS ARE EXISTING UNLESS OTHERWISE NOTED.
F) RELOCATE ALL EXISTING SIGNS AS REQUIRED BY THE ENGINEER.

APPROVED: DocuSigned by: Richard Odynski 6E04D032FEE446D...
DATE: 9/8/2017
SEAL

NORTH CAROLINA PROFESSIONAL SEAL 037467 ENGINEER RICHARD A ODYNSKI

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

wsp
1001 Morehead Square Dr.
Suite 610
Charlotte NC, 28203
NC LIC. NO. F-0165

PAVEMENT MARKING PLAN