COMPUTED BY: JDD	DATE: 4-15-15
CHECKED BY: WCC	DATE: 4-15-15

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	PROJECT REFERENCE NO.	SHEET NO.
	17BP.14.R.143	3-B

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SUMMARY OF EARTHWORK

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT+%	BORROW	WASTE
SUMMARY NO.1					
-L- STA. 14+25 TO STA. 15+66.56 (BEGIN BRIDGE)	26		63	37	
SUBTOTAL SUMMARY NO.1	26		63	37	
SUMMARY NO.2					
-L- STA. 16+14.16 (END BRIDGE) TO STA. 18+00	63		51		12
SUBTOTAL SUMMARY NO.2	63		51		12
PROJECT SUBTOTAL	89		114	37	12
WASTE IN LIEU OF BORROW				-12	-12
PROJECT TOTAL	89			25	
EST. 5% FOR REPLACING TOPSOIL ON BORROW PITS				1	
GRAND TOTAL	90		114	26	
SAY	95			30	

CONTINGENCY ITEMS:

INCIDENTAL STONE = 50 TONS

UNDERCUT EXCAVATION = 50 CY

SELECT GRANULAR MATERIAL = 50 CY

CLASS IV SUBGRADE STABILIZATION = 50 TONS

GEOTEXTILE FOR SOIL STABILIZATION = 50 SY

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the contract lump sum price for "grading".