DocuSign Envelope ID: 802A9456-4450-4837-B91F-6CECCC31086F

PROJ. REFERENCE NO.	SHEET NO.
14SP.20221.1/14SP.20221.2	PMP-1

PAVEMENT MARKING PLAN

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C. DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO LANE & MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES & MOUNTING
1262.01	GUARDRAIL END DELINEATION



FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PROJECT	QUANTITY BREAKDOWN	PAY ITEM	TOTAL QUANTITY
			PAVEMENT MARKING LINES		
PA	WHITE SOLID EDGE LINE	086	1300 FT	PAINT (4")	2600 FT
PI	YELLOW DOUBLE CENTER LINE	086	1300 FT	PAINT (4")	2600 FT
PA	WHITE SOLID EDGE LINE	087	1000 FT	PAINT (4")	2000 FT
PI	YELLOW DOUBLE CENTER LINE	087	1000 FT	PAINT (4")	2000 FT

SCALE: 1" = 50'

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A.) INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE

ROAD NAME:	MARKING
SR 1140 (MYERS CHAPEL ROAD)	PAINT

B.) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C.) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

V&M
Vaughn & Melton
Consulting Engineers
Asheville, North Carolina
828-253-2796
Charlotte, NC 704-357-0488
Boone, NC 828-355-9933
Tri-Cities, TN 423-467-8401
Knoxville, TN 865-546-5800
Spartanburg, SC 864-574-4775
Charleston, SC 843-974-5650
Middlesboro, KY 606-248-6600
Atlanta, GA 770-627-3509
Copyright © 2006 Vaughn & Melton, Inc. All Rights Reserved

APPROVED: DocuSigned by: Lloyd D. Wayne Brown DATE: 11/4/2016

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 20119 ENGINEER LLOYD D. BROWN

DIVISION OF HIGHWAYS · STATE OF NORTH CAROLINA · DEPARTMENT OF TRANSPORTATION · WORK ZONE TRAFFIC CONTROL

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PAVEMENT MARKING PLAN

11/4/2016
S:\Transportation\3j236-01MTC 14SP.20221.1Clay 86\Traffic\TrafficControl\TCP\BD-5114_086_087_PMP-1.dgn
User:cjmorrell