STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

ITEM	SECT	QUANTITY	UNIT	ITEM DESCRIPTION
1	800	1	LS	MOBILIZATION
2	801	1	LS	CONSTRUCTION SURVEYING
3	SP	1	LS	REINFORCED BRIDGE APPROACH FILL, -L- STA 13+68.50
4	226	1	LS	GRADING
5	226	200	CY	UNDERCUT EXCAVATION
6	300	60	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES
7	300	190	SY	FOUNDATION CONDITIONING GEOTEXTILE
8	310	556	LF	15" R.C. PIPE CULVERTS, CLASS IV
9	340	36	LF	PIPE REMOVAL
10	545	20	TON	INCIDENTAL STONE BASE
11	607	300	SY	MILLING ASPHALT PAVEMENT, 1.5" DEPTH (PAMLICO #9 BRIDGE DECK)
12	607	13,638	SY	MILLING ASPHALT PAVEMENT, 3" DEPTH
13	610	575	TON	ASPHALT CONCRETE BASE COURSE, TYPE B25.0B
14	610	1,672	TON	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B
15	610	4,466	TON	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B
16	620	375	TON	ASPHALT BINDER FOR PLANT MIX
17	840	11	EA	MASONRY DRAINAGE STRUCTURES
18	840	11	EA	FRAME WITH GRATE AND HOOD, STD 840.03
19	846	1,100	LF	2'-6" CONCRETE CURB AND GUTTER
20	848	280	SY	4" CONCRETE SIDEWALK
21	848	8	EA	CONCRETE CURB RAMPS
22	858	1	EA	ADJUSTMENT OF CATCH BASINS
23	862	15	LF	STEEL BEAM GUARDRAIL, SHOP CURVED
24	862	5	EA	ADDITIONAL GUARDRAIL POSTS
25	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
26	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
27	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
28	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE CAT-1
29	876	5	TON	RIP RAP, CLASS I
30	876	5	TON	RIP RAP, CLASS B
31	876	50	SY	GEOTEXTILE FOR DRAINAGE
32	1105	1	LS	TEMPORARY TRAFFIC CONTROL
33	SP	224	SF	WORK ZONE ADVANCE/ GENERAL WARNING SIGNING
34	1205	34,051	LF	PAINT PAVEMENT MARKING LINES, 4"
35	1205	300	LF	PAINT PAVEMENT MARKING LINES, 8"
36	1205	60	LF	PAINT PAVEMENT MARKING LINES, 24"
37	1205	6	EA	PAINT PAVEMENT MARKING SYMBOLS
38	1205	34,051	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
39	1205	300	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
40	1205	60	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
41	1205	6	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOLS, 90 MILS
42	1253	117	EA	SNOWPLOWABLE PAVEMENT MARKER
43	1605	1,300	LF	TEMPORARY SILT FENCE
44	1610	5	TON	STONE FOR EROSION CONTROL, CLASS B
45	1610	15	TON	SEDIMENT CONTROL STONE
46	1615	1	ACRE	TEMPORARY MULCHING
47	1620	50	LB	SEED FOR TEMPORARY SEEDING
48	1620	0.2	TON	FERTILIZER FOR TEMPORARY SEEDING
49	1622	200	LF	TEMPORARY SLOPE DRAINS
50	SP	300	LF	SAFETY FENCE
51	1630	15	CY	SILT EXCAVATION
52	1631	700	SY	MATTING FOR EROSION CONTROL
53	1632	440	LF	1/4" HARDWARE CLOTH
54	SP	300	SY	FLOATING TURBIDITY CURTAIN
55	SP	200	LF	WATTLE
56	1660	1	ACRE	SEEDING AND MULCHING
57	1661	50	LB	SEED FOR REPAIR SEEDING
58	1661	0.2	TON	FERTILIZER FOR REPAIR SEEDING
59	SP	1	LS	RELOCATE EXISTING 10" SANITARY SEWER MAIN
60	402	1	LS	REMOVAL OF EXISTING STRUCTURE AT -L- STA 13+68.50
61	450	2	EA	PDA TESTING
62	412	1	LS	UNCLASSIFIED STRUCTURE EXCAVATION
63	SP	3,139	SF	CONCRETE WEARING SURFACE
64	420	4,039	SF	GROOVING BRIDGE FLOORS
65	420	129.3	CY	CLASS AA CONCRETE (BRIDGE)
66	422	1	LS	BRIDGE APPROACH SLABS
67	425	11,806	LB	EPOXY COATED REINFORCING STEEL (BRIDGE)
68	450	960	LF	16" PRESTRESSED CONCRETE PILES
69	450	640	LF	24" PRESTRESSED CONCRETE PILES
70	450	320	LF	PREDRILLING FOR PILES
71	450	10	EA	PILE REDRIVES
72	876	124	TON	RIP RAP, CLASS II (2'-0" THICK)
73	876	138	SY	GEOTEXTILE FOR DRAINAGE
74	430	1	LS	ELASTOMETRIC BEARINGS
75	430	1540	LF	3'-0" X 2'-0" PRESTRESSED CONCRETE CORED SLABS
76	SP	1	LS	AESTHETIC LIGHTING
77	SP	307.67	LF	DECORATIVE METAL RAIL & CONCRETE PARAPET

REVISIONS

8/17/99

08-DEC-2014 13:56
S:\PROJECTS\B-5129A_PAMLICO\pamlico#24 (B-5129A)\B-5129A_DDC2_PSH_3.dgn
$$USERNAME$$