PROJECT REFERENCE NO.	SHEET NO.
B-5129A	UC2

UTILITIES ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 16710 ENGINEER DWAYNE H. ALLIGOOD

DocuSigned by: Dwayne Alligood 12/8/2014
E7E42C259C374D1...

UTILITY CONSTRUCTION

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

SANITARY SEWER FORCE MAIN	QUANTITY	UNIT	ITEM DESCRIPTION
	24	LF	6" DI PIPE - PC 350 (AWWA C151)
	115	LF	10" DI PIPE - PC 350 (AWWA C151)
	435	LF	12" HDPE PIPE - DR9 (AWWA C906)
	2	EA	10" GATE VALVE AND VALVE BOX
	2	EA	DI PIPE TO HDPE TRANSITION
	2	EA	DI PIPE TO PVC TRANSITION
	2	EA	CONCRETE THRUST COLLAR
	4	EA	6" DI 45° ELBOW WITH RESTRAINED JOINTS
	6	EA	10" DI 45° ELBOW WITH RESTRAINED JOINTS
	2	EA	2" AIR RELEASE VALVE
	23	LF	REMOVE 6" UTILITY PIPE
	533	LF	ABANDON/REMOVE 10" UTILITY PIPE
	300	LF	TEMPORARY SILT FENCE
	0.2	ACRES	SEEDING AND MULCHING

REVISIONS

8/17/99

08-DEC-2014 13:56
C:\PROJECTS\B5129A\ICO\pamlico#24 (B-5129A)\B-5129A_DDC2_PSH_UC2.DGN
$$$$USERNAME$$$$