COMPUTED BY: LJ DATE: 3-15-11
CHECKED BY: VT DATE: 3-15-11

PROJECT REFERENCE NO.	SHEET NO.
B-5129A	3B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF EARTHWORK
IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT+%	BORROW	WASTE
–L– 10+03.10 – 13+12.31	101		531	430	
–L– 14+23.50 – 17+00.00	13		896	883	
STRUCTURE EXCAVATION	330				330
UNDERCUT (CONTINGENCY)		200	240	240	200
TOTAL	444	200	1667	1553	530
SAY	450	200	1670	1560	530

PAVEMENT REMOVAL SUMMARY
IN SQUARE YARDS

LINE	STATION – STATION	LOCATION	REMOVAL (SY)
–L–	10+00.00 – 13+33.47	CL	1218
–L–	14+02.65 – 17+45.00	CL	1233
TOTAL			2451
		SAY	2460

NOTE:

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, STRUCTURE EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING."

4/24/06
08-DEC-2014 13:56
G:\PROJECTS\PAMLICO\pamlico*24 (B-5129A\B-5129A_DOC2_PSH_3B.dgn
$$$$USERNAME$$$$