



PAT McCRORY
Governor

NICHOLAS J. TENNYSON
Secretary

January 25, 2016

CONTRACT: DB00272
WBS ELEMENT: 2016CPT.02.33.20522.1
COUNTY: Jones
ROUTE: Various
DESCRIPTION: Crack Sealing Six SRs in Jones County

ADDENDUM 1

TO: PROSPECTIVE BIDDERS

Please note the following revision to the proposal for the above referenced project.

- Change of Special Provision “SEALING EXISTING PAVEMENT CRACKS AND JOINTS” to the attached Special Provision.
- Change of Line item 1 “SEALING EXISTING PAVEMENT CRACKS & JOINTS” quantity of 52,320 LB to “GENERIC MISCELLANEOUS ITEM SEALING PVMT CRACKS & JTS > RATE 1200 LBS/20’ RD MILE” quantity 49,020 LB. See attached revised list of bid items.
- See the attached updated list of Jones County Secondary Crack Seal Routes.

If electing to use the Computer Bid Preparation process, the Expedite File has been updated to reflect these revisions. Please download the Expedite Addendum File and follow the instructions for applying the addendum.


The Contractor’s bid must be based on these revised pay item quantities. The contract will be prepared accordingly.

Sincerely,

A handwritten signature in black ink, appearing to read 'Sarah Lentine'.

Sarah Lentine
Division Contract Officer

cc: Mr. Ed Eatmon, PE
Mr. Aaron Bullard, PE



SEALING EXISTING PAVEMENT CRACKS AND JOINTS:

Sealing of existing longitudinal and transverse pavement cracks and joints with hot applied joint sealer shall be performed in accordance with Section 657 of the Standard Specifications. Materials shall conform to Article 1028-2 of the Standard Specifications.

The bid quantities are approximate only and are to be used solely for the comparison of bids.

Measurement and Payment

Sealing Existing Pavement Cracks and Joints will be measured and paid at the contract unit price per pound for the appropriate rate. The appropriate rate will be determined on a per 20' Road Mile basis. Payment will be made only for the actual quantity of material satisfactorily placed.

Such prices shall include, but not be limited to, furnishing all labor, materials, tools, equipment, and other incidentals necessary to perform the required work.

Payment will be made under:

Pay Item	Pay Unit
SEALING PVMT CRACKS & JTS > RATE 1200 LBS/20' RD MILE	LBS
SEALING PVMT CRACKS & JTS RATE OF 1200 LBS/20' RD MILE OR LESS	LBS

County : Jones

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
--------	-------------	-------	-------------	----------	-----------	--------

ROADWAY ITEMS

0001	0000940000-E	SP	GENERIC MISCELLANEOUS ITEM SEALING PVMT CRACKS & JTS > RATE 1200 LBS/20' RD MILE	49,020 LB		
------	--------------	----	--	--------------	--	--

1233/Jan25/Q49020.0/D940000/E1

Total Amount Of Bid For Entire Project :

Jones County Secondary Crack Seal Routes

County	Map	WBS	Route Name	Route Number	From	To	Length	Number of Lanes	Transverse & Alligator Cracking	PS/LBS
Jones	1	2016CPT.02.33.20522.1	Kingfield	1320	NC 1002	NC 41	2.90	2	Severe	8,700
Jones	2	2016CPT.02.33.20522.1	Simmons Loop	1330	US 17	US 17	6.40	2	Mild	15,360
Jones	3	2016CPT.02.33.20522.1	Spann	1327	NC 58	NC 58	3.30	2	Low	5,940
Jones	4	2016CPT.02.33.20522.1	Mary Tate	1147	1146	Duplin Co Line	4.00	2	Low	7,200
Jones	5	2016CPT.02.33.20522.1	Watering Pond	1146	Lenoir Co Line	Onslow Co Line	4.10	2	Mild	9,840
Jones	6	2016CPT.02.33.20522.1	Potters Hill	1148	Lenoir Co Line	Duplin Co Line	1.10	2	Low	1,980
Total Miles							21.8	Total Material =		49,020