PROJECT NO.	SHEET NO.	TOTAL NO.
NC 123	5	5
2CR.10401.13		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TON	SHOULDER RECONSTRUCTION SMI	BASE COURSE, B25.0B TONS	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TON	SEED & MULCHING AC
NC 123	Greene	1	NC 123	WIDEN 3" ES STRENGTHEN AND RESURFACE	1	2	2WU	NO	NO	2.78	26	60	5.56	3,072	6,274	3,686	657	11.00
TOTAL FOR MAP NO. 1										**2.78**		**60**	**5.56**	**3,072**	**6,274**	**3,686**	**657**	**11.00**
TOTAL FOR PROJ NO. NC 123										**2.78**		**60**	**5.56**	**3,072**	**6,274**	**3,686**	**657**	**11.00**
GRAND TOTAL										**2.78**		**60**	**5.56**	**3,072**	**6,274**	**3,686**	**657**	**11.00**