PROJECT NO.	SHEET NO.	TOTAL NO.
2CR.20541.10	4	4

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	SURFACE COURSE, SF9.5A TONS	SURFACE COURSE, S4.75A TONS	ASPHALT BINDER FOR PLANT MIX TONS	ADJ. OF METER OR VALVE BOX EA	SEED & MULCHING AC
2CR.20541.10	Lenoir	1	SR 1621 - TOMLYN DRIVE	FROM SR 1544 TO SR 1622	1	2		NO	NO	0.241	23		0.46	340		23	1	0.112
TOTAL FOR MAP NO. 1										**0.241**			**0.46**	**340**		**23**	**1**	**0.112**
2CR.20541.10	Lenoir	2	SR 1622 - FORREST DRIVE	FROM SR 1621 TO SR 1644	1	2		NO	NO	0.799	22		1.45	1,101		74	2	0.352
TOTAL FOR MAP NO. 2										**0.799**			**1.45**	**1,101**		**74**	**2**	**0.352**
2CR.20541.10	Lenoir	3	SR 1644 - DOGWOOD LANE	FROM SR 1622 TO SR 1622	1	2		NO	NO	1.49	20		2.75	1,831		123	2	0.667
TOTAL FOR MAP NO. 3										**1.49**			**2.75**	**1,831**		**123**	**2**	**0.667**
2CR.20541.10	Lenoir	4	SR 1648 - BRINSON STREET	FROM SR 1622 TO SR 1649	2	2		NO	NO	0.084	20		0.16		53	4		0.039
TOTAL FOR MAP NO. 4										**0.084**			**0.16**		**53**	**4**		**0.039**
2CR.20541.10	Lenoir	5	SR 1649 - ENGLISH SQUIRE DRIVE	FROM SR 1644 TO DEAD END	2	2		NO	NO	0.434	20		0.86		206	14		0.208
TOTAL FOR MAP NO. 5										**0.434**			**0.86**		**206**	**14**		**0.208**
2CR.20541.10	Lenoir	6	SR 1650 - PINE KNOLL DRIVE	FROM SR 1644 TO SR 1649	2	2		NO	NO	0.305	20		0.54		163	11	5	0.131
TOTAL FOR MAP NO. 6										**0.305**			**0.54**		**163**	**11**	**5**	**0.131**
2CR.20541.10	Lenoir	7	SR 1654 - IRVIN DRIVE	FROM SR 1644 TO SR 1649	2	2		NO	NO	0.353	20		0.62		187	13	4	0.150
TOTAL FOR MAP NO. 7										**0.353**			**0.62**		**187**	**13**	**4**	**0.150**
2CR.20541.10	Lenoir	8	SR 1684 - PINERIDGE ROAD	FROM SR 1644 TO SR 1691	2	2		NO	NO	0.269	20		0.48		145	10	2	0.116
TOTAL FOR MAP NO. 8										**0.269**			**0.48**		**145**	**10**	**2**	**0.116**
2CR.20541.10	Lenoir	9	SR 1692 - ACORN CIRCLE	FROM SR 1644 TO DEAD END	2	2		NO	NO	0.041	20		0.07		46	3		0.017
TOTAL FOR MAP NO. 9										**0.041**			**0.07**		**46**	**3**		**0.017**
2CR.20541.10	Lenoir	10	SR 1683 - NORTHRIDGE PLACE	FROM SR 1644 TO SR 1684	2	2		NO	NO	0.164	20		0.30		87	6		0.073
TOTAL FOR MAP NO. 10										**0.164**			**0.3**		**87**	**6**		**0.073**
2CR.20541.10	Lenoir	11	SR 1691 - PRIMROSE ROAD	FROM SR 1644 TO SR 1684	2	2		NO	NO	0.167	19		0.31		85	6	2	0.075
TOTAL FOR MAP NO. 11										**0.167**			**0.31**		**85**	**6**	**2**	**0.075**
TOTAL FOR PROJ NO. 2CR.20541.10										**4.347**			**8.00**	**3,272**	**972**	**287**	**18**	**1.939**
GRAND TOTAL										**4.347**		**100**	**8.00**	**3,272**	**972**	**287**	**18**	**1.939**