PROJECT REFERENCE NO.	SHEET NO.
BD-5102Z	3

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

ITEM	SECT	QUANTITY	UNIT	ITEM DESCRIPTION
1	800	1	LS	MOBILIZATION
2	801	1	LS	CONSTRUCTION SURVEYING
3	SP	1	LS	REINFORCED BRIDGE APPROACH FILL, -L- STA 16+09.43
4	226	1	LS	GRADING
5	226	200	CY	UNDERCUT EXCAVATION
6	300	50	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES
7	300	140	SY	FOUNDATION CONDITIONING GEOTEXTILE
8	305	148	LF	24" DRAINAGE PIPE
9	305	148	LF	42" DRAINAGE PIPE
10	310	100	LF	15" R.C. PIPE CULVERTS, CLASS IV
11	520	870	TON	AGGREGATE BASE COURSE
12	610	300	TON	ASPHALT CONCRETE BASE COURSE, TYPE B25.0B
13	610	330	TON	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B
14	610	375	TON	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5A
15	620	55	TON	ASPHALT BINDER FOR PLANT MIX
16	840	4	EA	MASONRY DRAINAGE STRUCTURES
17	840	4	EA	FRAME WITH GRATE, STD 840.29
18	846	188	LF	SHOULDER BERM GUTTER
19	862	25	LF	STEEL BEAM GUARDRAIL
20	862	10	EA	ADDITIONAL GUARDRAIL POSTS
21	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
22	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
23	876	5	TON	RIP RAP, CLASS I
24	876	5	TON	RIP RAP, CLASS B
25	876	14	SY	GEOTEXTILE FOR DRAINAGE
26	1605	1500	LF	TEMPORARY SILT FENCE
27	1610	5	TON	STONE FOR EROSION CONTROL, CLASS B
28	1610	5	TON	SEDIMENT CONTROL STONE
29	1615	1	ACRE	TEMPORARY MULCHING
30	1620	50	LB	SEED FOR TEMPORARY SEEDING
31	1620	0.2	TON	FERTILIZER FOR TEMPORARY SEEDING
32	1622	200	LF	TEMPORARY SLOPE DRAINS

ITEM	SECT	QUANTITY	UNIT	ITEM DESCRIPTION
33	SP	550	LF	SAFETY FENCE
34	1630	10	CY	SILT EXCAVATION
35	1631	1400	SY	MATTING FOR EROSION CONTROL
36	1632	140	LF	1/4" HARDWARE CLOTH
37	SP	150	SY	FLOATING TURBIDITY CURTAIN
38	SP	320	LF	WATTLE
39	SP	1	LB	POLYACRYLAMIDE (PAM)
40	1660	1	ACRE	SEEDING AND MULCHING
41	1661	50	LB	SEED FOR REPAIR SEEDING
42	1661	0.2	TON	FERTILIZER FOR REPAIR SEEDING
43	402	1	LS	REMOVAL OF EXISTING STRUCTURE AT -L- STA 16+09.43
44	412	1	LS	UNCLASSIFIED STRUCTURE EXCAVATION
45	SP	1	EA	PDA TESTING
46	420	56.0	CY	CLASS A CONCRETE (BRIDGE)
47	422	1	LS	BRIDGE APPROACH SLABS
48	425	8922	LB	REINFORCING STEEL (BRIDGE)
49	450	800	LF	HP 12 X 53 STEEL PILES
50	450	10	EA	STEEL PILE POINTS
51	450	6	EA	PILE REDRIVES
52	SP	190	LF	VERTICAL CONCRETE BARRIER RAIL
53	876	174	TON	RIP RAP, CLASS II (2'-0" THICK)
54	876	194	SY	GEOTEXTILE FOR DRAINAGE
55	430	1	LS	ELASTOMETRIC BEARINGS
56	430	950	LF	3'-0" X 3'-3" PRESTRESSED CONCRETE BOX BEAMS

REVISIONS

8/17/99

10-NOV-2015 11:00
C:\pwworking\ctt\ctt20\BD5102Z_ddc2_psh_3.dgn
$$$$USERNAME$$$$