

BP2.R022.3

TIP NO

0.054 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 240043 OVER SWIFT CREEK ON SR 1465 (BEAVER DAM ROAD)

				SANFORD CONTRACTORS INC		T A LOVING COMPANY		BIRDSALL EXCAVATION AND CONSTRUCTIO		
				LEMON SPRINGS, NC		GOLDSBORO, NC		CLARKSVILLE, NY		
ROADWAY ITEMS										
0001	0000100000-N	800	MOBILIZATION	Lump Sum		74,050.00	75,000.00		60,000.00	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		16,975.00	10,000.00		25,000.00	
0003	0036000000-E	225	UNDERCUT EXCAVATION	300 CY	0.01	3.00	0.01	3.00	16.00	4,800.00
0004	0043000000-N	226	GRADING (226)	Lump Sum		124,250.00	145,368.08		124,000.00	
0005	0050000000-E	226	SUPP CLEARING & GRUBBING	1 ACR	0.01	0.01	0.01	0.01	5,000.00	5,000.00
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY	0.01	3.00	0.01	3.00	38.00	11,400.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	300 SY	0.01	3.00	0.01	3.00	5.50	1,650.00
0008	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE I MODIFIED APPROACH FILL -L- STA. 13+88.00	Lump Sum		27,100.00	30,000.00		58,000.00	
0009	0318000000-E	300	FND CONDIT MATL MINOR STRS	20 TON	40.00	800.00	60.00	1,200.00	75.00	1,500.00
0010	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	60 SY	3.75	225.00	2.00	120.00	7.00	420.00
0011	0335000000-E	305	*** DRAINAGE PIPE (60")	80 LF	283.68	22,694.40	257.00	20,560.00	150.00	12,000.00
0012	0335200000-E	305	15" DRAINAGE PIPE	28 LF	18.36	514.08	16.00	448.00	68.00	1,904.00
0013	0335700000-E	305	42" DRAINAGE PIPE	64 LF	268.74	17,199.36	140.00	8,960.00	115.00	7,360.00
0014	0995000000-E	340	PIPE REMOVAL	101 LF	5.00	505.00	15.00	1,515.00	30.00	3,030.00
0015	1308000000-E	607	MILLN ASPHALT PVMT ***** - ***** (0" TO 1.5")	230 SY	18.00	4,140.00	18.00	4,140.00	14.00	3,220.00
0016	1491000000-E	610	ASP CONC BASE CRS B25.0C	110 TON	128.00	14,080.00	128.00	14,080.00	155.00	17,050.00
0017	1519000000-E	610	ASP CONC SURF CRS S9.5B	230 TON	132.00	30,360.00	132.00	30,360.00	155.00	35,650.00
0018	1575000000-E	620	ASP FOR PLANT MIX	20 TON	585.00	11,700.00	585.00	11,700.00	725.00	14,500.00
0019	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY	0.01	0.45	0.01	0.45	36.00	1,612.80
0020	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200 SY	0.01	2.00	0.01	2.00	4.50	900.00
0021	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6 CY	0.01	0.34	0.01	0.34	90.00	3,024.00
0022	2044000000-E	815	6" PERF SUBDRN PIPE	200 LF	0.01	2.00	0.01	2.00	24.00	4,800.00
0023	2070000000-N	815	SUBDRN PIPE OUTLET	1 EA	0.01	0.01	0.01	0.01	1,000.00	1,000.00
0024	2077000000-E	815	6" OUTLET PIPE	6 LF	0.01	0.06	0.01	0.06	30.00	180.00
0025	2220000000-E	838	REINFORCED ENDWALLS	5.6 CY	2,311.96	12,946.98	1,100.00	6,160.00	2,200.00	12,320.00
0026	2286000000-N	840	MASNRY DRAINAGE STRUCT	1 EA	2,996.00	2,996.00	1,200.00	1,200.00	5,800.00	5,800.00
0027	2367000000-N	840	FRAME W/2GRTS 840.29 STD	1 EA	494.10	494.10	550.00	550.00	2,200.00	2,200.00
0028	2556000000-E	846	SHOULDER BERM GUTTER	60 LF	50.47	3,028.20	60.00	3,600.00	65.00	3,900.00
0029	2570000000-N	SP	MODIFIED CONCRETE FLUME	3 EA	2,750.60	8,251.80	2,000.00	6,000.00	3,500.00	10,500.00
0030	3030000000-E	862	STL BEAM GUARDRAIL	62.5 LF	25.00	1,562.50	25.00	1,562.50	38.00	2,375.00
0031	3045000000-E	862	SBGR SHOP CURVED	62.5 LF	28.00	1,750.00	28.00	1,750.00	85.00	5,312.50
0032	3150000000-N	862	ADDIT GUARDRAIL POSTS	5 EA	11.00	55.00	11.00	55.00	200.00	1,000.00
0033	3195000000-N	862	GR END TYPE AT-1	2 EA	1,150.00	2,300.00	1,150.00	2,300.00	3,500.00	7,000.00
0034	3215000000-N	862	GR ANCHOR TYPE III	4 EA	2,550.00	10,200.00	2,550.00	10,200.00	4,000.00	16,000.00
0035	3287000000-N	862	GR END TYPE TL-3	2 EA	3,350.00	6,700.00	3,350.00	6,700.00	4,000.00	8,000.00
0036	3578000000-N	SP	GENERIC FENCING ITEM (EA) GATE RESET	2 EA	500.00	1,000.00	2,800.00	5,600.00	600.00	1,200.00
0037	3649000000-E	876	RIP RAP, CLASS B	4 TON	235.00	940.00	54.00	216.00	100.00	400.00

BP2.R022.3

TIP NO

0.054 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 240043 OVER SWIFT CREEK ON SR 1465 (BEAVER DAM ROAD)

		SANFORD CONTRACTORS INC				T A LOVING COMPANY			BIRDSALL EXCAVATION AND CONSTRUCTIO		
		LEMON SPRINGS, NC				GOLDSBORO, NC			CLARKSVILLE, NY		
0038	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	245	SY	3.75	918.75	2.00	490.00	4.00	980.00
0039	4400000000-E	1110	WORK ZONE SIGNS (STAT)	324	SF	8.10	2,624.40	7.25	2,349.00	16.00	5,184.00
0040	4410000000-E	1110	WORK ZONE SIGNS (BARR)	94	SF	8.55	803.70	8.85	831.90	24.00	2,256.00
0041	4420000000-N	1120	PORTABLE CHANGE MSG SIGN	2	EA	4,860.00	9,720.00	3,200.00	6,400.00	5,500.00	11,000.00
0042	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	22.50	1,440.00	25.00	1,600.00	40.00	2,560.00
0043	6000000000-E	1605	TEMPORARY SILT FENCE	1,560	LF	3.25	5,070.00	3.44	5,366.40	4.20	6,552.00
0044	6006000000-E	1610	EROS CONTRL STONE CL A	75	TON	47.00	3,525.00	73.45	5,508.75	68.00	5,100.00
0045	6009000000-E	1610	EROS CONTRL STONE CL B	5	TON	188.00	940.00	54.00	270.00	85.00	425.00
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	10	TON	80.00	800.00	57.35	573.50	80.00	800.00
0047	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	2,500.00	1,250.00	1,850.00	925.00	2,400.00	1,200.00
0048	6018000000-E	1620	SEED FOR TEMP SEEDING	100	LB	5.00	500.00	2.00	200.00	6.50	650.00
0049	6021000000-E	1620	FERT FOR TEMP SEEDING	0.5	TON	900.00	450.00	1,092.00	546.00	800.00	400.00
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	0.01	2.00	1.00	200.00	22.00	4,400.00
0051	6029000000-E	SP	SAFETY FENCE	260	LF	2.00	520.00	2.85	741.00	6.50	1,690.00
0052	6030000000-E	1630	SILT EXCAVATION	10	CY	0.01	0.10	5.00	50.00	35.00	350.00
0053	6036000000-E	1631	MATTING FOR EROS CONTROL	1,500	SY	2.00	3,000.00	1.99	2,985.00	2.15	3,225.00
0054	6037000000-E	1629	COIR FIBER MAT	100	SY	6.50	650.00	4.36	436.00	6.50	650.00
0055	6042000000-E	1632	1/4" HARDWARE CLOTH	35	LF	6.00	210.00	3.75	131.25	34.00	1,190.00
0056	6048000000-E	SP	FLOAT TURBIDITY CURTAIN	675	SY	12.84	8,667.00	26.69	18,015.75	28.00	18,900.00
0057	6071012000-E	1642	COIR FIBER WATTLE	170	LF	14.00	2,380.00	14.50	2,465.00	10.50	1,785.00
0058	6084000000-E	1660	SEEDING AND MULCHING	0.5	ACR	6,000.00	3,000.00	4,950.00	2,475.00	4,200.00	2,100.00
0059	6087000000-E	1660	MOWING	0.5	ACR	250.00	125.00	295.00	147.50	3,000.00	1,500.00
0060	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	6.00	300.00	4.15	207.50	7.50	375.00
0061	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	600.00	150.00	1,092.00	273.00	850.00	212.50
0062	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	6.00	300.00	4.98	249.00	7.50	375.00
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25	TON	600.00	150.00	1,092.00	273.00	850.00	212.50
0064	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	55.00	550.00	75.00	750.00	95.00	950.00
0065	6117000000-N	1675	RESPONSE FOR EROS CONTROL	25	EA	0.01	0.25	10.00	250.00	225.00	5,625.00
0066	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	428.00	428.00	1,000.00	1,000.00	1,600.00	1,600.00
0067	6123000000-E	1670	REFORESTATION	0.1	ACR	8,900.00	890.00	4,400.00	440.00	4,500.00	450.00
0068	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	3	EA	428.00	1,284.00	1,000.00	3,000.00	2,000.00	6,000.00
STRUCTURE ITEMS											
0069	8035000000-N	402	REMV EXIST STR ***** BRG (402) (13+88.00 -L-)	Lump Sum			81,525.00		85,000.00		60,000.00
0070	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			2,500.00		2,000.00		2,500.00
0071	8121000000-N	412	UNCL STR EXCAV STA ***** (13+88.00 -L-)	Lump Sum			3,500.00		1,000.00		65,000.00
0072	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	59	CY	2,900.00	171,100.00	3,000.00	177,000.00	1,850.00	109,150.00
0073	8210000000-N	422	BRG APPR SLAB ***** (13+05.88 -L-, 14+70.13 -L-)	Lump Sum			56,000.00		50,000.00		95,000.00
0074	8217000000-E	425	REINF STEEL (BRIDGE)	8,798	LB	1.20	10,557.60	1.00	8,798.00	2.10	18,475.80

BP2.R022.3

TIP NO

0.054 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 240043 OVER SWIFT CREEK ON SR 1465 (BEAVER DAM ROAD)

				SANFORD CONTRACTORS INC		T A LOVING COMPANY		BIRDSALL EXCAVATION AND CONSTRUCTIO			
				LEMON SPRINGS, NC		GOLDSBORO, NC		CLARKSVILLE, NY			
0075	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES (HP 12 X 53)	10	EA	4,368.00	43,680.00	4,500.00	45,000.00	3,000.00	30,000.00
0076	8328400000-E	450	PILE DRV EQUIP SETUP ** GALV STEEL PILES (PP 18 X 0.50)	14	EA	5,472.00	76,608.00	6,000.00	84,000.00	3,500.00	49,000.00
0077	8364000000-E	450	HP12X53 PILES	600	LF	46.12	27,672.00	45.00	27,000.00	90.00	54,000.00
0078	8387000000-E	450	PP18X0.50 GALV STL PILE	1,260	LF	103.56	130,485.60	110.00	138,600.00	145.00	182,700.00
0079	8391000000-N	450	STEEL PILE POINTS	7	EA	545.70	3,819.90	700.00	4,900.00	900.00	6,300.00
0080	8394000000-N	450	DYNAMIC PILE TESTING	2	EA	2,500.00	5,000.00	3,000.00	6,000.00	16,000.00	32,000.00
0081	8505000000-E	460	VERT CONC BARRIER RAIL	280.51	LF	191.00	53,577.41	200.00	56,102.00	210.00	58,907.10
0082	8608000000-E	876	RIP RAP II (2'-0")	180	TON	55.50	9,990.00	115.00	20,700.00	95.00	17,100.00
0083	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	196	SY	3.75	735.00	2.00	392.00	4.00	784.00
0084	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			5,370.00		6,000.00		9,000.00
0085	8763000000-E	430	3'-0" X 2'-0"PRESTR SLABS	1,400	LF	251.00	351,400.00	240.00	336,000.00	278.50	389,900.00
		CONTRACT TOTAL		TOTAL		1,481,000.00	TOTAL	1,507,000.00	TOTAL	1,742,522.20	
		ROADWAY ITEMS		SUB-TOTAL		447,479.49	SUB-TOTAL	458,508.00	SUB-TOTAL	562,705.30	
		STRUCTURE ITEMS		SUB-TOTAL		1,033,520.51	SUB-TOTAL	1,048,492.00	SUB-TOTAL	1,179,816.90	

BP2.R022.3

TIP NO

0.054 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 240043 OVER SWIFT CREEK ON SR 1465 (BEAVER DAM ROAD)

				S T WOOTEN CORPORATION WILSON, NC			TRADER CONSTRUCTION CO NEW BERN, NC		
ROADWAY ITEMS									
0001	0000100000-N	800	MOBILIZATION	Lump Sum		90,000.00		90,000.00	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		22,500.00		14,000.00	
0003	0036000000-E	225	UNDERCUT EXCAVATION	300	CY	5.00	1,500.00	55.00	16,500.00
0004	0043000000-N	226	GRADING (226)	Lump Sum		80,000.00		132,000.00	
0005	0050000000-E	226	SUPP CLEARING & GRUBBING	1	ACR	1.00	1.00	1,000.00	1,000.00
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	300	CY	10.00	3,000.00	55.00	16,500.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	300	SY	1.00	300.00	4.75	1,425.00
0008	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE I MODIFIED APPROACH FILL -L- STA. 13+88.00	Lump Sum		18,000.00		25,000.00	
0009	0318000000-E	300	FND CONDIT MATL MINOR STRS	20	TON	90.00	1,800.00	75.00	1,500.00
0010	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	60	SY	1.00	60.00	5.75	345.00
0011	0335000000-E	305	*** DRAINAGE PIPE (60")	80	LF	520.00	41,600.00	550.00	44,000.00
0012	0335200000-E	305	15" DRAINAGE PIPE	28	LF	180.00	5,040.00	107.00	2,996.00
0013	0335700000-E	305	42" DRAINAGE PIPE	64	LF	300.00	19,200.00	320.00	20,480.00
0014	0995000000-E	340	PIPE REMOVAL	101	LF	10.00	1,010.00	25.00	2,525.00
0015	1308000000-E	607	MILLN ASPHALT PVMT ***** - ***** (0" TO 1.5")	230	SY	12.00	2,760.00	20.00	4,600.00
0016	1491000000-E	610	ASP CONC BASE CRS B25.0C	110	TON	250.00	27,500.00	140.00	15,400.00
0017	1519000000-E	610	ASP CONC SURF CRS S9.5B	230	TON	155.00	35,650.00	145.00	33,350.00
0018	1575000000-E	620	ASP FOR PLANT MIX	20	TON	500.00	10,000.00	645.00	12,900.00
0019	2022000000-E	815	SUBDRAIN EXCAVATION	44.8	CY	5.00	224.00	12.00	537.60
0020	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200	SY	1.00	200.00	3.50	700.00
0021	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6	CY	10.00	336.00	100.00	3,360.00
0022	2044000000-E	815	6" PERF SUBDRN PIPE	200	LF	5.00	1,000.00	6.00	1,200.00
0023	2070000000-N	815	SUBDRN PIPE OUTLET	1	EA	150.00	150.00	350.00	350.00
0024	2077000000-E	815	6" OUTLET PIPE	6	LF	5.00	30.00	20.00	120.00
0025	2220000000-E	838	REINFORCED ENDWALLS	5.6	CY	2,850.00	15,960.00	1,735.00	9,716.00
0026	2286000000-N	840	MASNRY DRAINAGE STRUCT	1	EA	6,000.00	6,000.00	6,250.00	6,250.00
0027	2367000000-N	840	FRAME W/2GRTS 840.29 STD	1	EA	1,600.00	1,600.00	695.00	695.00
0028	2556000000-E	846	SHOULDER BERM GUTTER	60	LF	65.00	3,900.00	115.00	6,900.00
0029	2570000000-N	SP	MODIFIED CONCRETE FLUME	3	EA	4,800.00	14,400.00	4,800.00	14,400.00
0030	3030000000-E	862	STL BEAM GUARDRAIL	62.5	LF	25.00	1,562.50	25.00	1,562.50
0031	3045000000-E	862	SBGR SHOP CURVED	62.5	LF	28.00	1,750.00	28.00	1,750.00
0032	3150000000-N	862	ADDIT GUARDRAIL POSTS	5	EA	11.00	55.00	11.00	55.00
0033	3195000000-N	862	GR END TYPE AT-1	2	EA	1,150.00	2,300.00	1,150.00	2,300.00
0034	3215000000-N	862	GR ANCHOR TYPE III	4	EA	2,550.00	10,200.00	2,550.00	10,200.00
0035	3287000000-N	862	GR END TYPE TL-3	2	EA	3,350.00	6,700.00	3,350.00	6,700.00
0036	3578000000-N	SP	GENERIC FENCING ITEM (EA) GATE RESET	2	EA	2,800.00	5,600.00	2,000.00	4,000.00
0037	3649000000-E	876	RIP RAP, CLASS B	4	TON	200.00	800.00	205.00	820.00
0038	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	245	SY	1.00	245.00	4.75	1,163.75

BP2.R022.3

TIP NO

0.054 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 240043 OVER SWIFT CREEK ON SR 1465 (BEAVER DAM ROAD)

				S T WOOTEN CORPORATION WILSON, NC			TRADER CONSTRUCTION CO NEW BERN, NC		
0039	4400000000-E	1110	WORK ZONE SIGNS (STAT)	324	SF	7.25	2,349.00	7.50	2,430.00
0040	4410000000-E	1110	WORK ZONE SIGNS (BARR)	94	SF	8.85	831.90	9.00	846.00
0041	4420000000-N	1120	PORTABLE CHANGE MSG SIGN	2	EA	10,500.00	21,000.00	5,300.00	10,600.00
0042	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	25.00	1,600.00	25.00	1,600.00
0043	6000000000-E	1605	TEMPORARY SILT FENCE	1,560	LF	4.27	6,661.20	3.25	5,070.00
0044	6006000000-E	1610	EROS CONTRL STONE CL A	75	TON	100.00	7,500.00	130.00	9,750.00
0045	6009000000-E	1610	EROS CONTRL STONE CL B	5	TON	200.00	1,000.00	120.00	600.00
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	10	TON	150.00	1,500.00	85.00	850.00
0047	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	1,500.00	750.00	2,500.00	1,250.00
0048	6018000000-E	1620	SEED FOR TEMP SEEDING	100	LB	3.00	300.00	5.00	500.00
0049	6021000000-E	1620	FERT FOR TEMP SEEDING	0.5	TON	760.00	380.00	900.00	450.00
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	5.00	1,000.00	30.00	6,000.00
0051	6029000000-E	SP	SAFETY FENCE	260	LF	2.97	772.20	2.00	520.00
0052	6030000000-E	1630	SILT EXCAVATION	10	CY	10.00	100.00	50.00	500.00
0053	6036000000-E	1631	MATTING FOR EROS CONTROL	1,500	SY	2.50	3,750.00	2.00	3,000.00
0054	6037000000-E	1629	COIR FIBER MAT	100	SY	3.78	378.00	6.50	650.00
0055	6042000000-E	1632	1/4" HARDWARE CLOTH	35	LF	3.55	124.25	6.00	210.00
0056	6048000000-E	SP	FLOAT TURBIDITY CURTAIN	675	SY	20.00	13,500.00	40.00	27,000.00
0057	6071012000-E	1642	COIR FIBER WATTLE	170	LF	17.00	2,890.00	14.00	2,380.00
0058	6084000000-E	1660	SEEDING AND MULCHING	0.5	ACR	4,250.00	2,125.00	6,000.00	3,000.00
0059	6087000000-E	1660	MOWING	0.5	ACR	750.00	375.00	250.00	125.00
0060	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	3.00	150.00	6.00	300.00
0061	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	760.00	190.00	600.00	150.00
0062	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	3.00	150.00	6.00	300.00
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25	TON	760.00	190.00	600.00	150.00
0064	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	100.00	1,000.00	55.00	550.00
0065	6117000000-N	1675	RESPONSE FOR EROS CONTROL	25	EA	5.00	125.00	500.00	12,500.00
0066	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	1,500.00	1,500.00	1,750.00	1,750.00
0067	6123000000-E	1670	REFORESTATION	0.1	ACR	15,000.00	1,500.00	8,900.00	890.00
0068	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	3	EA	1,500.00	4,500.00	1,750.00	5,250.00
STRUCTURE ITEMS									
0069	8035000000-N	402	REMOV EXIST STR ***** BRG (402) (13+88.00 -L-)	Lump Sum			220,000.00		135,000.00
0070	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			1,000.00		2,500.00
0071	8121000000-N	412	UNCL STR EXCAV STA ***** (13+88.00 -L-)	Lump Sum			15,000.00		12,000.00
0072	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	59	CY	1,650.00	97,350.00	2,975.00	175,525.00
0073	8210000000-N	422	BRG APPR SLAB ***** (13+05.88 -L-, 14+70.13 -L-)	Lump Sum			40,000.00		55,000.00
0074	8217000000-E	425	REINF STEEL (BRIDGE)	8,798	LB	2.50	21,995.00	3.20	28,153.60
0075	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES (HP 12 X 53)	10	EA	1,850.00	18,500.00	6,500.00	65,000.00

BP2.R022.3

TIP NO

0.054 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 240043 OVER SWIFT CREEK ON SR 1465 (BEAVER DAM ROAD)

				S T WOOTEN CORPORATION WILSON, NC		TRADER CONSTRUCTION CO NEW BERN, NC			
0076	8328400000-E	450	PILE DRV EQUIP SETUP ** GALV STEEL PILES (PP 18 X 0.50)	14	EA	2,000.00	28,000.00	8,000.00	112,000.00
0077	8364000000-E	450	HP12X53 PILES	600	LF	75.00	45,000.00	90.00	54,000.00
0078	8387000000-E	450	PP18X0.50 GALV STL PILE	1,260	LF	100.00	126,000.00	140.00	176,400.00
0079	8391000000-N	450	STEEL PILE POINTS	7	EA	270.00	1,890.00	1,200.00	8,400.00
0080	8394000000-N	450	DYNAMIC PILE TESTING	2	EA	5,000.00	10,000.00	7,700.00	15,400.00
0081	8505000000-E	460	VERT CONC BARRIER RAIL	280.51	LF	165.00	46,284.15	165.00	46,284.15
0082	8608000000-E	876	RIP RAP II (2'-0")	180	TON	130.00	23,400.00	135.00	24,300.00
0083	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	196	SY	1.00	196.00	4.75	931.00
0084	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			7,500.00		15,000.00
0085	8763000000-E	430	3'-0" X 2'-0"PRESTR SLABS	1,400	LF	380.00	532,000.00	295.00	413,000.00
CONTRACT TOTAL				TOTAL		1,745,240.20	TOTAL	1,945,365.60	
ROADWAY ITEMS				SUB-TOTAL		511,125.05	SUB-TOTAL	606,471.85	
STRUCTURE ITEMS				SUB-TOTAL		1,234,115.15	SUB-TOTAL	1,338,893.75	

BIDDERS IN ORDER

CONTRACT TOTAL

SANFORD CONTRACTORS INC	1	1,481,000.00
T A LOVING COMPANY	2	1,507,000.00
BIRDSALL EXCAVATION AND CONSTRUCTIO	3	1,742,522.20
S T WOOTEN CORPORATION	4	1,745,240.20
TRADER CONSTRUCTION CO	5	1,945,365.60



04/24/2026