



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

April 8, 2014

CONTRACT: DB00167
TIP NUMBER: B-4708
WBS ELEMENT: 38483.3.FD1
COUNTY: Beaufort
ROUTE: SR 1001
DESCRIPTION: Replacement of Bridge #5 over Aggie Run
ADDENDUM NUMBER 1

TO: Prospective Bidders

Please note the following revisions to the proposal for the above-referenced project. On the item sheets, the following pay item quantities have been revised:

<u>Item</u>	<u>Description</u>	<u>Old Quantity</u>	<u>New Quantity</u>
8 – 1498000000-E	Asphalt Conc Intermediate Course, Type I19.0B	660 Ton	0 Ton
9 – 1525000000-E	Asphalt Conc Surface Course, Type SF9.5A	490 Ton	490 Ton
10 – 1575000000-E	Asphalt Binder for Plant Mix	90 Ton	62 Ton
58 – 3656000000-E	Geotextile for Drainage	0 SY	118 SY

If electing to use the Computer Bid Preparation process, the Expedite File has been updated to reflect these revisions. Please download the Expedite Addendum File and follow the instructions for applying the addendum.

The Contractor's bid must be based on these revised pay item quantities. The contract will be prepared accordingly.

Sincerely,


Aaron Bullard, PE

Attachment

cc: Mr. Ed Eatmon, PE
Mr. Bill Kincannon, PE
Ms. Maria Rogerson, PE

MAILING ADDRESS:
DIVISION TWO - OPERATIONS
P.O. BOX 1587
GREENVILLE, NC 27835

TELEPHONE: (252) 439-2800
FAX: (252) 830-3341
WEBSITE: WWW.NCDOT.GOV

LOCATION:
1704 N GREENE ST
GREENVILLE, NC

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+62.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0345000000-E	310	24" SIDE DRAIN PIPE	80 LF		
0006	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	64 LF		
0007	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	660 TON		
0009	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	490 TON		
0010	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	62 TON		
0011	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0012	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	3 EA		
0013	2556000000-E	846	SHOULDER BERM GUTTER	66 LF		
0014	3030000000-E	862	STEEL BM GUARDRAIL	650 LF		
0015	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0016	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0017	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0018	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0019	3649000000-E	876	RIP RAP, CLASS B	46 TON		
0020	5325800000-E	1510	8" WATER LINE	407 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0021	5546000000-E	1515	8" VALVE	1	EA	
0022	5801000000-E	1530	ABANDON 8" UTILITY PIPE	446	LF	
0023	5890000000-N	1510	GENERIC UTILITY ITEM 10" TRANSITION COUPLING (HDPE TO DI)	2	EA	
0024	6000000000-E	1605	TEMPORARY SILT FENCE	1,300	LF	
0025	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	75	TON	
0026	6012000000-E	1610	SEDIMENT CONTROL STONE	50	TON	
0027	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0028	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0029	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5	TON	
0030	6029000000-E	SP	SAFETY FENCE	750	LF	
0031	6030000000-E	1630	SILT EXCAVATION	70	CY	
0032	6042000000-E	1632	1/4" HARDWARE CLOTH	90	LF	
0033	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	210	SY	
0034	6071012000-E	SP	COIR FIBER WATTLE	270	LF	
0035	6071020000-E	SP	POLYACRYLAMIDE (PAM)	40	LB	
0036	6071030000-E	1640	COIR FIBER BAFFLE	20	LF	
0037	6084000000-E	1660	SEEDING & MULCHING	3.99	ACR	
0038	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0039	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0040	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0041	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0042	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
58	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	118 SY		
STRUCTURE ITEMS						
0043	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+62.50)	Lump Sum	L.S.	
0044	8112730000-N	450	PDA TESTING	2 EA		
0045	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18+62.50)	Lump Sum	L.S.	
0046	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	69 CY		
0047	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+62.50)	Lump Sum	L.S.	
0048	8217000000-E	425	REINFORCING STEEL (BRIDGE)	10,290 LB		
0049	8364000000-E	450	HP12X53 STEEL PILES	840 LF		
0050	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	1,120 LF		
0051	8391000000-N	450	STEEL PILE POINTS	16 EA		
0052	8393000000-N	450	PILE REDRIVES	16 EA		
0053	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	250.75 LF		
0054	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	104 TON		
0055	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	116 SY		
0056	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,500 LF		

1003/Apr08/Q20541.49/D299020492000/E57

Total Amount Of Bid For Entire Project :
