PROJECT REFERENCE NO.	SHEET NO.
17.BP.2.R.55	UC-2

UTILITIES ENGINEER

NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 11274 BRYCE EDWARD EATMON

DocuSigned by: Bryce Eatmon 11/10/2025

UTILITY CONSTRUCTION

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

WATER MAIN	QUANTITY	UNIT	ITEM DESCRIPTION
	120	LF	8" DI PIPE - PC 350 (AWWA C600)
	370	LF	10" HDPE PIPE - DR9 (AWWA C906)
	2	EA	8" GATE VALVE AND VALVE BOX
	2	EA	DI PIPE TO HDPE TRANSITION REDUCERS
	6	EA	MECHANICAL JOINT WITH GRIPPING RING RESTRAINT
	488	LF	ABANDON 8" UTILITY PIPE
	200	LF	TEMPORARY SILT FENCE
	0.2	ACRES	SEEDING AND MULCHING

REVISIONS

8/17/99

01-OCT-2015 15:13
C:\WORKSPACE\AUFORT\beaufort 119\Beaufortlt_ddc2_psh_uc2.dgn
$$$$USERNAME$$$$