PROJECT REFERENCE NO.	SHEET NO.
17.BP.2.R.55	3

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

ITEM	SECT	QUANTITY	UNIT	ITEM DESCRIPTION
1	800	1	LS	MOBILIZATION
2	801	1	LS	CONSTRUCTION SURVEYING
3	SP	1	LS	REINFORCED BRIDGE APPROACH FILL, -L- STA 12+58.00
4	226	1	LS	GRADING
5	226	200	CY	UNDERCUT EXCAVATION
6	300	30	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES
7	300	80	SY	FOUNDATION CONDITIONING GEOTEXTILE
8	305	120	LF	15" DRAINAGE PIPE
9	305	72	LF	18" DRAINAGE PIPE
10	310	40	LF	15" R.C. PIPE CULVERTS, CLASS IV
11	610	70	TON	ASPHALT CONCRETE BASE COURSE, TYPE B25.0B
12	610	100	TON	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B
13	610	220	TON	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5A
14	620	25	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG64-22
15	840	2	EA	MASONRY DRAINAGE STRUCTURES
16	840	2	EA	FRAME WITH TWO GRATE, STD 840.29
17	846	126	LF	SHOULDER BERM GUTTER
18	862	20	LF	STEEL BEAM GUARDRAIL
19	862	70	LF	STEEL BEAM GUARDRAIL, SHOP CURVED
20	862	10	EA	ADDITIONAL GUARDRAIL POSTS
21	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
22	862	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
23	862	5	EA	GUARDRAIL ANCHOR UNITS, AT-1
24	876	30	TON	RIP RAP, CLASS I
25	876	14	TON	RIP RAP, CLASS B
26	876	90	SY	GEOTEXTILE FOR DRAINAGE
27	1605	825	LF	TEMPORARY SILT FENCE
28	1610	10	TON	SEDIMENT CONTROL STONE
29	1615	0.5	ACRE	TEMPORARY MULCHING
30	1620	50	LB	SEED FOR TEMPORARY SEEDING
31	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
32	1622	200	LF	TEMPORARY SLOPE DRAINS

ITEM	SECT	QUANTITY	UNIT	ITEM DESCRIPTION
32	SP	625	LF	SAFETY FENCE
33	1630	5	CY	SILT EXCAVATION
34	1631	250	SY	MATTING FOR EROSION CONTROL
35	1632	50	LF	1/4" HARDWARE CLOTH
36	SP	100	SY	FLOATING TURBIDITY CURTAIN
37	SP	50	LF	WATTLE
38	1660	0.50	ACRE	SEEDING AND MULCHING
39	1661	50	LB	SEED FOR REPAIR SEEDING
40	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
41	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
42	1665	0.50	TON	FERTILIZER TOPDRESSING
43	1675	13	EA	RESPONSE FOR EROSION CONTROL
44	SP	1	LS	RELOCATE EXISTING 8" WATER MAIN
45	402	1	LS	REMOVAL OF EXISTING STRUCTURE AT -L- STA 12+58.00
46	412	1	LS	UNCLASSIFIED STRUCTURE EXCAVATION
47	SP	2	EA	PDA TESTING
48	420	37.6	CY	CLASS A CONCRETE (BRIDGE)
49	422	1	LS	BRIDGE APPROACH SLABS
50	425	4898	LB	REINFORCING STEEL (BRIDGE)
51	450	550	LF	12" PRESTRESSED CONCRETE PILES
52	450	10	EA	PILE REDRIVES
53	SP	110.25	LF	VERTICAL CONCRETE BARRIER RAIL
54	876	54	TON	RIP RAP, CLASS II (3'-0" THICK)
55	876	150	SY	GEOTEXTILE FOR DRAINAGE
56	430	1	LS	ELASTOMETRIC BEARINGS
57	430	550	LF	3'-0" X 1'-9" PRESTRESSED CONCRETE CORED SLABS

REVISIONS

8/17/99

10-NOV-2015 12:01
C:\SUPPORT\STRUCTURES\BEAUFORT\beaufort 119\Beaufortlt-ddc2_psh_3.dgn
$$$$USERNAME$$$$