PROJECT REFERENCE NO.	SHEET NO.
17BP.2.R.56	3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
3/30/2016	3/30/2016

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

SECT	QUANTITY	UNIT	ITEM DESCRIPTION
800	1	LS	MOBILIZATION
801	1	LS	CONSTRUCTION SURVEYING
226	1	LS	GRADING
226	100	CY	UNDERCUT EXCAVATION
300	10	TON	FOUNDATION CONDITIONING MATERIAL,MINOR STRUCTURES
300	20	SY	FOUNDATION CONDITIONING GEOTEXTILE
402	1	LS	REMOVAL OF EXISTING STRUCTURE AT -L- STATION 14+76.00
310	40	LF	15" RC PIPE CULVERTS,CLASS IV
520	252	TON	AGGREGATE BASE COURSE
545	20	TON	INCIDENTAL STONE BASE
610	110	TON	ASPHALT CONCRETE BASE COURSE,TYPE B25.0B
610	66	TON	ASPHALT CONCRETE INTERMEDIATE COURSE,TYPE I19.0B
610	33	TON	ASPHALT CONCRETE SURFACE COURSE,TYPE SF9.5A
620	15	TON	ASPHALT BINDER FOR PLANT MIX,GRADE PG64-22
862	2	EA	STEEL BEAM GUARDRAIL OVER LOW FILL CULVERT (STD 862.01)
862	4	EA	GUARDRAIL ANCHOR UNITS,TYPE 350
876	160	TON	CLASS I RIP RAP
876	175	SY	GEOTEXTILE FOR DRAINAGE
1005	524	TON	#57 STONE
1605	100	LF	SAFETY FENCE
1615	0.5	ACRE	TEMPORARY MULCHING
1620	50	LB	SEED FOR TEMPORARY SEEDING
1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
1630	10	CY	SILT EXCAVATION
1632	150	SY	MATTING FOR EROSION CONTROL
1639	1	EA	SPECIAL STILLING BASIN
1660	1	ACRE	SEEDING AND MULCHING
1661	50	LB	SEED FOR REPAIR SEEDING
1661	0.2	TON	FERTILIZER FOR REPAIR SEEDING
SP	5	EA	RESPONSE FOR EROSION CONTROL
SP	120	LF	COIR FIBER WATTLE
SP	1	LS	60" BY 31'-5" X 7'-3" CORRUGATED ALUMINUM BOX CULVERT WITH HEADWALLS AT -L- STATION 14+76.00
SP	1	LS	RELOCATE EXISTING 6" WATER MAIN
SP	1	LS	DEWATERING
SP	66	LF	IMPERVIOUS DIKE

REVISIONS

8/17/99

28-MAR-2016 12:00
C:\SPECIALS\CRAVEN\craven124\Craven124_ddc2_psh3.dgn
$$$$USERNAME$$$$