PROJECT REFERENCE NO.	SHEET NO.
17BP.2.R.56	UC-2

UTILITIES ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL ENGINEER BRYCE EDWARD EATMON 11274 DOCUSIGNED BY: 2/25/2016

UTILITY CONSTRUCTION

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

WATER MAIN	QUANTITY	UNIT	ITEM DESCRIPTION
	60	LF	6" DI PIPE - PC 350 (AWWA C600)
	270	LF	8" HDPE PIPE - DR9 (AWWA C906)
	2	EA	6" GATE VALVE AND VALVE BOX
	2	EA	DI PIPE TO HDPE TRANSITION
	2	EA	CONCRETE THRUST COLLAR
	365	LF	ABANDON 6" UTILITY PIPE
	190	LF	TEMPORARY SILT FENCE
	0.2	ACRES	SEEDING AND MULCHING
	2	EA	33°30' ELBOW WITH RESTRAINED JOINTS

REVISIONS

8/17/99

16-FEB-2016 10:25
G:\WORK\CRAVEN\craven124\Craven124_ddc2_uc2.dgn
$$$$USERNAME$$$$