



PAT McCRORY
Governor

NICHOLAS J. TENNYSON
Secretary

May 12, 2016

CONTRACT: DB00287
WBS ELEMENT: 50138.3.150, 50138.3.151, 50138.3.152
FEDERAL AID NO: HSIP-0011(034), HSIP-0011(035), HSIP-0017(157)
COUNTY: LENOIR, PITT, JONES
ROUTE: Various
DESCRIPTION: GUARDRAIL END UNIT UPGRADES ON NC 11 IN LENOIR COUNTY AND PITT COUNTY, AND US 17 IN JONES COUNTY

ADDENDUM NUMBER 1

TO: Prospective Bidders

Please note the following revision to the proposal for the above referenced project.

- Add attached Special Provision titled “GUARDRAIL ANCHOR UNITS, TYPE 350 (TL-3)” to the proposal
- Line item 1 “IMPACT ATTENUATOR UNIT, TYPE 350” is now corrected to “GUARDRAIL ANCHOR UNITS, TYPE 350”

Include the attached revised Bid Items sheet in your bid.


If electing to use the Computer Bid Preparation process, the Expedite File has been updated to reflect these revisions. Please download the Expedite Addendum File and follow the instructions for applying the addendum.

The Contractor’s bid must be based on the revised pay item. The contract will be prepared accordingly.

Sincerely,

A handwritten signature in black ink, appearing to read "Sarah Lentine".

Sarah Lentine
Division Contract Officer



GUARDRAIL ANCHOR UNITS, TYPE 350 (TL-3):

(4-20-04) (Rev. 7-21-15)

862

SP8 R65

Description

Furnish and install guardrail anchor units in accordance with the details in the plans, the applicable requirements of Section 862 of the *2012 Standard Specifications*, and at locations shown in the plans.

Materials

Furnish guardrail anchor units listed on the NCDOT [Approved Products List](https://apps.dot.state.nc.us/vendor/approvedproducts/) at <https://apps.dot.state.nc.us/vendor/approvedproducts/> or approved equal.

Prior to installation the Contractor shall submit to the Engineer:

- (A) FHWA acceptance letter for each guardrail anchor unit certifying it meets the requirements of NCHRP Report 350, Test Level 3, in accordance with Article 106-2 of the *2012 Standard Specifications*.
- (B) Certified working drawings and assembling instructions from the manufacturer for each guardrail anchor unit in accordance with Article 105-2 of the *2012 Standard Specifications*.

No modifications shall be made to the guardrail anchor unit without the express written permission from the manufacturer. Perform installation in accordance with the details in the plans, and details and assembling instructions furnished by the manufacturer.

Construction Methods

Guardrail end delineation is required on all approach and trailing end sections for both temporary and permanent installations. Guardrail end delineation consists of yellow reflective sheeting applied to the entire end section of the guardrail in accordance with Article 1088-3 of the *2012 Standard Specifications* and is incidental to the cost of the guardrail anchor unit.

Measurement and Payment

Measurement and payment will be made in accordance with Article 862-6 of the *2012 Standard Specifications*.

Payment will be made under:

Pay Item
Guardrail Anchor Units, Type 350

Pay Unit
Each

County : Lenoir, Pitt, Jones

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
--------	-------------	-------	-------------	----------	-----------	--------

ROADWAY ITEMS

0001	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	79 EA		
------	--------------	----	-------------------------------------	----------	--	--

0917/May12/Q79.0/D3270000000/E1

Total Amount Of Bid For Entire Project :
