

BP2.R008.3

TIP NO

0.147 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 60010 OVER HERRING RUN ON SR 1110 (HERRING RUN ROAD)

				SANFORD CONTRACTORS INC LEMON SPRINGS, NC		T A LOVING COMPANY GOLDSBORO, NC		S T WOOTEN CORPORATION WILSON, NC	
<b>ROADWAY ITEMS</b>									
0001	0000100000-N	800	MOBILIZATION	Lump Sum		78,640.00	80,000.00		88,000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		14,113.06	15,000.00		17,500.00
0003	0008000000-E	200	SUPP CLEARING & GRUBBING	1 ACR	0.01	0.01	1,000.00	1,000.00	1,000.00
0004	0036000000-E	225	UNDERCUT EXCAVATION	450 CY	0.01	4.50	0.01	4.50	10.00
0005	0043000000-N	226	GRADING (226)	Lump Sum		170,166.25	158,812.29		150,000.00
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	450 CY	0.01	4.50	0.01	4.50	5.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	450 SY	6.42	2,889.00	0.01	4.50	1.00
0008	0223000000-E	275	ROCK PLATING	10 SY	461.69	4,616.90	300.00	3,000.00	300.00
0009	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE 1 BRIDGE APPROACH FILL, STATION 14+76.00 -L-	Lump Sum		28,299.04	35,000.00		22,000.00
0010	0318000000-E	300	FND CONDIT MATL MINOR STRS	23 TON	37.15	854.45	95.00	2,185.00	95.00
0011	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	56 SY	3.75	210.00	4.00	224.00	1.00
0012	1121000000-E	520	AGGREGATE BASE COURSE	30 TON	27.15	814.50	100.00	3,000.00	110.00
0013	1330000000-E	607	INCIDENTAL MILLING	220 SY	17.00	3,740.00	17.00	3,740.00	46.00
0014	1491000000-E	610	ASP CONC BASE CRS B25.0C	490 TON	130.00	63,700.00	130.00	63,700.00	152.00
0015	1519000000-E	610	ASP CONC SURF CRS S9.5B	400 TON	132.00	52,800.00	132.00	52,800.00	132.00
0016	1575000000-E	620	ASP FOR PLANT MIX	50 TON	675.00	33,750.00	675.00	33,750.00	650.00
0017	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY	0.01	0.45	0.01	0.45	5.00
0018	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200 SY	0.01	2.00	0.01	2.00	1.00
0019	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6 CY	0.01	0.34	0.01	0.34	10.00
0020	2044000000-E	815	6" PERF SUBDRN PIPE	200 LF	0.01	2.00	0.01	2.00	5.00
0021	2070000000-N	815	SUBDRN PIPE OUTLET	6 EA	0.01	0.06	0.01	0.06	100.00
0022	2077000000-E	815	6" OUTLET PIPE	1 LF	0.01	0.01	0.01	0.01	5.00
0023	2556000000-E	846	SHOULDER BERM GUTTER	150 LF	36.64	5,496.00	25.00	3,750.00	47.70
0024	2570000000-N	SP	MODIFIED CONCRETE FLUME	1 EA	1,618.38	1,618.38	700.00	700.00	3,950.00
0025	3030000000-E	862	STL BEAM GUARDRAIL	350 LF	24.50	8,575.00	24.50	8,575.00	24.50
0026	3150000000-N	862	ADDIT GUARDRAIL POSTS	5 EA	11.00	55.00	11.00	55.00	11.00
0027	3215000000-N	862	GR ANCHOR TYPE III	4 EA	2,400.00	9,600.00	2,400.00	9,600.00	2,400.00
0028	3287000000-N	862	GR END TYPE TL-3	4 EA	3,250.00	13,000.00	3,250.00	13,000.00	3,250.00
0029	3635000000-E	876	RIP RAP, CLASS II	105 TON	54.65	5,738.25	130.00	13,650.00	130.00
0030	3649000000-E	876	RIP RAP, CLASS B	2 TON	184.15	368.30	95.00	190.00	95.00
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	484 SY	3.75	1,815.00	6.00	2,904.00	6.00
0032	4400000000-E	1110	WORK ZONE SIGNS (STAT)	422 SF	8.95	3,776.90	8.95	3,776.90	6.45
0033	4410000000-E	1110	WORK ZONE SIGNS (BARR)	94 SF	8.55	803.70	8.55	803.70	6.75
0034	4420000000-N	1120	PORTABLE CHANGE MSG SIGN	2 EA	4,950.00	9,900.00	4,950.00	9,900.00	13,885.37
0035	4445000000-E	1145	BARRICADES (TYPE III)	80 LF	22.50	1,800.00	22.50	1,800.00	20.00
0036	5325400000-E	1510	4" WATER LINE	590 LF	82.00	48,380.00	82.00	48,380.00	30.85
0037	5329000000-E	1510	DI H2O PIPE FITTINGS	300 LB	15.00	4,500.00	15.00	4,500.00	18.00
0038	5538000000-E	1515	4" VALVE	2 EA	2,800.00	5,600.00	2,800.00	5,600.00	6,570.00
0039	5606000000-E	1515	2" BLOW OFF	1 EA	2,200.00	2,200.00	2,200.00	2,200.00	4,000.00
0040	5798000000-E	1530	ABANDON *** UTILITY PIPE 4"	585 LF	8.00	4,680.00	8.00	4,680.00	19.00

BP2.R008.3

TIP NO

0.147 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 60010 OVER HERRING RUN ON SR 1110 (HERRING RUN ROAD)

				SANFORD CONTRACTORS INC LEMON SPRINGS, NC			T A LOVING COMPANY GOLDSBORO, NC		S T WOOTEN CORPORATION WILSON, NC		
0041	5872600000-E	1550	DIRECT DRILL *** 4"	372	LF	90.00	33,480.00	90.00	33,480.00	70.00	26,040.00
0042	6000000000-E	1605	TEMPORARY SILT FENCE	945	LF	4.00	3,780.00	3.55	3,354.75	4.33	4,091.85
0043	6006000000-E	1610	EROS CONTRL STONE CL A	95	TON	44.15	4,194.25	95.00	9,025.00	95.00	9,025.00
0044	6009000000-E	1610	EROS CONTRL STONE CL B	55	TON	44.15	2,428.25	90.00	4,950.00	90.00	4,950.00
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	15	TON	37.15	557.25	85.00	1,275.00	85.00	1,275.00
0046	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	0.01	0.02	1,850.00	3,700.00	1,850.00	3,700.00
0047	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	0.01	2.00	2.00	400.00	2.00	400.00
0048	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	0.01	0.01	1,092.00	1,092.00	1,092.00	1,092.00
0049	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	0.01	2.00	1.00	200.00	5.00	1,000.00
0050	6029000000-E	SP	SAFETY FENCE	660	LF	3.00	1,980.00	3.00	1,980.00	3.74	2,468.40
0051	6030000000-E	1630	SILT EXCAVATION	70	CY	0.01	0.70	15.00	1,050.00	15.00	1,050.00
0052	6036000000-E	1631	MATTING FOR EROS CONTROL	3,000	SY	2.00	6,000.00	1.99	5,970.00	1.99	5,970.00
0053	6037000000-E	1629	COIR FIBER MAT	100	SY	6.50	650.00	4.36	436.00	4.36	436.00
0054	6042000000-E	1632	1/4" HARDWARE CLOTH	5	LF	6.00	30.00	3.75	18.75	3.75	18.75
0055	6048000000-E	SP	FLOAT TURBIDITY CURTAIN	370	SY	12.84	4,750.80	32.00	11,840.00	10.00	3,700.00
0056	6071002000-E	1642	FLOCCULANT	15	LB	10.00	150.00	23.75	356.25	23.75	356.25
0057	6071012000-E	1642	COIR FIBER WATTLE	190	LF	15.00	2,850.00	14.50	2,755.00	14.50	2,755.00
0058	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	0.01	0.03	100.00	300.00	495.00	1,485.00
0059	6087000000-E	1660	MOWING	1.5	ACR	250.00	375.00	295.00	442.50	295.00	442.50
0060	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	6.00	300.00	4.15	207.50	4.15	207.50
0061	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	600.00	150.00	1,092.00	273.00	1,092.00	273.00
0062	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	6.00	300.00	4.98	249.00	4.98	249.00
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5	TON	1,000.00	1,500.00	1,092.00	1,638.00	1,092.00	1,638.00
0064	6111000000-E	SP	IMPERVIOUS DIKE	232	LF	0.01	2.32	120.00	27,840.00	150.00	34,800.00
0065	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	75.00	750.00	75.00	750.00	75.00	750.00
0066	6117000000-N	1675	RESPONSE FOR EROS CONTROL	13	EA	0.01	0.13	100.00	1,300.00	120.00	1,560.00
0067	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	321.00	321.00	250.00	250.00	2,000.00	2,000.00
0068	6123000000-E	1670	REFORESTATION	0.1	ACR	8,000.00	800.00	5,500.00	550.00	1,950.00	195.00
0069	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	2	EA	750.00	1,500.00	250.00	500.00	2,000.00	4,000.00
<b>STRUCTURE ITEMS</b>											
0070	8035000000-N	402	REMV EXIST STR ***** BRG (402) 14+76.00 -L-	Lump Sum			72,492.32		70,000.00		100,000.00
0071	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			2,500.00		2,000.00		1,000.00
0072	8121000000-N	412	UNCL STR EXCAV STA ***** 14+76.00 -L-	Lump Sum			3,557.61		10,000.00		25,000.00
0073	8175000000-E	420	CLASS AA CONC (BRIDGE)	40.3	CY	3,754.65	151,312.40	3,800.00	153,140.00	3,500.00	141,050.00
0074	8210000000-N	422	BRG APPR SLAB ***** 14+76.00 -L-	Lump Sum			59,549.85		60,000.00		50,000.00
0075	8224000000-E	425	EPOXY COAT REINF STL BRDG	6,474	LB	1.64	10,617.36	2.00	12,948.00	4.10	26,543.40
0076	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES HP 12x53	14	EA	2,241.30	31,378.20	4,900.00	68,600.00	1,500.00	21,000.00

BP2.R008.3

TIP NO

0.147 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 60010 OVER HERRING RUN ON SR 1110 (HERRING RUN ROAD)

				SANFORD CONTRACTORS INC LEMON SPRINGS, NC		T A LOVING COMPANY GOLDSBORO, NC		S T WOOTEN CORPORATION WILSON, NC			
0077	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES HP 14x73	8	EA	3,888.92	31,111.36	6,000.00	48,000.00	2,000.00	16,000.00
0078	8364000000-E	450	HP12X53 PILES	875	LF	51.15	44,756.25	55.00	48,125.00	125.00	109,375.00
0079	8384000000-E	450	HP14X73 PILES	640	LF	211.86	135,590.40	215.00	137,600.00	150.00	96,000.00
0080	8393000000-N	450	PILE REDRIVES	11	EA	0.01	0.11	10.00	110.00	152.00	1,672.00
0081	8394000000-N	450	DYNAMIC PILE TESTING	2	EA	2,500.00	5,000.00	3,500.00	7,000.00	5,200.00	10,400.00
0082	8505000000-E	460	VERT CONC BARRIER RAIL	190.5	LF	396.24	75,483.72	300.00	57,150.00	225.70	42,995.85
0083	8608000000-E	876	RIP RAP II (2'-0")	140	TON	125.96	17,634.40	110.00	15,400.00	165.00	23,100.00
0084	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	150	SY	3.75	562.50	2.00	300.00	1.00	150.00
0085	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			4,261.01		5,000.00		6,000.00
0086	8762000000-E	430	3'-0"X 1'-9"PRESTR SLABS	1,045	LF	265.67	277,625.15	270.00	282,150.00	325.00	339,625.00
CONTRACT TOTAL						TOTAL	1,572,800.00	TOTAL	1,680,000.00	TOTAL	1,736,008.14
ROADWAY ITEMS						SUB-TOTAL	649,367.36	SUB-TOTAL	702,477.00	SUB-TOTAL	726,096.89
STRUCTURE ITEMS						SUB-TOTAL	923,432.64	SUB-TOTAL	977,523.00	SUB-TOTAL	1,009,911.25

BP2.R008.3

TIP NO

0.147 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 60010 OVER HERRING RUN ON SR 1110 (HERRING RUN ROAD)

TRADER CONSTRUCTION CO  
NEW BERN, NC

**ROADWAY ITEMS**

0001	0000100000-N	800	MOBILIZATION	Lump Sum		95,400.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		25,000.00
0003	0008000000-E	200	SUPP CLEARING & GRUBBING	1	ACR	2,500.00
0004	0036000000-E	225	UNDERCUT EXCAVATION	450	CY	55.00
0005	0043000000-N	226	GRADING (226)	Lump Sum		164,000.00
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	450	CY	105.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	450	SY	4.00
0008	0223000000-E	275	ROCK PLATING	10	SY	385.00
0009	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE 1 BRIDGE APPROACH FILL, STATION 14+76.00 -L-	Lump Sum		25,000.00
0010	0318000000-E	300	FND CONDIT MATL MINOR STRS	23	TON	80.00
0011	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	56	SY	4.00
0012	1121000000-E	520	AGGREGATE BASE COURSE	30	TON	65.00
0013	1330000000-E	607	INCIDENTAL MILLING	220	SY	55.00
0014	1491000000-E	610	ASP CONC BASE CRS B25.0C	490	TON	115.00
0015	1519000000-E	610	ASP CONC SURF CRS S9.5B	400	TON	140.00
0016	1575000000-E	620	ASP FOR PLANT MIX	50	TON	765.00
0017	2022000000-E	815	SUBDRAIN EXCAVATION	44.8	CY	12.00
0018	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200	SY	3.50
0019	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6	CY	100.00
0020	2044000000-E	815	6" PERF SUBDRN PIPE	200	LF	6.00
0021	2070000000-N	815	SUBDRN PIPE OUTLET	6	EA	350.00
0022	2077000000-E	815	6" OUTLET PIPE	1	LF	20.00
0023	2556000000-E	846	SHOULDER BERM GUTTER	150	LF	47.70
0024	2570000000-N	SP	MODIFIED CONCRETE FLUME	1	EA	3,950.00
0025	3030000000-E	862	STL BEAM GUARDRAIL	350	LF	24.50
0026	3150000000-N	862	ADDIT GUARDRAIL POSTS	5	EA	11.00
0027	3215000000-N	862	GR ANCHOR TYPE III	4	EA	2,400.00
0028	3287000000-N	862	GR END TYPE TL-3	4	EA	3,250.00
0029	3635000000-E	876	RIP RAP, CLASS II	105	TON	145.00
0030	3649000000-E	876	RIP RAP, CLASS B	2	TON	225.00
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	484	SY	4.50
0032	4400000000-E	1110	WORK ZONE SIGNS (STAT)	422	SF	6.45
0033	4410000000-E	1110	WORK ZONE SIGNS (BARR)	94	SF	6.75
0034	4420000000-N	1120	PORTABLE CHANGE MSG SIGN	2	EA	7,750.00
0035	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	20.00
0036	5325400000-E	1510	4" WATER LINE	590	LF	175.00
0037	5329000000-E	1510	DI H2O PIPE FITTINGS	300	LB	15.00
0038	5538000000-E	1515	4" VALVE	2	EA	3,500.00
0039	5606000000-E	1515	2" BLOW OFF	1	EA	11,500.00
0040	5798000000-E	1530	ABANDON *** UTILITY PIPE 4"	585	LF	20.00

BP2.R008.3

TIP NO

0.147 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 60010 OVER HERRING RUN ON SR 1110 (HERRING RUN ROAD)

TRADER CONSTRUCTION CO  
NEW BERN, NC

0041	5872600000-E	1550	DIRECT DRILL *** 4"	372	LF	65.00	24,180.00
0042	6000000000-E	1605	TEMPORARY SILT FENCE	945	LF	4.00	3,780.00
0043	6006000000-E	1610	EROS CONTRL STONE CL A	95	TON	145.00	13,775.00
0044	6009000000-E	1610	EROS CONTRL STONE CL B	55	TON	105.00	5,775.00
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	15	TON	80.00	1,200.00
0046	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	2,175.00	4,350.00
0047	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	8.95	1,790.00
0048	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	1,750.00	1,750.00
0049	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	30.00	6,000.00
0050	6029000000-E	SP	SAFETY FENCE	660	LF	3.90	2,574.00
0051	6030000000-E	1630	SILT EXCAVATION	70	CY	40.00	2,800.00
0052	6036000000-E	1631	MATTING FOR EROS CONTROL	3,000	SY	2.15	6,450.00
0053	6037000000-E	1629	COIR FIBER MAT	100	SY	7.50	750.00
0054	6042000000-E	1632	1/4" HARDWARE CLOTH	5	LF	8.75	43.75
0055	6048000000-E	SP	FLOAT TURBIDITY CURTAIN	370	SY	40.00	14,800.00
0056	6071002000-E	1642	FLOCCULANT	15	LB	15.00	225.00
0057	6071012000-E	1642	COIR FIBER WATTLE	190	LF	13.75	2,612.50
0058	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	2,750.00	8,250.00
0059	6087000000-E	1660	MOWING	1.5	ACR	700.00	1,050.00
0060	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	47.50	2,375.00
0061	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1,750.00	437.50
0062	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	15.00	750.00
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5	TON	1,750.00	2,625.00
0064	6111000000-E	SP	IMPERVIOUS DIKE	232	LF	310.00	71,920.00
0065	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	95.00	950.00
0066	6117000000-N	1675	RESPONSE FOR EROS CONTROL	13	EA	1.00	13.00
0067	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	1,650.00	1,650.00
0068	6123000000-E	1670	REFORESTATION	0.1	ACR	10,000.00	1,000.00
0069	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	2	EA	1,650.00	3,300.00
<b>STRUCTURE ITEMS</b>							
0070	8035000000-N	402	REMV EXIST STR ***** BRG (402) 14+76.00 -L-	Lump Sum			86,000.00
0071	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			2,500.00
0072	8121000000-N	412	UNCL STR EXCAV STA ***** 14+76.00 -L-	Lump Sum			10,000.00
0073	8175000000-E	420	CLASS AA CONC (BRIDGE)	40.3	CY	2,730.00	110,019.00
0074	8210000000-N	422	BRG APPR SLAB ***** 14+76.00 -L-	Lump Sum			70,000.00
0075	8224000000-E	425	EPOXY COAT REINF STL BRDG	6,474	LB	3.60	23,306.40
0076	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES HP 12x53	14	EA	2,200.00	30,800.00

BP2.R008.3

TIP NO

0.147 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 60010 OVER HERRING RUN ON SR 1110 (HERRING RUN ROAD)

TRADER CONSTRUCTION CO  
NEW BERN, NC

0077	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES HP 14x73	8	EA	4,200.00	33,600.00
0078	8364000000-E	450	HP12X53 PILES	875	LF	90.00	78,750.00
0079	8384000000-E	450	HP14X73 PILES	640	LF	110.00	70,400.00
0080	8393000000-N	450	PILE REDRIVES	11	EA	1,200.00	13,200.00
0081	8394000000-N	450	DYNAMIC PILE TESTING	2	EA	3,750.00	7,500.00
0082	8505000000-E	460	VERT CONC BARRIER RAIL	190.5	LF	255.00	48,577.50
0083	8608000000-E	876	RIP RAP II (2'-0")	140	TON	165.00	23,100.00
0084	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	150	SY	7.00	1,050.00
0085	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			12,000.00
0086	8762000000-E	430	3'-0"X 1'-9"PRESTR SLABS	1,045	LF	304.00	317,680.00
CONTRACT TOTAL						TOTAL	1,908,434.65
ROADWAY ITEMS						SUB-TOTAL	969,951.75
STRUCTURE ITEMS						SUB-TOTAL	938,482.90

**BIDDERS IN ORDER**

**CONTRACT TOTAL**

SANFORD CONTRACTORS INC	1	1,572,800.00
T A LOVING COMPANY	2	1,680,000.00
S T WOOTEN CORPORATION	3	1,736,008.14
TRADER CONSTRUCTION CO	4	1,908,434.65



05/29/2026