STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

ITEM	SECT	QUANTITY	UNIT	ITEM DESCRIPTION
1	800	1	LS	MOBILIZATION
2	801	1	LS	CONSTRUCTION SURVEYING
3	SP	1	LS	REINFORCED BRIDGE APPROACH FILL
4	226	1	LS	GRADING
5	226	200	CY	UNDERCUT EXCAVATION
6	300	40	TON	FOUNDATION CONDITIONING MATERIAL,MINOR STRUCTURES
7	300	110	SY	FOUNDATION CONDITIONING GEOTEXTILE
8	305	240	LF	18" DRAINAGE PIPE
9	305	44	LF	24" DRAINAGE PIPE
10	310	24	LF	15" R.C.PIPE CULVERTS,CLASS III
11	340	40	LF	PIPE REMOVAL
12	610	380	TON	ASPHALT CONCRETE BASE COURSE,TYPE B25.0B
13	610	285	TON	ASPHALT CONCRETE INTERMEDIATE COURSE,TYPE I19.0B
14	610	280	TON	ASPHALT CONCRETE SURFACE COURSE,TYPE S9.5A
15	620	60	TON	ASPHALT BINDER FOR PLANT MIX,GRADE PG64-22
16	840	1	EA	MASONRY DRAINAGE STRUCTURES
17	840	1	EA	FRAME WITH GRATE,STD 840.29
18	846	50	LF	SHOULDER BERM GUTTER
19	862	4	EA	GUARDRAIL ANCHOR UNITS,TYPE III
20	862	4	EA	GUARDRAIL ANCHOR UNITS,TYPE 350
21	876	1	TON	RIP RAP,CLASS B
22	876	5	SY	GEOTEXTILE FOR DRAINAGE
23	1605	650	LF	TEMPORARY SILT FENCE
24	1610	60	TON	STONE FOR EROSION CONTROL,CLASS B
25	1610	35	TON	SEDIMENT CONTROL STONE
26	1615	0.5	ACRE	TEMPORARY MULCHING
27	1620	50	LB	SEED FOR TEMPORARY SEEDING
28	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
29	SP	450	LF	SAFETY FENCE
30	1631	500	SY	MATTING FOR EROSION CONTROL
31	1632	25	LF	1/4" HARDWARE CLOTH
32	SP	100	LF	WATTLE
33	SP	10	LB	POLYACRYLAMIDE (PAM)
34	1660	0.5	ACRE	SEEDING AND MULCHING
35	1661	50	LB	SEED FOR REPAIR SEEDING
36	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
37	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
38	1665	0.5	TON	FERTILIZER TOPDRESSING
39	SP	13	EA	RESPONSE FOR EROSION CONTROL
40	SP	1	LS	RELOCATE EXISTING 6" WATER MAIN
41	402	1	LS	REMOVAL OF EXISTING STRUCTURE AT -L- STA 12+33.00
42	412	1	LS	UNCLASSIFIED STRUCTURE EXCAVATION
43	SP	2	EA	PDA TESTING
44	420	52.6	CY	CLASS A CONCRETE (BRIDGE)
45	422	1	LS	BRIDGE APPROACH SLABS
46	425	5954	LB	REINFORCING STEEL (BRIDGE)
47	450	700	LF	16" PRESTRESSED CONCRETE PILES
48	450	14	EA	PILE REDRIVES
49	SP	110.25	LF	VERTICAL CONCRETE BARRIER RAIL
50	876	58	TON	RIP RAP,CLASS II (3'-0" THICK)
51	876	287	SY	GEOTEXTILE FOR DRAINAGE
52	430	1	LS	ELASTOMETRIC BEARINGS
53	430	605	LF	3'-0" X 1'-9" PRESTRESSED CONCRETE CORED SLABS

REVISIONS

8/17/99

24-NOV-2015 07:38
S:\PROJECT\TIPS\BEAUFORT\beaufort 150\Beaufort150.dac2.psh3.dgn
$$$$USERNAME$$$$