PROJECT REFERENCE NO.	SHEET NO.
17.BP.2.R.54	UC-2

UTILITIES ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 11274 ENGINEER BRYCE EDWARD EATMON, III

DocuSigned by: Bryce Eatmon 11/24/2015

UTILITY CONSTRUCTION

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

WATER MAIN	QUANTITY	UNIT	ITEM DESCRIPTION
	124	LF	8" DI PIPE - PC 350 (AWWA C600)
	370	LF	10" HDPE PIPE - DR9 (AWWA C906)
	2	EA	8" GATE VALVE AND VALVE BOX
	2	EA	DI PIPE TO HDPE TRANSITION REDUCER
	1	EA	CONCRETE THRUST COLLAR
	3	EA	MECHANICAL JOINTS WITH GRIPPING RING RESTRAINTS
	478	LF	ABANDON 8" UTILITY PIPE
	275	LF	TEMPORARY SILT FENCE
	0.2	ACRES	SEEDING AND MULCHING

REVISIONS

8/17/99

01-OCT-2015 15:34
C:\WORKSPACE\BEAUFORT\beaufort 150\Beaufort150.ddc2.uc2.dgn
$$$$USERNAME$$$$