

TIP NO  
FED AID NO STATE FUNDED  
BRIDGE # 159 REPLACEMENT  
BRIDGE #159 OVER PUNGO SWAMP ON SR 1611

0.284 MI

		S T WOOTEN CORPORATION		DANE CONSTRUCTION INC		TRADER CONSTRUCTION CO	
		WILSON, NC		MOORESVILLE, NC		NEW BERN, NC	
<b>ROADWAY ITEMS</b>							
0001	0000100000-N	800	MOBILIZATION	Lump Sum	60000.00	65845.00	70000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	20000.00	8500.00	10000.00
0003	0030000000-N	SP	TYPE II MODIFIED APPR ***** 17+36.00	Lump Sum	12000.00	4400.00	25000.00
0004	0043000000-N	226	GRADING	Lump Sum	95000.00	125000.00	90000.00
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY	1.00 300.00	11.50 3450.00	9.00 2700.00
0006	0194000000-E	265	SELECT GRANULAR MATL, CLASS III	300 CY	5.00 1500.00	22.00 6600.00	29.00 8700.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	300 SY	3.00 900.00	4.00 1200.00	3.30 990.00
0008	0318000000-E	300	FND CONDIT MATL MINOR STRS	20 TON	60.00 1200.00	85.00 1700.00	145.00 2900.00
0009	0320000000-E	300	FND CONDIT GEOTEXTILE	60 SY	3.00 180.00	4.00 240.00	5.00 300.00
0010	0448200000-E	310	15" RCP CULV CLASS IV	16 LF	100.00 1600.00	95.00 1520.00	109.00 1744.00
0011	0448400000-E	310	24" RCP CULV CLASS IV	156 LF	120.00 18720.00	110.00 17160.00	105.00 16380.00
0012	1330000000-E	607	INCIDENTAL MILLING	400 SY	15.00 6000.00	20.00 8000.00	32.00 12800.00
0013	1491000000-E	610	ASP CONC BASE CRS B25.0C	720 TON	77.00 55440.00	77.00 55440.00	77.00 55440.00
0014	1519000000-E	610	ASP CONC SURF CRS S9.5B	1,180 TON	68.00 80240.00	68.00 80240.00	68.00 80240.00
0015	1575000000-E	620	ASP FOR PLANT MIX	105 TON	500.00 52500.00	500.00 52500.00	500.00 52500.00
0016	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY	1.00 45.00	38.00 1710.00	25.00 1125.00
0017	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200 SY	3.00 600.00	2.25 450.00	5.00 1000.00
0018	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	34 CY	5.00 170.00	67.00 2278.00	65.00 2210.00
0019	2044000000-E	815	6" PERF SUBDRN PIPE	200 LF	1.00 200.00	20.00 4000.00	12.00 2400.00
0020	2070000000-N	815	SUBDRN PIPE OUTLET	6 EA	5.00 30.00	487.00 2922.00	350.00 2100.00
0021	2077000000-E	815	6" OUTLET PIPE	1 LF	1.00 1.00	79.00 79.00	25.00 25.00
0022	2286000000-N	840	MASNRY DRAINAGE STRUCT	2 EA	3500.00 7000.00	2500.00 5000.00	3355.00 6710.00
0023	2367000000-N	840	FRAME W/2GRTS 840.29 STD	2 EA	700.00 1400.00	700.00 1400.00	600.00 1200.00
0024	2556000000-E	846	SHOULDER BERM GUTTER	130 LF	50.00 6500.00	30.00 3900.00	65.00 8450.00
0025	3030000000-E	862	STL BEAM GUARDRAIL	180 LF	17.00 3060.00	18.00 3240.00	18.00 3240.00
0026	3150000000-N	862	ADDIT GUARDRAIL POSTS	5 EA	11.00 55.00	11.00 55.00	11.00 55.00
0027	3195000000-N	862	GR END TYPE AT-1	3 EA	750.00 2250.00	750.00 2250.00	750.00 2250.00
0028	3215000000-N	SP	GR ANCHOR TYPE III	4 EA	1850.00 7400.00	1850.00 7400.00	1850.00 7400.00
0029	3288000000-N	SP	GR END TYPE TL-2	1 EA	3200.00 3200.00	3200.00 3200.00	3200.00 3200.00
0030	3578000000-N	SP	GENERIC FENCING ITEM (EA) RESET EXISTING GATE	2 EA	2300.00 4600.00	2300.00 4600.00	2300.00 4600.00
0031	3628000000-E	876	RIP RAP, CLASS I	40 TON	77.00 3080.00	120.00 4800.00	100.00 4000.00
0032	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	250 SY	3.00 750.00	4.00 1000.00	3.00 750.00
0033	5325600000-E	1510	6" WATER LINE	129 LF	157.00 20253.00	157.00 20253.00	157.00 20253.00
0034	5325800000-E	1510	8" WATER LINE	409 LF	50.00 20450.00	50.00 20450.00	50.00 20450.00
0035	5329000000-E	1510	DI H2O PIPE FITTINGS	340 LB	8.00 2720.00	8.00 2720.00	8.00 2720.00
0036	5540000000-E	1515	6" VALVE	2 EA	1595.00 3190.00	1595.00 3190.00	1595.00 3190.00
0037	5800000000-E	1530	ABANDON 6" UTILITY PIPE	537 LF	6.00 3222.00	6.00 3222.00	6.00 3222.00
0038	5872600000-E	1550	DIRECT DRILL *** 8"	409 LF	55.00 22495.00	55.00 22495.00	55.00 22495.00

TIP NO  
FED AID NO STATE FUNDED  
BRIDGE # 159 REPLACEMENT  
BRIDGE #159 OVER PUNGO SWAMP ON SR 1611

0.284 MI

					S T WOOTEN CORPORATION	DANE CONSTRUCTION INC	TRADER CONSTRUCTION CO			
					WILSON, NC	MOORESVILLE, NC	NEW BERN, NC			
0039	6000000000-E	1605	TEMPORARY SILT FENCE	1,900 LF	2.50	4750.00	3.25	6175.00	3.25	6175.00
0040	6006000000-E	1610	EROS CONTRL STONE CL A	90 TON	50.00	4500.00	110.00	9900.00	90.00	8100.00
0041	6009000000-E	1610	EROS CONTRL STONE CL B	70 TON	55.00	3850.00	110.00	7700.00	90.00	6300.00
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	40 TON	50.00	2000.00	85.00	3400.00	80.00	3200.00
0043	6015000000-E	1615	TEMPORARY MULCHING	4 ACR	600.00	2400.00	910.00	3640.00	910.00	3640.00
0044	6018000000-E	1620	SEED FOR TEMP SEEDING	300 LB	3.00	900.00	4.65	1395.00	4.65	1395.00
0045	6021000000-E	1620	FERT FOR TEMP SEEDING	1.5 TON	800.00	1200.00	1200.00	1800.00	1200.00	1800.00
0046	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF	0.50	100.00	15.00	3000.00	35.00	7000.00
0047	6029000000-E	SP	SAFETY FENCE	1,600 LF	2.00	3200.00	2.00	3200.00	2.00	3200.00
0048	6030000000-E	1630	SILT EXCAVATION	70 CY	10.00	700.00	15.00	1050.00	17.00	1190.00
0049	6036000000-E	1631	MATTING FOR EROS CONTROL	1,400 SY	2.25	3150.00	2.00	2800.00	2.00	2800.00
0050	6037000000-E	SP	COIR FIBER MAT	100 SY	4.75	475.00	5.00	500.00	5.00	500.00
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF	4.00	200.00	5.00	250.00	5.00	250.00
0052	6048000000-E	SP	FLOAT TURBIDITY CURTAIN	170 SY	32.50	5525.00	55.00	9350.00	35.00	5950.00
0053	6071012000-E	SP	COIR FIBER WATTLE	320 LF	15.00	4800.00	10.75	3440.00	10.75	3440.00
0054	6071014000-E	SP	COIR FIBER WATTLE BARRIER	100 LF	17.00	1700.00	15.00	1500.00	15.00	1500.00
0055	6071020000-E	SP	POLYACRYLAMIDE (PAM)	30 LB	9.00	270.00	25.00	750.00	25.00	750.00
0056	6084000000-E	1660	SEEDING AND MULCHING	6 ACR	195.00	1170.00	2250.00	13500.00	2250.00	13500.00
0057	6090000000-E	1661	SEED FOR REPAIR SEEDING	3 LB	10.00	30.00	25.00	75.00	25.00	75.00
0058	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25 TON	400.00	100.00	1200.00	300.00	1200.00	300.00
0059	6096000000-E	1662	SEED FOR SUPP SEEDING	100 LB	2.00	200.00	5.50	550.00	5.50	550.00
0060	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON	1.00	3.00	900.00	2700.00	900.00	2700.00
0061	6117000000-N	SP	RESPONSE FOR EROS CONTROL	13 EA	20.00	260.00	50.00	650.00	200.00	2600.00
0062	6117500000-N	SP	CONC WASHOUT STRUCTURE	2 EA	1000.00	2000.00	1935.00	3870.00	2200.00	4400.00
0063	6123000000-E	1670	REFORESTATION	0.1 ACR	500.00	50.00	7500.00	750.00	7500.00	750.00
0064	8035000000-N	402	REMV EXIST STR ***** 17+36.00	Lump Sum		68250.00		50220.00		75000.00
0065	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum		1000.00		1050.00		2000.00
0066	8112730000-N	450	PDA TESTING	2 EA	5000.00	10000.00	3100.00	6200.00	10000.00	20000.00
0067	8121000000-N	412	UNCL STR EXCAV STA ***** 17+36.00	Lump Sum		25000.00		8000.00		7500.00
0068	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	46 CY	1300.00	59800.00	1800.00	82800.00	1900.00	87400.00
0069	8210000000-N	422	BRG APPR SLAB ***** 17+36.00	Lump Sum		29500.00		15250.00		45000.00
0070	8217000000-E	425	REINF STEEL (BRIDGE)	8,472 LB	1.50	12708.00	1.25	10590.00	2.50	21180.00
0071	8328000000-E	450	PILE DRV EQUIP SETUP * PRESTR CONC PILES 12"	14 EA	1800.00	25200.00	3500.00	49000.00	1500.00	21000.00
0072	8328000000-E	450	PILE DRV EQUIP SETUP * PRESTR CONC PILES 16"	14 EA	2100.00	29400.00	5000.00	70000.00	1800.00	25200.00
0073	8329000000-E	450	12" PRESTR CONC PILES	630 LF	95.00	59850.00	66.75	42052.50	157.00	98910.00
0074	8333000000-E	450	16" PRESTR CONC PILES	630 LF	105.00	66150.00	72.00	45360.00	178.00	112140.00

TIP NO  
FED AID NO STATE FUNDED  
BRIDGE # 159 REPLACEMENT  
BRIDGE #159 OVER PUNGO SWAMP ON SR 1611

0.284 MI

				S T WOOTEN CORPORATION		DANE CONSTRUCTION INC		TRADER CONSTRUCTION CO		
				WILSON, NC		MOORESVILLE, NC		NEW BERN, NC		
0075	8393000000-N	450	PILE REDRIVES	16 EA	50.00	800.00	250.00	4000.00	750.00	12000.00
0076	8505000000-E	460	VERT CONC BARRIER RAIL	251 LF	115.00	28865.00	105.00	26355.00	130.00	32630.00
0077	8608000000-E	876	RIP RAP II (2'-0")	240 TON	85.00	20400.00	63.75	15300.00	120.00	28800.00
0078	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	270 SY	3.00	810.00	4.00	1080.00	3.00	810.00
0079	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum		6000.00		7500.00		12000.00
0080	8762000000-E	430	3'-0"X 1'-9"PRESTR SLABS	1,375 LF	145.00	199375.00	180.00	247500.00	125.00	171875.00
CONTRACT TOTAL					TOTAL	1204892.00	TOTAL	1316911.50	TOTAL	1408249.00
ROADWAY ITEMS					SUB-TOTAL	1204892.00	SUB-TOTAL	1316911.50	SUB-TOTAL	1408249.00

TIP NO  
FED AID NO STATE FUNDED  
BRIDGE # 159 REPLACEMENT  
BRIDGE #159 OVER PUNGO SWAMP ON SR 1611

0.284 MI

T A LOVING COMPANY

GOLDSBORO, NC

ROADWAY ITEMS

0001	0000100000-N	800	MOBILIZATION	Lump Sum		74000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		18000.00
0003	0030000000-N	SP	TYPE II MODIFIED APPR ***** 17+36.00	Lump Sum		34000.00
0004	0043000000-N	226	GRADING	Lump Sum		137635.48
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY	11.50	3450.00
0006	0194000000-E	265	SELECT GRANULAR MATL, CLASS III	300 CY	22.00	6600.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	300 SY	4.00	1200.00
0008	0318000000-E	300	FND CONDIT MATL MINOR STRS	20 TON	85.00	1700.00
0009	0320000000-E	300	FND CONDIT GEOTEXTILE	60 SY	4.00	240.00
0010	0448200000-E	310	15" RCP CULV CLASS IV	16 LF	95.00	1520.00
0011	0448400000-E	310	24" RCP CULV CLASS IV	156 LF	110.00	17160.00
0012	1330000000-E	607	INCIDENTAL MILLING	400 SY	25.00	10000.00
0013	1491000000-E	610	ASP CONC BASE CRS B25.0C	720 TON	81.40	58608.00
0014	1519000000-E	610	ASP CONC SURF CRS S9.5B	1,180 TON	82.90	97822.00
0015	1575000000-E	620	ASP FOR PLANT MIX	105 TON	620.00	65100.00
0016	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY	0.01	0.45
0017	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200 SY	0.01	2.00
0018	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	34 CY	0.01	0.34
0019	2044000000-E	815	6" PERF SUBDRN PIPE	200 LF	0.01	2.00
0020	2070000000-N	815	SUBDRN PIPE OUTLET	6 EA	0.01	0.06
0021	2077000000-E	815	6" OUTLET PIPE	1 LF	0.01	0.01
0022	2286000000-N	840	MASNRY DRAINAGE STRUCT	2 EA	2500.00	5000.00
0023	2367000000-N	840	FRAME W/2GRTS 840.29 STD	2 EA	700.00	1400.00
0024	2556000000-E	846	SHOULDER BERM GUTTER	130 LF	30.00	3900.00
0025	3030000000-E	862	STL BEAM GUARDRAIL	180 LF	18.00	3240.00
0026	3150000000-N	862	ADDIT GUARDRAIL POSTS	5 EA	11.00	55.00
0027	3195000000-N	862	GR END TYPE AT-1	3 EA	750.00	2250.00
0028	3215000000-N	SP	GR ANCHOR TYPE III	4 EA	1850.00	7400.00
0029	3288000000-N	SP	GR END TYPE TL-2	1 EA	3200.00	3200.00
0030	3578000000-N	SP	GENERIC FENCING ITEM (EA) RESET EXISTING GATE	2 EA	2300.00	4600.00
0031	3628000000-E	876	RIP RAP, CLASS I	40 TON	120.00	4800.00
0032	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	250 SY	4.00	1000.00
0033	5325600000-E	1510	6" WATER LINE	129 LF	157.00	20253.00
0034	5325800000-E	1510	8" WATER LINE	409 LF	50.00	20450.00
0035	5329000000-E	1510	DI H2O PIPE FITTINGS	340 LB	8.00	2720.00
0036	5540000000-E	1515	6" VALVE	2 EA	1595.00	3190.00
0037	5800000000-E	1530	ABANDON 6" UTILITY PIPE	537 LF	6.00	3222.00
0038	5872600000-E	1550	DIRECT DRILL *** 8"	409 LF	55.00	22495.00

TIP NO  
FED AID NO STATE FUNDED  
BRIDGE # 159 REPLACEMENT  
BRIDGE #159 OVER PUNGO SWAMP ON SR 1611

0.284 MI

T A LOVING COMPANY

GOLDSBORO, NC

0039	6000000000-E	1605 TEMPORARY SILT FENCE	1,900 LF	3.25	6175.00
0040	6006000000-E	1610 EROS CONTRL STONE CL A	90 TON	110.00	9900.00
0041	6009000000-E	1610 EROS CONTRL STONE CL B	70 TON	110.00	7700.00
0042	6012000000-E	1610 SEDIMENT CONTROL STONE	40 TON	85.00	3400.00
0043	6015000000-E	1615 TEMPORARY MULCHING	4 ACR	910.00	3640.00
0044	6018000000-E	1620 SEED FOR TEMP SEEDING	300 LB	4.65	1395.00
0045	6021000000-E	1620 FERT FOR TEMP SEEDING	1.5 TON	1200.00	1800.00
0046	6024000000-E	1622 TEMPORARY SLOPE DRAINS	200 LF	5.00	1000.00
0047	6029000000-E	SP SAFETY FENCE	1,600 LF	2.00	3200.00
0048	6030000000-E	1630 SILT EXCAVATION	70 CY	10.00	700.00
0049	6036000000-E	1631 MATTING FOR EROS CONTROL	1,400 SY	2.00	2800.00
0050	6037000000-E	SP COIR FIBER MAT	100 SY	5.00	500.00
0051	6042000000-E	1632 1/4" HARDWARE CLOTH	50 LF	5.00	250.00
0052	6048000000-E	SP FLOAT TURBIDITY CURTAIN	170 SY	15.00	2550.00
0053	6071012000-E	SP COIR FIBER WATTLE	320 LF	10.75	3440.00
0054	6071014000-E	SP COIR FIBER WATTLE BARRIER	100 LF	15.00	1500.00
0055	6071020000-E	SP POLYACRYLAMIDE (PAM)	30 LB	25.00	750.00
0056	6084000000-E	1660 SEEDING AND MULCHING	6 ACR	500.00	3000.00
0057	6090000000-E	1661 SEED FOR REPAIR SEEDING	3 LB	25.00	75.00
0058	6093000000-E	1661 FERT FOR REPAIR SEEDING	0.25 TON	1200.00	300.00
0059	6096000000-E	1662 SEED FOR SUPP SEEDING	100 LB	5.50	550.00
0060	6108000000-E	1665 FERTILIZER TOPDRESSING	3 TON	900.00	2700.00
0061	6117000000-N	SP RESPONSE FOR EROS CONTROL	13 EA	200.00	2600.00
0062	6117500000-N	SP CONC WASHOUT STRUCTURE	2 EA	100.00	200.00
0063	6123000000-E	1670 REFORESTATION	0.1 ACR	7500.00	750.00
0064	8035000000-N	402 REMV EXIST STR ***** 17+36.00	Lump Sum		37263.86
0065	8065000000-N	SP ASBESTOS ASSESSMENT	Lump Sum		2000.00
0066	8112730000-N	450 PDA TESTING	2 EA	1800.00	3600.00
0067	8121000000-N	412 UNCL STR EXCAV STA ***** 17+36.00	Lump Sum		20958.80
0068	8182000000-E	420 CLASS A CONCRETE (BRIDGE)	46 CY	3200.00	147200.00
0069	8210000000-N	422 BRG APPR SLAB ***** 17+36.00	Lump Sum		64000.00
0070	8217000000-E	425 REINF STEEL (BRIDGE)	8,472 LB	1.00	8472.00
0071	8328000000-E	450 PILE DRV EQUIP SETUP * PRESTR CONC PILES 12"	14 EA	4115.00	57610.00
0072	8328000000-E	450 PILE DRV EQUIP SETUP * PRESTR CONC PILES 16"	14 EA	4475.00	62650.00
0073	8329000000-E	450 12" PRESTR CONC PILES	630 LF	37.00	23310.00
0074	8333000000-E	450 16" PRESTR CONC PILES	630 LF	63.00	39690.00

TIP NO  
FED AID NO STATE FUNDED  
BRIDGE # 159 REPLACEMENT  
BRIDGE #159 OVER PUNGO SWAMP ON SR 1611

0.284 MI

---

T A LOVING COMPANY

GOLDSBORO, NC

---

0075	8393000000-N	450	PILE REDRIVES	16	EA	10.00	160.00
0076	8505000000-E	460	VERT CONC BARRIER RAIL	251	LF	160.00	40160.00
0077	8608000000-E	876	RIP RAP II (2'-0")	240	TON	60.00	14400.00
0078	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	270	SY	3.00	810.00
0079	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			7500.00
0080	8762000000-E	430	3'-0"X 1'-9"PRESTR SLABS	1,375	LF	195.00	268125.00

CONTRACT TOTAL TOTAL 1495000.00

ROADWAY ITEMS SUB-TOTAL 1495000.00

**BIDDERS IN ORDER**

**CONTRACT TOTAL**

S T WOOTEN CORPORATION	1	1204892.00
DANE CONSTRUCTION INC	2	1316911.50
TRADER CONSTRUCTION CO	3	1408249.00
T A LOVING COMPANY	4	1495000.00