

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

ROY COOPER GOVERNOR J. ERIC BOYETTE Secretary

September 17, 2021

| CONTRACT: | DB00513 |
|--------------|----------------------------------------------|
| WBS ELEMENT: | 2022CPT.02.05.20161 |
| COUNTY: | CARTERET |
| ROUTE: | VARIOUS |
| DESCRIPTION: | MILLING, STRENGTHENING, RESURFACING, AND |
| | SHOULDER RECONSTRUCTION OF VARIOUS ROUTES IN |
| | THE TOWN OF BEAUFORT IN CARTERET COUNTY |

ADDENDUM 1

TO: PROSPECTIVE BIDDERS

Please note the following revisions to the proposal.

- Removal of the resurfacing of SR 1170 and associated quantities from the project.
- Revise Intermediate Contract Time Numbers 2 and 3 to reflect revised map numbers.
- Revise Notes to Contractor to reflect revised map numbers.
- Addition of Shoulder Wedge Provision to the proposal.
- Revised Plans to remove the resurfacing of SR 1170 from the project and revise the existing map numbers.
- Please see attached page A1-A15.
- A revised electronic file has been uploaded to bid express named DB00513.001.

Sincerely,

DocuSigned by Mary Voelker Moore -714C11DCCEBC4C6...

Mary Voelker Moore, PE Division Contract Engineer cc: Ms. Mary Beth Houston, PE Mr. Jeremy Stroud, PE Mr. Brad McMannen, PE Ms. Heather Lane, PE Mr. Cadmus Capehart, PE Mr. Jeff Cabaniss, PE Sep 17, 2021 12:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. DB00513

Page 1 of 2

| Count | ty: Cart | 3 | A1 | | | CRAVEN |
|-----------|--------------|----------|-----------------------------------------------------------------------------------|---------------|-----------|--------|
| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
| | | | ROADWAY ITEMS | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| | 0262000000-N | SP | GENERIC GRADING ITEM HAULING NCDOT SUPPLIED SHOULDE R MATERIAL | 68 EA | | |
| 0003 | 1220000000-Е | 545 | INCIDENTAL STONE BASE | 103 TON | | |
| 0004 | 1245000000-Е | SP | SHOULDER RECONSTRUCTION | 3.38 SMI | | |
| 0005 | 1297000000-E | 607 | MILLING ASPHALT PAVEMENT, ***" DEPTH 1.75" MILLING | 77,000 SY | | |
| 0006 | 133000000-Е | 607 | INCIDENTAL MILLING | 1,600 SY | | |
| 0007 | 1503000000-Е | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C | 800 TON | | |
| 8000 | 151900000-Е | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 9,700 TON | | |
| 0009 | 1575000000-Е | 620 | ASPHALT BINDER FOR PLANT MIX | 689 TON | | |
| 0010 | 1880000000-E | SP | GENERIC PAVING ITEM 4" DEPTH MILL PATCHING EXISTIN G PAVEMENT - B 25.0 C | 150 TON | | |
| 0011 | 275200000-Е | SP | GENERIC PAVING ITEM 2'6" CURB & GUTTER - REMOVE/RE PLACE | 219 LF | | |
| | 275900000-N | SP | GENERIC PAVING ITEM CONCRETE CURB RAMP - REMOVE/RE PLACE | 14 EA | | |
| 0013 | 2830000000-N | 858 | ADJUSTMENT OF MANHOLES | 20 EA | | |
| 0014 | 2845000000-N | 858 | ADJUSTMENT OF METER BOXES OR VALVE BOXES | 4 EA | | |
| 0015 | 4413000000-Е | SP | WORK ZONE ADVANCE/GENERAL WARNING SIGNING | 400 SF | | |
| 0016 | 4457000000-N | SP | TEMPORARY TRAFFIC CONTROL | Lump Sum | L.S. | |
| 0017 | 600000000-Е | 1605 | TEMPORARY SILT FENCE | 660 LF | | |

| • | 7, 2021 12:16 pm y : Cartஹல(0513 | | ITEMIZED PROPOSAL FOR CONTR A2 | Page 2 of 2 CRAVEN | | | | |
|-----------|-------------------------------------|----------|-----------------------------------|-----------------------|-----------|--------|--|--|
| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount | | |
| | | | | | | | | |
| 0018 | 6071010000-E | SP | WATTLE | 120 LF | | | | |
| 0019 | 6084000000-Е | 1660 | SEEDING & MULCHING | 4.13 ACR | | | | |
| 0020 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 1 EA | | | | |

1216/Sep17/Q91557.51/D56159110000/E20

Total Amount Of Bid For Entire Project :

INTERMEDIATE CONTRACT TIME NUMBER 2 AND LIQUIDATED DAMAGES:

| (2-20-07) | 108 | SP1 G14 D |
|-----------|-----|-----------|
| | | |

The Contractor shall complete the required work of installing, maintaining and removing the traffic control devices for road closures and restoring traffic to the existing traffic pattern. The Contractor shall not close **Maps #2, #3, and #4** during the following time restrictions:

DAY AND TIME RESTRICTIONS

No Work Between Memorial Day and Labor Day

The time of availability for this intermediate contract time will be the time the Contractor begins to install traffic control devices required for road closures according to the time restrictions stated herein.

The completion time for this intermediate contract time will be the time the Contractor is required to complete the removal of traffic control devices required for the road closures according to the time restrictions stated herein and restore traffic to the existing traffic pattern.

The liquidated damages are **Eight Hundred Fifty Dollars** (\$ 850.00) per hour.

INTERMEDIATE CONTRACT TIME NUMBER 3 AND LIQUIDATED DAMAGES: (2-20-07) 108 SPI G14 C

The Contractor shall complete the required work of installing, maintaining and removing the traffic control devices for lane closures and restoring traffic to the existing traffic pattern. The Contractor shall not close or narrow a lane of traffic on **Map #1** during the following time restrictions:

DAY AND TIME RESTRICTIONS

One Hour Before School Starts to 30 Minutes After School Starts One Hour Before School Dismissal to 30 Minutes After School Dismissal Monday to Friday School Days Only

The time of availability for this intermediate contract time will be the time the Contractor begins to install traffic control devices required for the lane closures according to the time restrictions stated herein.

The completion time for this intermediate contract time will be the time the Contractor is required to complete the removal of traffic control devices required for the lane closures according to the time restrictions stated herein and restore traffic to the existing traffic pattern.

The liquidated damages are **Eight Hundred Fifty Dollars** (**\$ 850.00**) per hour

PERMANENT VEGETATION ESTABLISHMENT:

(2-16-12) (Rev. 10-15-13)

104

SP1 G16

Establish a permanent stand of the vegetation mixture shown in the contract. During the period between initial vegetation planting and final project acceptance, perform all work necessary to establish permanent vegetation on all erodible areas within the project limits, as well as, in borrow and waste pits. This work

PROJECT SPECIAL PROVISIONS

ROADWAY

NOTE TO CONTRACTOR

Map #3 (SR 1493) allows on-street parking. It is the Contractor's responsibility to ensure that these spaces are clear for paving.

Map #4 (SR 1493) includes the mill and fill of NC 101 from SR 1493 (Live Oak Street) north for approximately 300 feet.

All Concrete work, Drainage Structure Adjustments, Manhole Adjustments, and Valve Adjustments shall be performed before the final surface layer of asphalt is placed.

SHOULDER RECONSTRUCTION PER SHOULDER MILE:

(11-16-10) (Rev. 8-21-12)

560

SP1 R07AR (Rev)

Description

This work consists of reconstructing each shoulder (including median shoulders as applicable) in accordance with Standard Drawing No. 560.01 and 560.02 of the 2018 Roadway Standard Drawings except that the rate of slope and width will be as shown on typical section, or to the existing shoulder point, whichever is nearer, as long as the desired typical is achieved, and when completed, seeding and mulching. This work shall be performed immediately after the resurfacing operations are complete as directed by the Engineer.

This project will require the removal of excess material from the existing pavement by mechanical means prior to paving routes. Excess material generated by clipping excessive shoulder material from the existing pavement will be required to be removed by the Contractor. The Contractor should take care in removing excessive material from the existing pavement to minimize the amount of disturbance to adjacent established vegetation. There will be no direct payment for the removal of any excess material generated from the existing pavement as this work shall be considered incidental to the asphalt pavement line items that correspond with that map.

Quantities for Shoulder Reconstruction are included to address drop off issues identified by the Engineer after paving is completed. Shoulder Reconstruction shall not be performed unless directed by the Engineer.

Materials

The NCDOT will furnish all earth material necessary for the construction of the shoulders at the Carteret County Maintenance Yard located at 139 Masontown Road in Newport.

Hauling

SHOULDER WEDGE:

(9-20-11) (Rev. 8-21-12)

610


SP6 R03R

Revise the 2018 Standard Specifications as follows:


Page 6-21, Article 610-8, SPREADING AND FINISHING, add the following after line 39:


Attach a device, mounted on screed of paving equipment, capable of constructing a shoulder wedge with an angle of 30 degrees plus or minus 4 degrees along the outside edge of the roadway, measured from the horizontal plane in place after final compaction on the final surface course. Use an approved mechanical device which will form the asphalt mixture to produce a wedge with uniform texture, shape and density while automatically adjusting to varying heights.

Payment for use of this device will be incidental to the other pay items in the contract.




DB00513





| | PROJECT REFERENCE NO. DB005/BAVEN | SHEET NO. |
|------------------------------------------------------------------------|--------------------------------------|-----------|
| | DBOOSIKAVEIN | 2 |
| | | |
| PAVEMENT SCHEDULE | | |
| 1.5″ ASPHALT CONCRETE SURFACE COL RATE OF 165 LBS. PER SQ. YD. | JRSE, TYPE S9.5B | |
| 1.75″ ASPHALT CONCRETE SURFACE CO RATE OF 192.5 LBS. PER SQ. YD. | DURSE, TYPE S9.5B | |
| 2.5″ ASPHALT CONCRETE INTERMEDIAT T AN AVERAGE RATE OF 285 LBS. PER | E COURSE, SQ. YD. | |
| LLING. | | |
| 1.75" FOR THE ENTIRE WIDTH OF RO | ADWAY. | |
| NSTRUCTION. | | |
| RAWINGS NOT TO SCALE | | |




| PROJECT REFERENCE NO. | T SHEET NO. |
|-----------------------------------------------------------------------------------------|-------------|
| DBOOSISKAVEI | N 3 |
| | |
| PAVEMENT SCHEDULE | |
| 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B RATE OF 165 LBS. PER SQ. YD. | |
| 1.75" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B RATE OF 192.5 LBS. PER SQ. YD. | |
| 2.5" ASPHALT CONCRETE INTERMEDIATE COURSE, T AN AVERAGE RATE OF 285 LBS. PER SQ. YD. | |
| LLING. | |
| 1.75" FOR THE ENTIRE WIDTH OF ROADWAY. | |
| NSTRUCTION. | |
| RAWINGS NOT TO SCALE | |

SUMMARY OF QUANTITIES

| | | | | | | | | | | | 122000000-E | 124500000-E | | | 150300000-E | | | | | 2759000000-N | 283000000-N | 2845000000-N | | | | 6117000000-N | 4413000000-E | 4457000000- |
|------------------------------|----------------------------------|---------|----------------------------------------|----------------|--------|-----------|---------|------------|------|-------|-------------|----------------|---------------|------------|----------------|---------------|-----------|------------|----------------|----------------|-------------|---------------|------------|--------|----------|--------------|-----------------|-------------|
| PROJECT NO COUNTY | MAP NO ROUTE | | DESCRIPTION | TYP NO | | | | X LENGTH W | | JLING | INCIDENTAL | SHOULDER | 1.75" MILLING | | | | ASPHALT | 4" DEPTH | 2'6" CURB & | CONCRETE CURB | ADJ. OF | ADJ. OF METER | | WATTLE | SEED & | RESPONSE FOR | WORK ZONE | TEMPORAR |
| | | | | | TYP | E SURFACE | | | NC | | STONE BASE | RECONSTRUCTION | N | MILLING | COURSE, I19.0C | COURSE, S9.5B | | | GUTTER - | RAMP - | MANHOLES | OR VALVE BOX | SILT FENCE | | MULCHING | | ADVANCE/GENERAL | |
| | | | | | | TESTING | REQUIRE | D | | PLIED | | | | | | | PLANT MIX | | REMOVE/REPLACE | REMOVE/REPLACE | | | | | | CONTROL | WARNING SIGNING | CONTROL |
| | | | | | | REQUIRED | | | SHOU | | | | | | | | | EXISTING | | | | | | | | | | |
| | | | | | | | | | MAT | ERIAL | | | | | | | | PAVEMENT - | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | B 25.0 C | | | | | | | | | | |
| | | | | | | | | | | A | TONS | SMI | SY | SY | TONS | TONS | TONS | TON | LF | EA | EA | EA | LF | LF | AC | EA | SF | LS |
| 2022CPT.02.05.20161 Carteret | | AWAY RD | FROM NC 101 TO CAMPEN RD | 1 | 2 2WU | J NO | NO | | | 14 | 18 | 0.70 | | 500 | 800 | 500 | 72 | | | | | | 56 | 40 | 0.35 | | 40 | 0.07 |
| TOTAL | FOR MAP NO. 1 | | | | | | | 0.35 | 1 | 14 | 18 | 0.70 | | 500 | 800 | 500 | 72 | | | | | | 56 | 40 | 0.35 | | 40 | 0.07 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2022CPT.02.05.20161 Carteret | | ONT ST | FROM HILL ST TO SR 1310 LENNOXVILLE RD | 2 | 2 2WU | J NO | NO | 1.34 | | 54 | | 2.68 | | 300 | | 1,500 | 101 | 150 | | | 8 | 4 | 214 | 40 | 1.34 | | 150 | 0.28 |
| TOTAL | FOR MAP NO. 2 | | | | | | | 1.34 | 5 | 54 | | 2.68 | | 300 | | 1,500 | 101 | 150 | | | 8 | 4 | 214 | 40 | 1.34 | | 150 | 0.28 |
| | | | | | | | | | | | | | | | | | | | | 12 | | | | | | | 80 | |
| 2022CPT.02.05.20161 Carteret | 3 SR 1493 - CED FOR MAP NO. 3 | DARSI | FROM DEAD END TO SR 1493 LIVE OAK RD | 3,4 | 2 MU | NO | NO | | 40 | | | | 17,000 | 300 300 | | 1,700 | 114 | - | 53 53 | 12 | | | | | | | | 0.14 |
| TOTAL | FOR MAP NO. 3 | | | | | | | 0.70 | | | | | 17,000 | 300 | | 1,700 | 114 | | 53 | 12 | | | | | | | 80 | 0.14 |
| 2022CPT.02.05.20161 Carteret | 4 SR 1493 - LIVE (| OAKGT | FROM CEDAR ST TO SR 1472 PIVER RD | 3.4 | 2 MU | NO | NO | 2.44 | 35 | | 85 | | 60.000 | 500 | | 6.000 | 402 | | 166 | 2 | 12 | | 390 | 40 | 2.44 | | 130 | 0.51 |
| | 4 SK 1493 - LIVE V | UAK SI | FRONT CEDAR ST TO SR 1472 PIVER RD | 3,4 | 2 1010 | NU | NU | 2.44 | 30 | | 85 | | 60,000 | 500 | | 6,000 | 402 | | 166 | 2 | 12 | | 390 | 40 | 2.44 | 1 | 130 | 0.51 |
| TOTAL | FOR MAP NO. 4 | | | | | | | 4.83 | | 58 | 103 | 3 | 77,000 | 1,600 | 800 | 9,700 | 689 | 150 | 219 | 14 | 20 | 4 | 660 | 120 | 4 | 1 | 400 | 1.00 |
| TOTAL FOR PROJ | I NO. 2022CPT.02.05.20161 | H | | | | | | 4.65 | 0 | 56 | 105 | 3 | 77,000 | 1,600 | 800 | 9,700 | 089 | 150 | 219 | 14 | 20 | 4 | 000 | 120 | 4 | 1 | 400 | 1.00 |
| | | | | _ | I | | | | | | | | | | | | | 150 | | | | | | | | 1 | | |
| | | | | | | 1 | | 4.83 | 6 | 58 | 103 | 3.38 | 77,000 | 1,600 | 800 | 9,700 | 689 | 150 | 219 | 14 | 20 | 4 | 660 | 120 | 4.13 | 1 | 400 | 1 |
| GR | RAND TOTAL | - | | | | | | 4.05 | | | 105 | 5.50 | 77,000 | 1,000 | 000 | 5,700 | 005 | 150 | 215 | 14 | 20 | - | 000 | 120 | 4.15 | - | 400 | - |
| | | | | STA. | STA | WIDTH | MAP | | | | | | | 1 | | | 1 | 150 | | | | | | | | 1 1 | | 1 |
| | | - | 4" MILL PATCH | 0+10 | | 8' RT | 2 | - | | | | | | | | | | | | | | | | | | | | |
| | | - | 4 Miller Aren | 4+01 | | 8' RT | 2 | - | | | | | | | | | | | | | | | | | | | | |
| | | H | | 20+33 | | 8' RT | 2 | - | | | | | | | | | | | | | | | | | | | | |
| | | H | | 20.00 | 22.50 | 0 111 | - | - | | | | | | | | | | | | | | | | | | | | |
| | | H | | STA. | STA | LENGTH | MAP | - | | | | | | | | | | | | | | | | | | | | |
| | | H | CURB & GUTTER REPAIR | 6+13 | | 20' RT | 3 | - | | | | | | | | | | | | | | | | | | | | |
| | | H | COND & COTTENTIEL AIR | 25+47 | | 19' RT | 3 | - | | | | | | | | | | | | | | | | | | | | |
| | | F | | 25+47 | 25+61 | 14' LT | 3 | - | | | | | | | | | | | | | | | | | | | | |
| | | F | | 19+10 | | 8' LT | 4 | - | | | | | | | | | | | | | | | | | | | | |
| | | F | | | | 110' LT | 4 | - | | | | | | | | | | | | | | | | | | | | |
| | | F | | 26+10 26+53 | 26+84 | 31 RT | 4 | - | | | | | | | | | | | | | | | | | | | | |
| | | F | | 27+06 | | 17 RT | 4 | - | | | | | | | | | | | | | | | | | | | | |
| | | L | | 27.00 | | 47.01 | | | | | | | | | | | | | | | | | | | | | | |

CRAVEN

| PROJECT NO. | SHEET NO. | TOTAL NO. |
|-------------|-----------|-----------|
| DB00513 | 4 | |
| | | |




NOTE:

- 1. THE CONTRACTOR SHALL PERFORM ANY UNIFORM OR INCIDENTAL MILLING AT TIE-INS BEFORE PERFORMING THE 4" DEPTH MILL PATCHING.
- 2. THE CONTRACTOR SHALL PERFORM THE MILL PATCHING REMOVAL AND REPLACEMENT IN THE SAME DAY.
- 3. 4" DEPTH MILL PATCHING SHALL BE PERFORMED AT LOCATIONS AS SHOWN ON SHEET 4, AND AS DIRECTED BY THE ENGINEER.

| PROJECT REFERENCE DB09513 | |
|----------------------------------------------------------------------|-------|
| | |
| VEMENT SCHEDULE | |
| ASPHALT CONCRETE SURFACE COURSE, TYPE S OF 165.0 LBS. PER SQ. YD. | S9.5B |
| | |
| CHING W/ B 25.0C | |
| VINGS NOT TO SCALE | |


MILLING TYPICALS



DETAIL 1 BEGIN/END MAP TIE-IN




NOTE: MILLING SHALL BE PERFORMED AT MAIN LINE TIE-INS AND Y-LINE TIE-INS AS DIRECTED BY THE ENGINEER, IN ACCORDANCE WITH THIS DETAIL.



DETAIL 2 BRIDGE MILLING

NOTE:

MILLING SHALL BE PERFORMED AT THE BRIDGE APPROACHES AS DIRECTED 1. BY THE ENGINEER, IN ACCORDANCE WITH THIS DETAIL.




DETAIL 3 BRIDGE MILLING



1. INCLUDES MILLING FOR THE ENTIRE WIDTH OF THE BRIDGE WEARING SURFACE, AS DIRECTED BY THE ENGINEER

SHOULDER TYPICAL



NOTE:

- 1.
- 2. GENERATE BORROW MATERIAL WILL NOT BE ALLOWED.
- з. APPROVED DISPOSAL SITE.

RECONSTRUCTION

PROJECT REFEREN


DBOOSTRAVE


SHEET NC

DIV2-I


SHOULDER RECONSTRUCTION DETAIL

SHOULDERS SHALL BE RECONSTRUCTED AS SHOWN IN STD. DWG. NO. 560.01 & 560.02, WITH A MINIMUM SLOPE OF 1" PER FOOT TO ENSURE POSITIVE DRAINAGE AWAY FROM THE ROADWAY. A VEGETATIVE BUFFER SHALL BE MAINTAINED BETWEEN THE DISTURBED AREA ALONG THE EDGE OF PAVEMENT AND THE DITCH SHOULDER POINT TO MINIMIZE EROSION. PULLING DITCHES OR CUTTING SHOULDERS TO REQUIRED BORROW MATERIAL MAY BE OBTAINED FROM NCDOT STOCKPILES. ANY EXCESS MATERIAL SHALL BE DISPOSED OF BY THE CONTRACTOR IN AN






| | PROJECT REFERENCE NO. DBOOSBAVEN | sheet no. EC-1 |
|------------------------|-------------------------------------|-------------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| < 5' - 10' Undisturbed | buffer from | |
| ditchline, add BMP | | |
| - | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| Area | | |
| | | |
| | | |
| | | |
| | | |
| • | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| <u></u> | | |
|)P | | |
| | | |
| | | |
| | NOT TO SCAL | <u> </u> |
| | | |



DB00513





RESURFACING ADVANCE WARNING SIGNS FOR RURAL AND SUBURBAN 2 LANE ROADWAYS