TIP NO BP2-R015 0.108 MILES
FED AID NO STATE FUNDED
GRADING, DRAINAGE, PAVING, AND SRUCTURE
BRIDGE 160131 OVER OLD MILL CREEK ON SR 1718 (SINDEY ROAD)

						T A LOVING COMPANY GOLDSBORO, NC		TRADER CONSTRUCTION CO NEW BERN, NC		S T WOOTEN CORPORATION WILSON, NC	
			ROADWAY ITEMS								
0001	0000100000-N	800	MOBILIZATION	Lump Sum			63,000.00		66,500.00		68,000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum			10,000.00		28,000.00		16,250.00
0003	0008000000-E	200	SUPP CLEARING & GRUBBING	1	ACR	530.00	530.00	100.00	100.00	1.00	1.00
0004	0036000000-E	225	UNDERCUT EXCAVATION	300	CY	0.01	3.00	40.00	12,000.00	10.00	3,000.00
0005	0043000000-N	226	GRADING (226)	Lump Sum			127,212.79		78,000.00		120,000.00
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	300	CY	0.01	3.00	75.00	22,500.00	15.00	4,500.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	300	SY	0.01	3.00	4.00	1,200.00	1.00	300.00
0008	0223000000-E	275	ROCK PLATING	310	SY	121.00	37,510.00	150.00	46,500.00	93.00	28,830.00
0009	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE 1 BRIDGE APPROACH FILL, STATION 15+86.00 -L-	Lump Sum			35,000.00		47,500.00		26,000.00
0010	0318000000-E	300	FND CONDIT MATL MINOR STRS	10	TON	87.40	874.00	85.00	850.00	140.00	1,400.00
0011	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	20	SY	3.00	60.00	5.00	100.00	1.00	20.00
0012	0335200000-E	305	15" DRAINAGE PIPE	20	LF	68.75	1,375.00	90.00	1,800.00	280.00	5,600.00
0013	0448200000-E	310	15" RCP CULV CLASS IV	32	LF	103.25	3,304.00	120.00	3,840.00	260.00	8,320.00
0014	1121000000-E	520	AGGREGATE BASE COURSE	15	TON	77.00	1,155.00	90.00	1,350.00	160.00	2,400.00
0015	1330000000-E	607	INCIDENTAL MILLING	260	SY	38.00	9,880.00	38.00	9,880.00	9.00	2,340.00
0016	1491000000-E	610	ASP CONC BASE CRS B25.0C	450	TON	85.00	38,250.00	85.00	38,250.00	150.00	67,500.00
0017	1519000000-E	610	ASP CONC SURF CRS S9.5B	350	TON	140.00	49,000.00	140.00	49,000.00	125.00	43,750.00
0018	1575000000-E	620	ASP FOR PLANT MIX	50	TON	800.00	40,000.00	800.00	40,000.00	725.00	36,250.00
0019	2022000000-E	815	SUBDRAIN EXCAVATION	44.8	CY	0.01	0.45	12.00	537.60	5.00	224.00
0020	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200	SY	0.01	2.00	2.00	400.00	1.00	200.00
0021	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6	CY	0.01	0.34	65.00	2,184.00	5.00	168.00
0022	2044000000-E	815	6" PERF SUBDRN PIPE	200	LF	0.01	2.00	5.00	1,000.00	5.00	1,000.00
0023	2070000000-N	815	SUBDRN PIPE OUTLET	1	EA	0.01	0.01	85.00	85.00	40.00	40.00
0024	2077000000-E	815	6" OUTLET PIPE	6	LF	0.01	0.06	10.00	60.00	5.00	30.00
0025	2286000000-N	840	MASNRY DRAINAGE STRUCT	2	EA	3,670.00	7,340.00	6,500.00	13,000.00	8,000.00	16,000.00
0026	2367000000-N	840	FRAME W/2GRTS 840.29 STD	2	EA	1,195.00	2,390.00	1,200.00	2,400.00	1,300.00	2,600.00
0027	2556000000-E	846	SHOULDER BERM GUTTER	90	LF	75.00	6,750.00	145.00	13,050.00	100.00	9,000.00
0028	3030000000-E	862	STL BEAM GUARDRAIL	450	LF	25.50	11,475.00	25.50	11,475.00	25.50	11,475.00
0029	3150000000-N	862	ADDIT GUARDRAIL POSTS	5	EA	11.00	55.00	11.00	55.00	11.00	55.00
0030	3215000000-N	862	GR ANCHOR TYPE III	4	EA	2,350.00	9,400.00	2,350.00	9,400.00	2,350.00	9,400.00
0031	3287000000-N	862	GR END TYPE TL-3	4	EA	3,250.00	13,000.00	3,250.00	13,000.00	3,250.00	13,000.00
0032	3635000000-E	876	RIP RAP, CLASS II	195	TON	110.00	21,450.00	150.00	29,250.00	50.00	9,750.00
0033	3649000000-E	876	RIP RAP, CLASS B	56	TON	87.00	4,872.00	135.00	7,560.00	115.00	6,440.00
0034	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	475	SY	3.00	1,425.00	5.00	2,375.00	1.00	475.00
0035	4400000000-E	1110	WORK ZONE SIGNS (STAT)	386	SF	6.75	2,605.50	6.75	2,605.50	6.75	2,605.50
0036	4410000000-E	1110	WORK ZONE SIGNS (BARR)	94	SF	7.15	672.10	7.15	672.10	7.15	672.10
0037	4420000000-N	1120	PORTABLE CHANGE MSG SIGN	1	EA	5,200.00	5,200.00	6,615.00	6,615.00	21,000.00	21,000.00
0038	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	21.00	1,680.00	21.00	1,680.00	21.00	1,680.00
0039	6000000000-E	1605	TEMPORARY SILT FENCE	860	LF	4.25	3,655.00	4.00	3,440.00	3.99	3,431.40
0040	6006000000-E	1610	EROS CONTRL STONE CL A	65	TON	77.50	5,037.50	120.00	7,800.00	50.00	3,250.00

TIP NO BP2-R015 0.108 MILES
FED AID NO STATE FUNDED
GRADING, DRAINAGE, PAVING, AND SRUCTURE
BRIDGE 160131 OVER OLD MILL CREEK ON SR 1718 (SINDEY ROAD)

						T A LOVING COMPANY GOLDSBORO, NC		TRADER CONSTRUCTION CO NEW BERN, NC		S T WOOTEN CORPORATION WILSON, NC	
0041	6009000000-E	1610	EROS CONTRL STONE CL B	25	TON	93.00	2,325.00	124.00	3,100.00	115.00	2,875.00
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	55	TON	69.00	3,795.00	80.00	4,400.00	50.00	2,750.00
0043	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	2,160.00	4,320.00	2,250.00	4,500.00	225.00	450.00
0044	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	6.00	1,200.00	8.85	1,770.00	8.85	1,770.00
0045	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	1,120.00	1,120.00	1,675.00	1,675.00	1,675.00	1,675.00
0046	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	1.00	200.00	28.00	5,600.00	5.00	1,000.00
0047	6029000000-E	SP	SAFETY FENCE	660	LF	3.50	2,310.00	3.90	2,574.00	3.89	2,567.40
0048	6030000000-E	1630	SILT EXCAVATION	30	CY	12.40	372.00	35.00	1,050.00	30.00	900.00
0049	6036000000-E	1631	MATTING FOR EROS CONTROL	1,600	SY	3.00	4,800.00	2.50	4,000.00	2.15	3,440.00
0050	6037000000-E	1629	COIR FIBER MAT	100	SY	7.45	745.00	6.95	695.00	6.95	695.00
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	55	LF	7.30	401.50	7.85	431.75	7.85	431.75
0052	6048000000-E	SP	FLOAT TURBIDITY CURTAIN	150	SY	32.03	4,804.50	45.00	6,750.00	85.00	12,750.00
0053	6070000000-N	1639	SPECIAL STILLING BASINS	2	EA	1,000.00	2,000.00	670.00	1,340.00	900.00	1,800.00
0054	6071002000-E	1642	FLOCCULANT	5	LB	16.00	80.00	25.00	125.00	20.00	100.00
0055	6071012000-E	1642	COIR FIBER WATTLE	150	LF	9.50	1,425.00	13.75	2,062.50	13.75	2,062.50
0056	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	100.00	300.00	1,000.00	3,000.00	100.00	300.00
0057	6087000000-E	1660	MOWING	3	ACR	250.00	750.00	400.00	1,200.00	40.00	120.00
0058	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	6.50	325.00	27.65	1,382.50	28.00	1,400.00
0059	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1,120.00	280.00	1,650.00	412.50	1,650.00	412.50
0060	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	6.25	312.50	15.00	750.00	15.00	750.00
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	1,120.00	1,400.00	1,750.00	2,187.50	1,750.00	2,187.50
0062	6111000000-E	SP	IMPERVIOUS DIKE	179	LF	145.00	25,955.00	160.00	28,640.00	200.00	35,800.00
0063	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	135.00	1,350.00	85.00	850.00	85.00	850.00
0064	6117000000-N	1675	RESPONSE FOR EROS CONTROL	13	EA	1.00	13.00	1.00	13.00	1.00	13.00
0065	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	250.00	250.00	1,015.00	1,015.00	2,000.00	2,000.00
0066	6123000000-E	1670	REFORESTATION	0.1	ACR	5,000.00	500.00	10,000.00	1,000.00	10,000.00	1,000.00
0067	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	2	EA	500.00	1,000.00	1,015.00	2,030.00	2,000.00	4,000.00
			STRUCTURE ITEMS								
0068	8035000000-N	402	REMV EXIST STR ****** BRG (402) (15+86.00 -L-)	Lump Sum			100,000.00		50,000.00		91,000.00
0069	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			2,100.00		2,100.00		1,000.00
0070	8121000000-N	412	UNCL STR EXCAV STA ***** (15+86.00 -L-)	Lump Sum			25,000.00		8,500.00		50,000.00
0071	8175000000-E	420	CLASS AA CONC (BRIDGE)	43.2	CY	3,000.00	129,600.00	1,800.00	77,760.00	2,000.00	86,400.00
0072	8210000000-N	422	BRG APPR SLAB ********** (15+86.00 -L-)	Lump Sum			60,000.00		54,500.00		50,000.00
0073	8224000000-E	425	EPOXY COAT REINF STL BRDG	5,188	LB	2.00	10,376.00	3.25	16,861.00	4.00	20,752.00
0074	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES (HP 12x53)	14	EA	5,800.00	81,200.00	6,650.00	93,100.00	2,000.00	28,000.00
0075	8364000000-E	450	HP12X53 PILES	980	LF	65.00	63,700.00	115.00	112,700.00	115.00	112,700.00
0076	8393000000-N	450	PILE REDRIVES	7	EA	10.00	70.00	900.00	6,300.00	50.00	350.00
0077	8394000000-N	450	DYNAMIC PILE TESTING	2	EA	3,000.00	6,000.00	3,500.00	7,000.00	3,000.00	6,000.00

BP2.R015.3

TIP NO BP2-R015 0.108 MILES
FED AID NO STATE FUNDED
GRADING, DRAINAGE, PAVING, AND SRUCTURE
BRIDGE 160131 OVER OLD MILL CREEK ON SR 1718 (SINDEY ROAD)

						T A LOVING COMPANY GOLDSBORO, NC		TRADER CONSTRUCTION CO NEW BERN, NC		S T WOOTEN CORPORATION WILSON, NC	
0078	8505000000-E	460	VERT CONC BARRIER RAIL	110.25	LF	375.00	41,343.75	275.00	30,318.75	320.00	35,280.00
0079	8608000000-E	876	RIP RAP II (2'-0")	130	TON	110.00	14,300.00	185.00	24,050.00	175.00	22,750.00
0080	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	140	SY	2.00	280.00	5.50	770.00	1.00	140.00
0081	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			5,000.00		1,200.00		3,500.00
0082	8762000000-E	430	3'-0"X 1'-9"PRESTR SLABS	605	LF	325.00	196,625.00	310.00	187,550.00	345.00	208,725.00
			CONTRACT TOTAL			TOTAL	1,312,100.00	TOTAL	1,331,277.70	TOTAL	1,347,653.65
			ROADWAY ITEMS			SUB-TOTAL	576,505.25	SUB-TOTAL	658,567.95	SUB-TOTAL	631,056.65
			STRUCTURE ITEMS			SUB-TOTAL	735,594.75	SUB-TOTAL	672,709.75	SUB-TOTAL	716,597.00

BIDDERS IN ORDER		**CONTRACT TOTAL**
T A LOVING COMPANY	1	1,312,100.00
TRADER CONSTRUCTION CO	2	1,331,277.70
S T WOOTEN CORPORATION	3	1,347,653.65



09/24/2026