


STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.2.C.6	1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS


LENOIR COUNTY

**LOCATION: PIPE REPLACEMENT ON SR 1143 (LIDDELL ROAD)
0.6 MILES EAST OF SR 1154 (BURNCOAT ROAD)
STRUCTURE NUMBER 53 2067**

TYPE OF WORK: PIPE REPLACEMENT, PAVING AND GRADING




VICINITY MAP
(NOT TO SCALE)
See Sheet 1-A For Index of Sheets



DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

PROJECT: 17BP.2.C.6

CONTRACT: DB00313



PROJECT LENGTH

LENGTH ROADWAY PROJECT 17BP.2.C.6 = 0.014 mi

Prepared in the Office of:
DIVISION OF HIGHWAYS
1704 North Greene Street Greenville, NC 27835

2012 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE: WILLIAM C KINCANNON, PE
PROJECT ENGINEER


LETTING DATE: JOSH WILDER
PROJECT DESIGN ENGINEER
SEPTEMBER 2016

HYDRAULICS ENGINEER



DocuSigned by:
William C Kincannon 9/8/2016
SIGNATURE

ROADWAY DESIGN ENGINEER

DocuSigned by:
William C Kincannon 9/8/2016
SIGNATURE



08-SEP-2016 09:45 G:\PROJECTS\LENOIR\LENOIR2067\Lenoir2067_pshl.dgn \$\$\$\$USERNAME\$\$\$\$ 09/08/16

PROJECT REFERENCE NO.		SHEET NO.	
17BP.2.C.6		1A	
R/W SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
			
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED			

INDEX OF SHEETS

1	TITLE SHEET
1A	INDEX OF SHEETS, GENERAL NOTES, STANDARD DRAWINGS
1B	CONVENTIONAL SYMBOLS
2	TYPICAL SECTIONS
3	SUMMARY OF QUANTITIES
3A	SUMMARY OF DRAINAGE AND EARTHWORK QUANTITIES
4	PLAN AND PROFILE SHEET
UC1-UC4	UTILITY CONSTRUCTION
TMP1-TMP2	TRAFFIC MANAGEMENT PLANS
EC1-EC4	EROSION CONTROL SHEETS
X1A	CROSS-SECTION SUMMARY
X1	CROSS-SECTIONS

GENERAL NOTES:

2012 SPECIFICATIONS
EFFECTIVE: 01-17-2012
REVISED: 07-30-2012

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE DEEP RUN WATER CORP.
CONTACT MR JAMIE CANNON 252-568-3006.
CENTURY LINK

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS, EXCEPT AS SHOWN ON THE PLANS.

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY OTHERS.

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	Method of Clearing - Method II
225.02	Guide for Grading Subgrade - Secondary and Local
DIVISION 3 - PIPE CULVERTS	
300.01	Method of Pipe Installation

STATE OF NORTH CAROLINA, DIVISION OF HIGHWAYS

CONVENTIONAL PLAN SHEET SYMBOLS

Note: Not to Scale *S.U.E. = *Subsurface Utility Engineering*

04/05/15

BOUNDARIES AND PROPERTY:

State Line	-----
County Line	-----
Township Line	-----
City Line	-----
Reservation Line	-----
Property Line	-----
Existing Iron Pin	○ EIP
Property Corner	----->
Property Monument	□ EDM
Parcel/Sequence Number	⑫③
Existing Fence Line	-x-x-x-
Proposed Woven Wire Fence	○
Proposed Chain Link Fence	□
Proposed Barbed Wire Fence	◇
Existing Wetland Boundary	----- WLB
Proposed Wetland Boundary	----- WLB
Existing Endangered Animal Boundary	----- EAB
Existing Endangered Plant Boundary	----- EPB
Existing Historic Property Boundary	----- HPB
Known Contamination Area: Soil	-----
Potential Contamination Area: Soil	-----
Known Contamination Area: Water	-----
Potential Contamination Area: Water	-----
Contaminated Site: Known or Potential	☠ ?

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	○
Sign	○ S
Well	○ W
Small Mine	✕
Foundation	□
Area Outline	□
Cemetery	□
Building	□
School	□
Church	□
Dam	□

HYDROLOGY:

Stream or Body of Water	-----
Hydro, Pool or Reservoir	-----
Jurisdictional Stream	----- JS
Buffer Zone 1	----- BZ 1
Buffer Zone 2	----- BZ 2
Flow Arrow	←
Disappearing Stream	-----
Spring	○
Wetland	-----
Proposed Lateral, Tail, Head Ditch	-----
False Sump	-----

RAILROADS:

Standard Gauge	-----
RR Signal Milepost	○ MILEPOST 35
Switch	□ SWITCH
RR Abandoned	-----
RR Dismantled	-----

RIGHT OF WAY:

Baseline Control Point	◆
Existing Right of Way Marker	△
Existing Right of Way Line	-----
Proposed Right of Way Line	-----
Proposed Right of Way Line with Iron Pin and Cap Marker	-----
Proposed Right of Way Line with Concrete or Granite R/W Marker	-----
Proposed Control of Access Line with Concrete CA Marker	-----
Existing Control of Access	-----
Proposed Control of Access	-----
Existing Easement Line	----- E
Proposed Temporary Construction Easement	----- E
Proposed Temporary Drainage Easement	----- TDE
Proposed Permanent Drainage Easement	----- PDE
Proposed Permanent Drainage / Utility Easement	----- DUE
Proposed Permanent Utility Easement	----- PUE
Proposed Temporary Utility Easement	----- TUE
Proposed Aerial Utility Easement	----- AUE
Proposed Permanent Easement with Iron Pin and Cap Marker	-----

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	-----
Existing Curb	-----
Proposed Slope Stakes Cut	----- C
Proposed Slope Stakes Fill	----- F
Proposed Curb Ramp	----- CR
Existing Metal Guardrail	-----
Proposed Guardrail	-----
Existing Cable Guiderail	-----
Proposed Cable Guiderail	-----
Equality Symbol	⊕
Pavement Removal	-----

VEGETATION:

Single Tree	☼
Single Shrub	☼
Hedge	-----
Woods Line	-----

Orchard	☼ ☼ ☼ ☼
Vineyard	□ Vineyard

EXISTING STRUCTURES:

MAJOR:	
Bridge, Tunnel or Box Culvert	----- CONC
Bridge Wing Wall, Head Wall and End Wall	----- CONC WW
MINOR:	
Head and End Wall	----- CONC HW
Pipe Culvert	-----
Footbridge	-----
Drainage Box: Catch Basin, DI or JB	□ CB
Paved Ditch Gutter	-----
Storm Sewer Manhole	⊙
Storm Sewer	----- S

UTILITIES:

POWER:	
Existing Power Pole	●
Proposed Power Pole	○
Existing Joint Use Pole	●
Proposed Joint Use Pole	○
Power Manhole	⊙
Power Line Tower	⊠
Power Transformer	⊠
U/G Power Cable Hand Hole	●
H-Frame Pole	●
U/G Power Line LOS B (S.U.E.*)	----- P
U/G Power Line LOS C (S.U.E.*)	----- P
U/G Power Line LOS D (S.U.E.*)	----- P

TELEPHONE:

Existing Telephone Pole	●
Proposed Telephone Pole	○
Telephone Manhole	⊙
Telephone Pedestal	⊠
Telephone Cell Tower	⊠
U/G Telephone Cable Hand Hole	●
U/G Telephone Cable LOS B (S.U.E.*)	----- T
U/G Telephone Cable LOS C (S.U.E.*)	----- T
U/G Telephone Cable LOS D (S.U.E.*)	----- T
U/G Telephone Conduit LOS B (S.U.E.*)	----- TC
U/G Telephone Conduit LOS C (S.U.E.*)	----- TC
U/G Telephone Conduit LOS D (S.U.E.*)	----- TC
U/G Fiber Optics Cable LOS B (S.U.E.*)	----- T FO
U/G Fiber Optics Cable LOS C (S.U.E.*)	----- T FO
U/G Fiber Optics Cable LOS D (S.U.E.*)	----- T FO

WATER:

Water Manhole	⊙
Water Meter	○
Water Valve	⊗
Water Hydrant	⊕
U/G Water Line LOS B (S.U.E.*)	----- W
U/G Water Line LOS C (S.U.E.*)	----- W
U/G Water Line LOS D (S.U.E.*)	----- W
Above Ground Water Line	----- A/G Water

TV:

TV Pedestal	⊠
TV Tower	⊗
U/G TV Cable Hand Hole	⊠
U/G TV Cable LOS B (S.U.E.*)	----- TV
U/G TV Cable LOS C (S.U.E.*)	----- TV
U/G TV Cable LOS D (S.U.E.*)	----- TV
U/G Fiber Optic Cable LOS B (S.U.E.*)	----- TV FO
U/G Fiber Optic Cable LOS C (S.U.E.*)	----- TV FO
U/G Fiber Optic Cable LOS D (S.U.E.*)	----- TV FO

GAS:

Gas Valve	◇
Gas Meter	⊕
U/G Gas Line LOS B (S.U.E.*)	----- G
U/G Gas Line LOS C (S.U.E.*)	----- G
U/G Gas Line LOS D (S.U.E.*)	----- G
Above Ground Gas Line	----- A/G Gas

SANITARY SEWER:


Sanitary Sewer Manhole	⊙
Sanitary Sewer Cleanout	⊕
U/G Sanitary Sewer Line	----- SS
Above Ground Sanitary Sewer	----- A/G Sanitary Sewer
SS Forced Main Line LOS B (S.U.E.*)	----- FSS
SS Forced Main Line LOS C (S.U.E.*)	----- FSS
SS Forced Main Line LOS D (S.U.E.*)	----- FSS

MISCELLANEOUS:


Utility Pole	●
Utility Pole with Base	⊠
Utility Located Object	○
Utility Traffic Signal Box	⊠
Utility Unknown U/G Line LOS B (S.U.E.*)	----- ?U/L
U/G Tank; Water, Gas, Oil	□
Underground Storage Tank, Approx. Loc.	⊠ UST
A/G Tank; Water, Gas, Oil	□
Geoenvironmental Boring	⊕
U/G Test Hole LOS A (S.U.E.*)	⊕
Abandoned According to Utility Records	AATUR
End of Information	E.O.I.

C1	PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 165 LBS. PER SQ.YD. IN EACH OF 2 LAYERS.
E1	PROP. APPROX. 5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 570 LBS. PER SQ.YD.
J	VARIABLE DEPTH AGGREGATE BASE COURSE
I	EARTH MATERIAL.
U	PAVEMENT REMOVAL.
V	FILTER FABRIC
Y	#57 WASHED STONE


NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.



TYPICAL SECTION (NTS)
-L- STATION 14+87.21 - 15+62.29



TYPICAL BOX CULVERT SECTION (NTS)
-L- STATION 15+24.62



TYPICAL BOX CULVERT SECTION (NTS)
-L- STATION 15+24.62

REVISIONS

8/17/99
08-SEP-2016 09:40:01 P:\LENDIR2067\Lenoir2067_psi2.dgn
338411581

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

SECT	QUANTITY	UNIT	ITEM DESCRIPTION
800	1	LS	MOBILIZATION
801	1	LS	CONSTRUCTION SURVEYING
226	1	LS	GRADING
226	100	CY	UNDERCUT EXCAVATION
520	200	TON	AGGREGATE BASE COURSE
610	35	TON	ASPHALT CONCRETE SURFACE COURSE,TYPE SF9.5A
620	50	TON	ASPHALT CONCRETE BASE COURSE,TYPE B250B
620	5	TON	ASPHALT BINDER FOR PLANT MIX,GRADE PG64-22
862	2	EA	STEEL BEAM GUARDRAIL OVER LOW FILL CULVERT (STD 862.01)
862	4	EA	GUARDRAIL ANCHOR UNITS,TYPE 350
876	245	SY	GEOTEXTILE FOR DRAINAGE
1005	200	TON	*57 STONE
1605	100	LF	TEMPORARY SILT FENCE
SP	100	LF	SAFETY FENCE (AS DIRECTED BY THE ENGINEER)
1615	0.5	ACRE	TEMPORARY MULCHING
1620	50	LB	SEED FOR TEMPORARY SEEDING
1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
1630	10	CY	SILT EXCAVATION
1632	260	SY	MATTING FOR EROSION CONTROL
1660	1	ACRE	SEEDING AND MULCHING
1661	50	LB	SEED FOR REPAIR SEEDING
1661	0.2	TON	FERTILIZER FOR REPAIR SEEDING
SP	3	EA	RESPONSE FOR EROSION CONTROL
SP	60	LF	COIR FIBER WATTLE
SP	1	LS	2 @ 45' - TWIN 87' - SPAN X 63' RISE,10 GA,3"x1" CORRUGATED ALUMINUM ARCH PIPE -L- STA 15+24.62
SP	1	LS	RELOCATE EXISTING 6" WATER MAIN
SP	75	LF	IMPERVIOUS DIKE
SP	1	LS	DEWATERING

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

LIST OF PIPES, ENDWALLS, ETC.

STATION	LOCATION (L, RT, OR CL)	STRUCTURE NO.	TOP ELEVATION	INVERT ELEVATION	INVERT ELEVATION	SLOPE CRITICAL	R.C. PIPE (CLASS III)							PIPE REMOVAL LIN. FT.	ALUMINUM BOX CULVERT
							15"	18"	24"	30"	36"	42"	48"		
-L- 15+24.62	CL			96.39	96.39	0.0%									TWIN 87" SPAN X 63" RISE 10 GA. 3" X 1" CORRUGATED ALUMINUM PIPE ARCH FULLY WELDED TO ALUMINUM STRUCTURAL PLATE HEADWALL WITH 2" WIDE BANDS & 2" WIDE FLAT GASKET
TOTALS															2 @ 45'

NOTE: Invert Elevations are for Bid Purposes only and shall not be used for project construction stakeout. See "Standard Specifications For Roads and Structures, Section 300-5".

**SUMMARY OF EARTHWORK
IN CUBIC YARDS**

LOCATION	UNCLASSIFIED EXCAVATION	BOX CULVERT EXCAVATION	UNDERCUT	EMBT+%	BORROW	WASTE
-L- 14+87.21 - 15+62.29	59		0	11	0	48
UNDERCUT (CONTINGENCY)			100	120	120	100
UNCLASSIFIED STRUCTURE EXCAVATION		892		1000	108	0
SUB TOTAL	59	892	100	1131	228	148
SAY	65	895	105	1135	230	150

**PAVEMENT REMOVAL SUMMARY
IN SQUARE YARDS**

LINE	STATION - STATION	LOCATION	REMOVAL (SY)
-L-	14+87.21 - 15+62.29	CL	170
TOTAL			170
SAY			175

NOTE:
APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, UNCLASSIFIED STRUCTURE EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING."


GUARDRAIL SUMMARY

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL.
TOTAL SHOULDER WIDTH = DISTANCE FROM EDGE OF TRAVEL LANE TO SHOULDER BREAK POINT.
FLARE LENGTH = DISTANCE FROM LAST SECTION OF PARALLEL GUARDRAIL TO END OF GUARDRAIL.
W = TOTAL WIDTH OF FLARE FROM BEGINNING OF TAPER TO END OF GUARDRAIL.
G = GATING IMPACT ATTENUATOR TYPE 350
NG = NON-GATING IMPACT ATTENUATOR TYPE 350

SURVEY LINE	BEG. STA.	END STA.	LOCATION	LENGTH			WARRANT POINT		"N" DIST. FROM E.O.L.	TOTAL SHOULDER WIDTH	FLARE LENGTH		W		ANCHORS							IMPACT ATTENUATOR TYPE 350	REMARKS				
				STRAIGHT	SHOP CURVED	DOUBLE FACED	APPROACH END	TRAILING END			APPROACH END	TRAILING END	APPROACH END	TRAILING END	TYPE 350												
-L-	14+25.33	16+24.62	LT	100			16+24.62	14+25.33	3	4	50	50	1	1	2												
-L-	14+23.89	16+24.62	RT	100			14+23.89	16+24.62	3	4	50	50	1	1	2												
TOTAL				200											4												

REVISIONS

8/17/99
08-SEP-2016 09:51:50 J:\PROJECTS\2067\Lenoir\2067_psl_3a.dgn




-L- PROFILE
 SCALE: 1" = 20' HORIZ.
 1" = 4' VERT.

BEGIN GRADE
 -L- STATION 14+87.21
 ELEV 104.72

CL STATION 15+24.62
 1 @ TWIN 87" SPAN X 63" RISE
 10 GA 3"x11" ABC 45'
 CL RDWY ELEVATION 104.78'
 PIPE INVERT 96.39'
 SLOPE 0%

END GRADE
 -L- STATION 15+62.29
 ELEV 104.85



REVISIONS

8/17/99





08-SEP-2016 01:55:01P:\LENDR2067\Lenor2067_pst4.dgn

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

**UTILITY CONSTRUCTION PLANS
LENOIR COUNTY**

**LOCATION: PIPE REPLACEMENT ON SR 1143 (LIDDELL ROAD)
0.6 MILES EAST OF SR 1154 (BURN COAT ROAD)
TYPE OF WORK: WATER MAIN RELOCATION**


TIP PROJECT: 17BP.2.C.6



INDEX OF SHEETS

SHEET NO.	DESCRIPTION
UC-1	TITLE SHEET
UC-2	SUMMARY OF QUANTITIES
UC-3	UTILITY CONSTRUCTION SHEET
UC-4	DETAILS SHEET


WATER OWNER ON PROJECT
DEEP RUN WATER CORP - WATER



PREPARED IN THE OFFICE OF:
**DIVISION OF HIGHWAYS
DIVISION 2 - DDC**

P.O. BOX 1587
GREENVILLE, NC 27835
PHONE (252) 439-2800
FAX (252) 830-3352

WILLIAM C. KINCANNON, P.E. UTILITIES ENGINEER
JOSH WILDER UTILITIES PROJECT DESIGNER




UTILITY CONSTRUCTION

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS SUMMARY OF QUANTITIES

REVISIONS


<u>WATER MAIN</u>	<u>QUANTITY</u>	<u>UNIT</u>	<u>ITEM DESCRIPTION</u>
	40	LF	6" DI PIPE - PC 350 (AWWA C600)
	377	LF	8" HDPE PIPE - DR9 (AWWA C906)
	2	EA	6" GATE VALVE AND VALVE BOX
	2	EA	DI PIPE TO HDPE TRANSITION
	2	EA	CONCRETE THRUST COLLAR
	381	LF	REMOVE 6" UTILITY PIPE
	375	LF	TEMPORARY SILT FENCE
	0.5	ACRES	SEEDING AND MULCHING

NOTE:
MAINTAIN SERVICE TO THE
RESIDENCE ON PARCEL 1
DURING CONSTRUCTION



NOTE:
INSTALL WATER VALVES PRIOR
TO DRILL TO MINIMIZE
SERVICE INTERRUPTIONS


-WM- PROFILE
SCALE: 1" = 20' HORIZ
1" = 4' VERT.




REVISIONS

8/17/99

C:\Users\206_0844\OneDrive\Lenoir\2067\Lenoir-2067.dgn
 8/17/2016 10:58:58 AM




UTILITY CONSTRUCTION DETAILS SHEET




TYPICAL VALVE BOX
 NTS

- NOTES:
1. ONLY MANUFACTURED VALVE BOX EXTENSIONS SHALL BE ALLOWED.
 2. VALVE OPERATING NUT MUST BE EXTENDED SO THAT THE DEPTH IS NO GREATER THAN 5" (ft.) FROM THE SURFACE USING A MANUFACTURER APPROVED EXTENSION KIT.
 3. PRECAST CONCRETE ENCASEMENT IS ALLOWED OUTSIDE OF PAVED AREAS.




TYPICAL VALVE BOX
 NTS

- NOTES:
1. VALVE BOX COVER SHALL WEIGH A MINIMUM 26 lbs.
 2. ENTIRE VALVE BOX ASSEMBLY & COVER SHALL BE CAST FROM CLASS 35 GRAY IRON.
 3. ASSEMBLY SHALL BE DOMESTICALLY MADE AND MANUFACTURED IN THE U.S.A.




TYPICAL RESILIENT MECHANICAL
 JOINT GATE VALVE DETAIL
 NTS



TYPICAL BEDDING FOR FLEXIBLE & SEMI-RIGID PIPE
 NTS

- NOTES:
1. EMBEDMENT MATERIAL MUST BE CLASS I (NO. 67 OR NO. 78M WASHED STONE IS TYPICALLY USED).
 2. EMBEDMENT MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% STANDARD PROCTOR DENSITY FOR CLASS I MATERIAL.
 3. STANDARD BEDDING SHALL BE UTILIZED FOR ALL CASES WHERE TRENCH BOTTOMS ARE UNSTABLE DUE TO SOIL TYPE, OR MOISTURE CONDITIONS.



ANCHOR RING DIMENSIONS		
NOMINAL PIPE SIZE	O.D. OF RINGS	THICKNESS
4" - 12"	PIPE O.D. + 6"	1/2"
16" - 24"	PIPE O.D. + 7"	3/4"
30" & 36"	PIPE O.D. + 8"	1"

TYPICAL DIP TO HDPE TRANSITION DETAIL WITH THRUST COLLAR
 NTS

BEARING AREA AGAINST UNDISTURBED EARTH MUST EQUAL 7 S.F.
 ANSI/AWWA STANDARD MJ GLAND AND GASKETS W/ EXTENDED BOLTS PER MJ FITTING MANUFACTURER



REVISIONS

8/17/99
 I:\Projects\2016\1848\ENGR\LENDIR2067\LenDir2067.dgn
 9:58 AM 8/17/2016

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

TRANSPORTATION MANAGEMENT PLAN

LENOIR COUNTY



INDEX OF SHEETS

SHEET NO.	TITLE
TMP-1	TITLE SHEET WITH VICINITY MAP & INDEX OF SHEETS, LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, AND LEGEND.
TMP-2	PROJECT NOTES, DETOUR AND PLANS.

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS"-HIGHWAY DESIGN BRANCH-N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C. DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.03 (SHT. 1 OF 9)	TEMPORARY ROAD CLOSURES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1145.01	BARRICADES (TYPE III)

LEGEND


GENERAL

- DIRECTION OF TRAFFIC FLOW
- DIRECTION OF PEDESTRIAN TRAFFIC FLOW
- NORTH ARROW
- PROPOSED PVMT.
- EXIST. PVMT.
- WORK AREA

TRAFFIC CONTROL DEVICES

- BARRICADE (TYPE III)

08-SEP-2016 08:20 C:\PROJECTS\LENOIR\LENOIR2067\Lenoir2067_Tmpl.dgn



N.C.D.O.T. WORK ZONE TRAFFIC CONTROL
P.O. BOX 1587, GREENVILLE, NC 27835
105 PACTOLUS HWY. (NC 33), GREENVILLE, NC 27835
PHONE: (252) 830-3490 FAX: (252) 830-3352

W. C. KINCANNON, PE **TRAFFIC ENGINEER**
W. C. KINCANNON, PE **TRAFFIC CONTROL PROJECT ENGINEER**
JOSH WILDER **TRAFFIC CONTROL PROJECT DESIGN ENGINEER**
JOSH WILDER **TRAFFIC CONTROL DESIGN ENGINEER**



APPROVED:
DATE: 9/8/2016

SEAL



SHEET NO.
TMP-1

17BP.2.C.6





STATE PROJECT:

GENERAL NOTES

IMPLEMENT TRAFFIC CONTROL IN ACCORDANCE WITH THE ROADWAY STANDARD DRAWINGS LISTED ON TMP-1.


CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS, OR RESULT IN DUPLICATE, OR UNDESIRED OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING OR REMOVAL OF DEVICES, AS DIRECTED BY THE ENGINEER.

STATE FORCES WILL INSTALL AND MAINTAIN THE PROJECT DETOUR AND THE TYPE III BARRICADES AT THE PROJECT LIMITS. STATE FORCES WILL INSTALL PAINT AND MARKERS ON THE FINISHED PROJECT. CALL JIM EVANS AT 252-830-3493 FOR COORDINATION.




APPROVED: *William C. Kingannon* DATE: 9/8/2016

SEAL





TIP PROJECT: 17BP.2.C.6



See Sheet 1-A For Index of Sheets

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
**PLAN FOR PROPOSED
HIGHWAY EROSION CONTROL**

**LOCATION: PIPE REPLACEMENT ON SR 1143 (LIDDELL ROAD)
0.6 MILES EAST OF SR 1154 (BURNCOAT ROAD)
STRUCTURE NUMBER 53 2067**




STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.2.C.6	EC-1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	

EROSION AND SEDIMENT CONTROL MEASURES

Std. #	Description	Symbol
1630.05	Temporary Silt Ditch	TD
1630.05	Temporary Diversion	TD
1605.01	Temporary Silt Fence	III III III
1606.01	Special Sediment Control Fence	▲▲▲▲▲
1622.01	Temporary Berms and Slope Drains	T
1630.02	Silt Basin Type B	▨
1633.01	Temporary Rock Silt Check Type-A	▨
	Temporary Rock Silt Check Type-A with Matting and Polyacrylamide (PAM)	▨
1633.02	Temporary Rock Silt Check Type-B	▨
	Wattle / Coir Fiber Wattle	W
	Wattle / Coir Fiber Wattle with Polyacrylamide (PAM)	W
1634.01	Temporary Rock Sediment Dam Type-A	▨
1634.02	Temporary Rock Sediment Dam Type-B	▨
1635.01	Rock Pipe Inlet Sediment Trap Type-A	U
1635.02	Rock Pipe Inlet Sediment Trap Type-B	U
1630.04	Stilling Basin	▭
1630.06	Special Stilling Basin	▭
	Rock Inlet Sediment Trap:	
1632.01	Type A	A
1632.02	Type B	B
1632.03	Type C	C
	Skimmer Basin	▭
	Tiered Skimmer Basin	▭
	Infiltration Basin	▭

**THIS PROJECT CONTAINS
EROSION CONTROL PLANS
FOR CLEARING AND
GRUBBING PHASE OF
CONSTRUCTION.**

**THIS PROJECT HAS
BEEN DESIGNED TO
SENSITIVE WATERSHED
STANDARDS.**



ROADSIDE ENVIRONMENTAL UNIT
DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

**THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY
WITH THE REGULATIONS SET FORTH BY THE
NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011
ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND
NATURAL RESOURCES DIVISION OF WATER QUALITY.**

2012 STANDARD SPECIFICATIONS

Prepared In the Office of:
DIVISION 2 DDC
1704 NORTH GREENE STREET
GREENVILLE, NC 27835

Josh Wilder
Level III
Certification #3332


Roadway Standard Drawings

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N. C. Department of Transportation - Raleigh, N. C., dated January 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.



1604.01 Railroad Erosion Control Detail	1632.01 Rock Inlet Sediment Trap Type A
1605.01 Temporary Silt Fence	1632.02 Rock Inlet Sediment Trap Type B
1606.01 Special Sediment Control Fence	1632.03 Rock Inlet Sediment Trap Type C
1607.01 Gravel Construction Entrance	1633.01 Temporary Rock Silt Check Type A
1622.01 Temporary Berms and Slope Drains	1633.02 Temporary Rock Silt Check Type B
1630.01 Riser Basin	1634.01 Temporary Rock Sediment Dam Type A
1630.02 Silt Basin Type B	1634.02 Temporary Rock Sediment Dam Type B
1630.03 Temporary Silt Ditch	1635.01 Rock Pipe Inlet Sediment Trap Type A
1630.04 Stilling Basin	1635.02 Rock Pipe Inlet Sediment Trap Type B
1630.05 Temporary Diversion	1640.01 Coir Fiber Baffle
1630.06 Special Stilling Basin	1645.01 Temporary Stream Crossing
1631.01 Matting Installation	

08-SEP-2016 08:24
G:\PROJECTS\17BP.2.C.6\17BP.2.C.6.ec1.dgn
###USER NAME###

8/17/99



PI Sta. 12+91.11
 $\Delta = 20^\circ 29' 24.2''$ (RT)
 $D = 5' 32'' 06.0''$
 $L = 370.19'$
 $T = 187.09'$
 $R = 1,035.16'$



SOIL STABILIZATION TIMEFRAMES

SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HOW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HOW ZONES.

Std. #	Description	Symbol
1605.01	Temporary Silt Fence	
1632.03	Rock Inlet Sediment Trap Type C	
SP	Wattle with Polyacrylamide	
SP	Wattle	
	Ditch Flow Line	


NOTE: THE CONTRACTOR SHALL INSTALL WATTLES IN LOW AREAS OF SILT FENCE AS NEEDED OR AS DIRECTED BY THE ENGINEER.

NOTES: ANY DEVIATION FROM OPTIONS GIVEN WILL REQUIRE PRIOR APPROVAL BY ENGINEER.
 ADDITIONAL EROSION CONTROL DEVICES MAY NEED TO BE INSTALLED AS DIRECTED BY THE ENGINEER.
 CONTRACTOR SHALL INSTALL SPECIAL SEDIMENT CONTROL FENCE OR WATTLES IN LOW AREAS OF SILT FENCE AS NEEDED OR DIRECTED BY THE ENGINEER.


REVISIONS

08-SEP-2016 09:16:16 J:\PROJECTS\17BP.2.C.6\17BP.2.C.6.dgn

SILT FENCE WATTLE BREAK DETAIL



ISOMETRIC VIEW





VIEW FROM SLOPE

NOTES:

- USE MINIMUM 12 IN. DIAMETER EXCELSIOR WATTLE AND LENGTH OF 10 FT.
- EXCAVATE A 1 TO 2 INCH TRENCH FOR WATTLE TO BE PLACED.
- DO NOT PLACE WATTLE ON TOE OF SLOPE.
- USE 2 FT. WOODEN STAKES WITH A 2 IN. BY 2 IN. NOMINAL CROSS SECTION.
- INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO GROUND.
- PROVIDE STAPLES MADE OF 0.125 IN. DIAMETER STEEL WIRE FORMED INTO A U SHAPE NOT LESS THAN 12" IN LENGTH.
- INSTALL STAPLES APPROXIMATELY EVERY 1 LINEAR FOOT ON BOTH SIDES OF WATTLE AND AT EACH END TO SECURE IT TO THE SOIL.
- WATTLE INSTALLATION CAN BE ON OUTSIDE OF THE SILT FENCE AS DIRECTED.
- INSTALL TEMPORARY SILT FENCE IN ACCORDANCE WITH SECTION 1605 OF THE STANDARD SPECIFICATIONS.

INSET A



SIDE VIEW

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION TIMEFRAMES

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.


NOTE: Approximate quantities only. Unclassified excavation, Borrow Excavation, Fine Grading, Clearing and Grubbing, Removal of Existing Pavement and Breaking of Existing Pavement will be paid for at the contract Lump Sum price for "Grading".

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
CROSS-SECTION SUMMARY
IN CUBIC YARDS

LOCATION (-L-)	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBANKMENT	STRUCTURE EXCAVATION
14+87.21	0	0	0	0
15+07.87	16	0	3	169
15+24.62	13	0	3	275
15+41.37	13	0	3	276
15+62.29	17	0	2	172

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT.

NOTE:
APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION,
UNCLASSIFIED STRUCTURE EXCAVATION, BORROW EXCAVATION,
FINE GRADING, CLEARING AND GRUBBING AND REMOVAL OF
EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP
SUM PRICE FOR "GRADING."



110	105	100	110	105	100	95	90	110	105	100	95	90	110	105	100	95	90	110	105	100	95	90	110	105	100	95	90
-----	-----	-----	-----	-----	-----	----	----	-----	-----	-----	----	----	-----	-----	-----	----	----	-----	-----	-----	----	----	-----	-----	-----	----	----

DENOTES STRUCTURE EXCAVATION

