



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

October 6, 2014

CONTRACT: DB00203
WBS ELEMENT: 45332.3.5
TIP: W-5202E
FA NUMBER: HSIP-0043(19)
COUNTY: Pitt
ROUTE: NC 43
DESCRIPTION: Widening, Grading, Paving, and Drainage of NC 43 from Blue Banks Rd to Aaron Circle

ADDENDUM NUMBER 1

TO: Prospective Bidders

Please note the following revisions to the proposal for the above referenced project.

- Remove "Construction Surveying" from bid items. See attached for the revised list of bid items. Surveying will be performed by NCDOT.
- Replace Contract Time and Liquidated Damages special provision with the attached provision.
- Add attached Intermediate Contract Time Number 2 and Liquidated Damages.
- Add attached Permanent Vegetation Establishment special provision.

If electing to use the Computer Bid Preparation process, the Expedite File has been updated to reflect these revisions. Please download the Expedite Addendum File and follow the instructions for applying the addendum.

The Contractor's bid must be based on these revised pay item quantities. The contract will be prepared accordingly.

Sincerely,

A handwritten signature in black ink, appearing to read "Sarah Lentine".

Sarah Lentine
Division Contract Officer

cc: Mr. Ed Eatmon, PE
Ms. Maria Rogerson, PE
Mr. Bill Kincannon, PE

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0004	0255000000-E	SP	GENERIC GRADING ITEM AGGREGATE SHOULDER BORROW	4,250 TON		
0005	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	490 TON		
0006	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	1,540 SY		
0007	0335000000-E	305	*** DRAINAGE PIPE 15"	180 LF		
0008	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	1,106 LF		
0009	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	1,223 LF		
0010	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	195 LF		
0011	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	55 LF		
0012	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	76 LF		
0013	0995000000-E	340	PIPE REMOVAL	278 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
0015	1245000000-E	SP	SHOULDER RECONSTRUCTION	11.6 SMI		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,750 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,050 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,500 TON		
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	540 TON		
0020	2209000000-E	838	ENDWALLS	3.6 CY		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	34 EA		
0022	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	9 EA		
0023	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	25 EA		
0024	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	3,170 LF		
0025	3628000000-E	876	RIP RAP, CLASS I	30 TON		
0026	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	55 SY		
0027	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0028	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	86.02 SF		
0029	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	66,100 LF		
0030	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	65,000 LF		
0031	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	1,200 LF		
0032	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	38 EA		
0033	5912000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING 6" WATER MAI N	Lump Sum	L.S.	
0034	6000000000-E	1605	TEMPORARY SILT FENCE	3,900 LF		
0035	6012000000-E	1610	SEDIMENT CONTROL STONE	40 TON		
0036	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0037	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.6 TON		
0038	6042000000-E	1632	1/4" HARDWARE CLOTH	1,500 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	6071010000-E	SP	WATTLE	225		
					LF	
0040	6071020000-E	SP	POLYACRYLAMIDE (PAM)	8		
					LB	
0041	6084000000-E	1660	SEEDING & MULCHING	1		
					ACR	
0042	6090000000-E	1661	SEED FOR REPAIR SEEDING	50		
					LB	
0043	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.2		
					TON	
0044	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	4		
					EA	

1143/Oct06/Q161908.02/D132306130000/E43

Total Amount Of Bid For Entire Project :

CONTRACT TIME AND LIQUIDATED DAMAGES:

(4-17-12)

108

SP1 G07 C

The date of availability for this contract is **December 1, 2014**.

The completion date for this contract is **October 29, 2015**.

Except where otherwise provided by the contract, observation periods required by the contract will not be a part of the work to be completed by the completion date and/or intermediate contract times stated in the contract. The acceptable completion of the observation periods that extend beyond the final completion date shall be a part of the work covered by the performance and payment bonds.

The liquidated damages for this contract are **Seven Hundred Fifty Dollars (\$750.00)** per calendar day. These liquidated damages will not be cumulative with any liquidated damages which may become chargeable under Intermediate Contract Time Number 2.

INTERMEDIATE CONTRACT TIME NUMBER 2 AND LIQUIDATED DAMAGES:

(7-1-95) (Rev. 2-21-12)

108

SP1 G13 A

Except for that work required under the Project Special Provisions entitled *Planting, Reforestation* and/or *Permanent Vegetation Establishment*, included elsewhere in this proposal, the Contractor will be required to complete all work included in this contract and shall place and maintain traffic on same.

The date of availability for this intermediate contract time is **July 31, 2015**.

The completion date for this intermediate contract time is **October 29, 2015**.

The liquidated damages for this intermediate contract time are **Two Hundred Fifty Dollars (\$250.00)** per calendar day.

Upon apparent completion of all the work required to be completed by this intermediate date, a final inspection will be held in accordance with Article 105-17 and upon acceptance, the Department will assume responsibility for the maintenance of all work except *Planting, Reforestation* and/or *Permanent Vegetation Establishment*. The Contractor will be responsible for and shall make corrections of all damages to the completed roadway caused by his planting operations, whether occurring prior to or after placing traffic through the project.

PERMANENT VEGETATION ESTABLISHMENT:

(2-16-12) (Rev. 10-15-13)

104

SP1 G16

Establish a permanent stand of the vegetation mixture shown in the contract. During the period between initial vegetation planting and final project acceptance, perform all work necessary to establish permanent vegetation on all erodible areas within the project limits, as well as, in borrow and waste pits. This work shall include erosion control device maintenance and installation, repair seeding and mulching, supplemental seeding and mulching, mowing, and fertilizer topdressing, as directed. All work shall be performed in accordance with the applicable section of the *2012 Standard Specifications*. All work required for initial vegetation planting shall be performed as a part of the work necessary for the completion and acceptance of the Intermediate Contract Time (ICT). Between the time of ICT and Final Project acceptance, or otherwise referred to as the vegetation establishment period, the Department will be responsible for preparing the required National Pollutant Discharge Elimination System (NPDES) inspection records.

Once the Engineer has determined that the permanent vegetation establishment requirement has been achieved at an 80% vegetation density (the amount of established vegetation per given area to stabilize the soil) and no erodible areas exist within the project limits, the Contractor will be notified to remove the remaining erosion control devices that are no longer needed. The Contractor will be responsible for, and shall correct any areas disturbed by operations performed in permanent vegetation establishment and the removal of temporary erosion control measures, whether occurring prior to or after placing traffic on the project.

Payment for *Response for Erosion Control, Seeding and Mulching, Repair Seeding, Supplemental Seeding, Mowing, Fertilizer Topdressing, Silt Excavation, and Stone for Erosion Control* will be made at contract unit prices for the affected items. Work required that is not represented by contract line items will be paid in accordance with Articles 104-7 or 104-3 of the *2012 Standard Specifications*. No additional compensation will be made for maintenance and removal of temporary erosion control items.