

# STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

October 20, 2014

CONTRACT: DB00203
WBS ELEMENT: 45332.3.5
TIP: W-5202E
FA NUMBER: HSIP-0043(19)

COUNTY: Pitt ROUTE: NC 43

DESCRIPTION: Widening, Grading, Paving, and Drainage of NC 43 from Blue Banks Rd to

TELEPHONE: (252) 439-2800

FAX: (252) 830-3325

WEBSITE: WWW.NCDOT.GOV

Aaron Circle

**ADDENDUM NUMBER 2** 

TO: Prospective Bidders

Please note the following revisions to the proposal for the above referenced project.

• Add attached Shoulder Reconstruction per Shoulder Mile special provision.

The contract will be prepared accordingly.

Sincerely,

Sarah Lentine

**Division Contract Officer** 

LOCATION:

1704 N GREENE ST

GREENVILLE, NC

cc: Mr. Ed Eatmon, PE

Ms. Maria Rogerson, PE Mr. Bill Kincannon, PE

## SHOULDER RECONSTRUCTION PER SHOULDER MILE:

(1-18-00) (Rev. 8-21-12) 560 SP1 R07AR (Revised)

## **Description**

This work consists of reconstructing each shoulder (including median shoulders as applicable) in accordance with Standard Drawing No. 560.01 and 560.02 of the 2012 Roadway Standard Drawings except that the rate of slope and width will be as shown on typical section, or to the existing shoulder point, whichever is nearer, as long as the desired typical is achieved, and when completed, seeding and mulching. This work shall be performed immediately after the resurfacing operations are complete as directed by the Engineer.

#### **Materials**

The Contractor **shall use** Aggregate Shoulder Borrow (ASB) which meets the following gradation on **all maps**.

<u>Sieve</u>	Percent Passing
1 1/2"	100
1/2"	55 - 95
#4	35 - 74

### **Construction Methods**

Obtain material from approved source. Material shall be compacted to the satisfaction of the Engineer.

Any excess material generated by the shoulder reconstruction shall be disposed of by the Contractor in an approved disposal site.

## **Measurement and Payment**

Shoulder Reconstruction will be measured and paid as the actual number of miles of shoulders that have been reconstructed. Measurement will be made along the surface of each shoulder to the nearest 0.01 of a mile. Such price will include disposing of any excess material in an approved disposal site, and for all labor, tools, equipment, and incidentals necessary to complete the work.

Aggregate Shoulder Borrow will be measured and paid at the contract unit price per ton.

Incidental Stone Base will be measured and paid as provided in Article 545-6 of the 2012 Standard Specifications. If ASB is used for Incidental Stone Base, payment will be made for **Aggregate Shoulder Borrow** as referenced above.

Where ASB is used, seeding and mulching will not be required.

Payment will be made under:

Pay Item
Shoulder Reconstruction
Aggregate Shoulder Borrow

Pay Unit Shoulder Mile Ton