



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

November 7, 2022

CONTRACT: DB00544
WBS ELEMENT: 2BP.R020.3
COUNTY: CRAVEN
ROUTE: SR 1700
DESCRIPTION: DRAINAGE, GRADING, PAVING, AND CULVERT
CONSTRUCTION ON SR 1700 IN CRAVEN COUNTY

ADDENDUM 4

TO: PROSPECTIVE BIDDERS

Please note the following revisions to the proposal.

- Removal of Line Item #10 and #11. Please see attached pages AAAA1-AAAA7.
- A revised electronic file has been uploaded to bid express named DB00544.002.

Please make sure to sign the addendum page in the proposal to acknowledge this addendum.

Sincerely,

DocuSigned by:
Mary Voelker Moore
714C11DCCEBC4C6...

Mary Voelker Moore, PE
Division Contract Engineer

cc: Mr. Michael Aman, PE
Mr. Jordan Scott, PE
Ms. Heather C. Lane, PE
Mr. Brad McMannen, PE

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION 2
PROJECT DEVELOPMENT GROUP
GREENVILLE, NC 27834

Telephone: (252) 439-2828
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
1037 W.H. SMITH BLVD.
GREENVILLE, NC 27834

Mr. Cadmus Capehart, PE
Mr. Hon Yeung, PE

County: CRAVEN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0036000000-E	225	UNDERCUT EXCAVATION	300 CY		
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	600 SY		
0007	0199000000-E	SP	TEMPORARY SHORING	1,542 SF		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	42 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	130 SY		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	92 LF		
0013	0995000000-E	340	PIPE REMOVAL	192 LF		
0014	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0015	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	190 TON		
0016	1121000000-E	520	AGGREGATE BASE COURSE	730 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0018	1275000000-E	600	PRIME COAT	720 GAL		
0019	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1.5" DEPTH)	100 SY		

County: CRAVEN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1330000000-E	607	INCIDENTAL MILLING	260 SY		
0021	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	700 TON		
0022	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	430 TON		
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	690 TON		
0024	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	105 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0026	2022000000-E	815	SUBDRAIN EXCAVATION	448 CY		
0027	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	2,000 SY		
0028	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	336 CY		
0029	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,000 LF		
0030	2070000000-N	815	SUBDRAIN PIPE OUTLET	4 EA		
0031	2077000000-E	815	6" OUTLET PIPE	24 LF		
0032	2264000000-E	840	PIPE PLUGS	1 CY		
0033	2275000000-E	SP	FLOWABLE FILL	30 CY		
0034	2612000000-E	848	6" CONCRETE DRIVEWAY	30 SY		
0035	3030000000-E	862	STEEL BEAM GUARDRAIL	950 LF		
0036	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	100 LF		

County: CRAVEN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0038	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0039	3210000000-N	862	GUARDRAIL END UNITS, TYPE CAT-1	1 EA		
0040	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	2 EA		
0041	3635000000-E	876	RIP RAP, CLASS II	60 TON		
0042	3649000000-E	876	RIP RAP, CLASS B	6 TON		
0043	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	575 SY		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	172 SF		
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	10 SF		
0046	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0047	4424500000-N	SP	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	1 EA		
0048	4430000000-N	1130	DRUMS	265 EA		
0049	4445000000-E	1145	BARRICADES (TYPE III)	12 LF		
0050	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	8 EA		
0051	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	1,369 LF		
0052	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM 4' X 12' STEEL ROAD PLATE	1 EA		
0053	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM 6' X 20' STEEL ROAD PLATE	1 EA		

County: CRAVEN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM 8' X 20' STEEL ROAD PLATE	1 EA		
0055	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,415 LF		
0056	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	96 LF		
0057	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,000 LF		
0058	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	96 LF		
0059	5328000000-E	1510	30" WATER LINE	680 LF		
0060	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	440 LB		
0061	5606000000-E	1515	2" BLOW OFF	2 EA		
0062	5678600000-E	1515	8" LINE STOP	2 EA		
0063	5801000000-E	1530	ABANDON 8" UTILITY PIPE	670 LF		
0064	5872600000-E	1550	DIRECTIONAL DRILLING OF *** (8" WATER LINE)	566 LF		
0065	6000000000-E	1605	TEMPORARY SILT FENCE	4,055 LF		
0066	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0067	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	185 TON		
0068	6012000000-E	1610	SEDIMENT CONTROL STONE	165 TON		
0069	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0070	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		

County: CRAVEN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0072	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0073	6029000000-E	SP	SAFETY FENCE	1,720 LF		
0074	6030000000-E	1630	SILT EXCAVATION	230 CY		
0075	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,200 SY		
0076	6037000000-E	SP	COIR FIBER MAT	480 SY		
0077	6042000000-E	1632	1/4" HARDWARE CLOTH	10 LF		
0078	6045000000-E	SP	*** TEMPORARY PIPE (12")	59 LF		
0079	6045000000-E	SP	*** TEMPORARY PIPE (24")	235 LF		
0080	6070000000-N	1639	SPECIAL STILLING BASINS	4 EA		
0081	6071013000-E	SP	WATTLE BARRIER	290 LF		
0082	6071020000-E	SP	POLYACRYLAMIDE (PAM)	100 LB		
0083	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0084	6087000000-E	1660	MOWING	3 ACR		
0085	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0086	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0087	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

County: CRAVEN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0089	6111000000-E	SP	IMPERVIOUS DIKE	150 LF		
0090	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0091	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0092	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0093	6123000000-E	1670	REFORESTATION	0.1 ACR		
CULVERT						
0094	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+34.00 -L-)	Lump Sum	L.S.	
0095	8126000000-N	414	CULVERT EXCAVATION, STA ***** (16+34.00 -L-)	Lump Sum	L.S.	
0096	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT (FOUNDATION COND. MAT'L.)	134 TON		
0097	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	11.2 CY		
0098	8248000000-E	425	EPOXY COATED REINFORCING STEEL (CULVERT)	1,492 LB		
0099	8804000000-N	SP	GENERIC CULVERT ITEM 31'-1" X 9'-2" ALUMINUM BOX CULVERT	Lump Sum	L.S.	
0100	8818000000-E	SP	GENERIC CULVERT ITEM CULVERT BACKFILL (#57 STONE)	1,163 TON		
WALL ITEMS						
0101	8847000000-E	SP	GENERIC RETAINING WALL ITEM GALVANIZED SHEET PILE RETAINING WALLS	16,327 SF		

County: CRAVEN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
1501/Nov07/Q62363.8/D413396033000/E99			Total Amount Of Bid For Entire Project :			
