

BP2.R020.3

TIP NO

0.398 MILES

FED AID NO STATE FUNDED

DRAINAGE, GRADING, PAVING, AND CULVERT


SR 1700 (ADAMS CREEK ROAD) OVER CLUB FOOT CREEK

TRADER CONSTRUCTION CO
NEW BERN, NC

MOUNTAIN CREEK CONTRACTORS
INC
MT PLEASANT, SC

ROADWAY

Item No	Code	Quantity	Description	Unit	TRADER CONSTRUCTION CO	MOUNTAIN CREEK CONTRACTORS INC	Total
0001	0000100000-N	800	MOBILIZATION		Lump Sum	145,000.00	207,000.00
0002	0036000000-E	225	UNDERCUT EXCAVATION	300 CY	76.50	22,950.00	60.00 18,000.00
0003	0043000000-N	226	GRADING		Lump Sum	215,000.00	400,000.00
0004	0050000000-E	226	SUPP CLEARING & GRUBBING	1 ACR	100.00	100.00	100.00 100.00
0005	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY	42.00	12,600.00	70.00 21,000.00
0006	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	600 SY	3.00	1,800.00	3.00 1,800.00
0007	0199000000-E	SP	TEMPORARY SHORING	1,542 SF	2.00	3,084.00	95.00 146,490.00
0008	0318000000-E	300	FND CONDIT MATL MINOR STRS	42 TON	70.00	2,940.00	70.00 2,940.00
0009	0320000000-E	300	FND CONDIT GEOTEXTILE	130 SY	2.50	325.00	3.50 455.00
0012	0344000000-E	310	18" SIDE DRAIN PIPE	92 LF	50.00	4,600.00	80.00 7,360.00
0013	0995000000-E	340	PIPE REMOVAL	192 LF	25.00	4,800.00	50.00 9,600.00
0014	1099500000-E	505	SHALLOW UNDERCUT	100 CY	76.50	7,650.00	25.00 2,500.00
0015	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	190 TON	101.50	19,285.00	60.00 11,400.00
0016	1121000000-E	520	AGGREGATE BASE COURSE	730 TON	80.00	58,400.00	60.00 43,800.00
0017	1220000000-E	545	INCIDENTAL STONE BASE	20 TON	50.00	1,000.00	55.00 1,100.00
0018	1275000000-E	600	PRIME COAT	720 GAL	13.50	9,720.00	14.50 10,440.00
0019	1297000000-E	607	MILL ASP PVMT ***** DTH (1.5" DEPTH)	100 SY	12.95	1,295.00	48.00 4,800.00
0020	1330000000-E	607	INCIDENTAL MILLING	260 SY	24.95	6,487.00	24.00 6,240.00
0021	1491000000-E	610	ASP CONC BASE CRS B25.0C	700 TON	108.60	76,020.00	130.00 91,000.00
0022	1503000000-E	610	ASP CONC INTR CRS I19.0C	430 TON	105.95	45,558.50	130.00 55,900.00
0023	1519000000-E	610	ASP CONC SURF CRS S9.5B	690 TON	81.50	56,235.00	150.00 103,500.00
0024	1575000000-E	620	ASP FOR PLANT MIX	105 TON	874.00	91,770.00	720.00 75,600.00
0025	1693000000-E	654	ASPH PLT MIX PVMT REPAIR	100 TON	106.65	10,665.00	215.00 21,500.00
0026	2022000000-E	815	SUBDRAIN EXCAVATION	448 CY	1.00	448.00	20.00 8,960.00
0027	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	2,000 SY	1.00	2,000.00	3.00 6,000.00
0028	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	336 CY	1.00	336.00	95.00 31,920.00
0029	2044000000-E	815	6" PERF SUBDRN PIPE	2,000 LF	1.00	2,000.00	11.00 22,000.00
0030	2070000000-N	815	SUBDRN PIPE OUTLET	4 EA	1.00	4.00	425.00 1,700.00
0031	2077000000-E	815	6" OUTLET PIPE	24 LF	1.00	24.00	40.00 960.00
0032	2264000000-E	840	PIPE PLUGS	1 CY	3,000.00	3,000.00	2,500.00 2,500.00
0033	2275000000-E	SP	FLOWABLE FILL	30 CY	450.00	13,500.00	350.00 10,500.00
0034	2612000000-E	848	6" CONCRETE DRIVEWAY	30 SY	200.00	6,000.00	150.00 4,500.00
0035	3030000000-E	862	STL BEAM GUARDRAIL	950 LF	33.50	31,825.00	29.75 28,262.50
0036	3045000000-E	862	SBGR SHOP CURVED	100 LF	28.00	2,800.00	35.00 3,500.00
0037	3150000000-N	862	ADDIT GUARDRAIL POSTS	5 EA	11.00	55.00	60.00 300.00
0038	3195000000-N	862	GR END TYPE AT-1	1 EA	950.00	950.00	1,500.00 1,500.00
0039	3210000000-N	862	GR END TYPE CAT-1	1 EA	950.00	950.00	1,800.00 1,800.00
0040	3287000000-N	SP	GR END TYPE TL-3	2 EA	3,500.00	7,000.00	4,500.00 9,000.00
0041	3635000000-E	876	RIP RAP, CLASS II	60 TON	95.00	5,700.00	150.00 9,000.00
0042	3649000000-E	876	RIP RAP, CLASS B	6 TON	100.00	600.00	150.00 900.00



11/10/2022

BP2.R020.3

TIP NO

0.398 MILES

FED AID NO STATE FUNDED

DRAINAGE, GRADING, PAVING, AND CULVERT

SR 1700 (ADAMS CREEK ROAD) OVER CLUB FOOT CREEK

						TRADER CONSTRUCTION CO	MOUNTAIN CREEK CONTRACTORS INC		
						NEW BERN, NC	MT PLEASANT, SC		
0043	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	575	SY	4.00	2,300.00	5.00	2,875.00
0044	4400000000-E	1110	WORK ZONE SIGNS (STAT)	172	SF	7.85	1,350.20	14.10	2,425.20
0045	4410000000-E	1110	WORK ZONE SIGNS (BARR)	10	SF	115.00	1,150.00	11.00	110.00
0046	4420000000-N	1120	PORTABLE CHANGE MSG SIGN	2	EA	6,050.00	12,100.00	9,100.00	18,200.00
0047	4424500000-N	SP	TEMP PORT TRAF SIGNAL SYS	1	EA	40,000.00	40,000.00	30,000.00	30,000.00
0048	4430000000-N	1130	DRUMS	265	EA	50.00	13,250.00	70.00	18,550.00
0049	4445000000-E	1145	BARRICADES (TYPE III)	12	LF	80.00	960.00	25.00	300.00
0050	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	8	EA	6,100.00	48,800.00	6,950.00	55,600.00
0051	4490000000-E	1170	PORT CONC BARRIER(ANCHRD)	1,369	LF	57.00	78,033.00	77.95	106,713.55
0052	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (EA) 4' X 12' STEEL ROAD PLATE	1	EA	6,200.00	6,200.00	7,500.00	7,500.00
0053	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (EA) 6' X 20' STEEL ROAD PLATE	1	EA	8,700.00	8,700.00	18,000.00	18,000.00
0054	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (EA) 8' X 20' STEEL ROAD PLATE	1	EA	8,700.00	8,700.00	25,000.00	25,000.00
0055	4810000000-E	1205	PAINT PVMT MARKINGS 4"	11,415	LF	0.95	10,844.25	1.30	14,839.50
0056	4835000000-E	1205	PAINT PVT MKG LINES 24"	96	LF	20.00	1,920.00	6.00	576.00
0057	4850000000-E	1205	LINE REMOVAL 4" WIDE	3,000	LF	2.00	6,000.00	2.65	7,950.00
0058	4870000000-E	1205	LINE REMOVAL 24" WIDE	96	LF	10.00	960.00	10.00	960.00
0059	5328000000-E	1510	30" WATER LINE	680	LF	140.00	95,200.00	140.00	95,200.00
0060	5329000000-E	1510	DI H2O PIPE FITTINGS	440	LB	13.00	5,720.00	13.00	5,720.00
0061	5606000000-E	1515	2" BLOW OFF	2	EA	3,400.00	6,800.00	3,400.00	6,800.00
0062	5678600000-E	1515	8" LINE STOP	2	EA	27,400.00	54,800.00	27,400.00	54,800.00
0063	5801000000-E	1530	ABANDON 8" UTILITY PIPE	670	LF	15.00	10,050.00	15.00	10,050.00
0064	5872600000-E	1550	DIRECT DRILL *** (8" WATER LINE)	566	LF	95.00	53,770.00	95.00	53,770.00
0065	6000000000-E	1605	TEMPORARY SILT FENCE	4,055	LF	3.25	13,178.75	3.00	12,165.00
0066	6006000000-E	1610	EROS CONTRL STONE CL A	75	TON	80.00	6,000.00	100.00	7,500.00
0067	6009000000-E	1610	EROS CONTRL STONE CL B	185	TON	80.00	14,800.00	75.00	13,875.00
0068	6012000000-E	1610	SEDIMENT CONTROL STONE	165	TON	65.00	10,725.00	70.00	11,550.00
0069	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	1,800.00	3,600.00	2,000.00	4,000.00
0070	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	5.00	1,000.00	5.00	1,000.00
0071	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	1,800.00	1,800.00	1,500.00	1,500.00
0072	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	25.00	5,000.00	23.00	4,600.00
0073	6029000000-E	SP	SAFETY FENCE	1,720	LF	3.25	5,590.00	2.50	4,300.00
0074	6030000000-E	1630	SILT EXCAVATION	230	CY	55.00	12,650.00	13.00	2,990.00
0075	6036000000-E	1631	MATTING FOR EROS CONTROL	2,200	SY	1.79	3,938.00	2.50	5,500.00
0076	6037000000-E	SP	COIR FIBER MAT	480	SY	6.00	2,880.00	10.00	4,800.00
0077	6042000000-E	1632	1/4" HARDWARE CLOTH	10	LF	10.00	100.00	8.00	80.00
0078	6045000000-E	SP	*** TEMPORARY PIPE (12")	59	LF	50.00	2,950.00	100.00	5,900.00

BP2.R020.3

Nov 09, 2022

DB00544

TIP NO

0.398 MILES

FED AID NO STATE FUNDED

DRAINAGE, GRADING, PAVING, AND CULVERT

SR 1700 (ADAMS CREEK ROAD) OVER CLUB FOOT CREEK

				TRADER CONSTRUCTION CO		MOUNTAIN CREEK CONTRACTORS INC			
				NEW BERN, NC		MT PLEASANT, SC			
0079	6045000000-E	SP	*** TEMPORARY PIPE (24")	235	LF	75.00	17,625.00	125.00	29,375.00
0080	6070000000-N	1639	SPECIAL STILLING BASINS	4	EA	550.00	2,200.00	750.00	3,000.00
0081	6071013000-E	SP	WATTLE BARRIER	290	LF	16.50	4,785.00	10.00	2,900.00
0082	6071020000-E	SP	POLYACRYLAMIDE (PAM)	100	LB	14.00	1,400.00	10.00	1,000.00
0083	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	2,650.00	7,950.00	2,500.00	7,500.00
0084	6087000000-E	1660	MOWING	3	ACR	750.00	2,250.00	500.00	1,500.00
0085	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	1.00	50.00	5.00	250.00
0086	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1.00	0.25	2,000.00	500.00
0087	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	1.00	50.00	5.00	250.00
0088	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	1.00	1.25	1,800.00	2,250.00
0089	6111000000-E	SP	IMPERVIOUS DIKE	150	LF	255.00	38,250.00	200.00	30,000.00
0090	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	75.00	750.00	75.00	750.00
0091	6117000000-N	SP	RESPONSE FOR EROS CONTROL	25	EA	500.00	12,500.00	50.00	1,250.00
0092	6117500000-N	SP	CONC WASHOUT STRUCTURE	2	EA	3,000.00	6,000.00	1,500.00	3,000.00
0093	6123000000-E	1670	REFORESTATION	0.1	ACR	10,000.00	1,000.00	5,000.00	500.00
CULVERT									
0094	8056000000-N	402	REMV EXIST STR ***** (16+34.00 -L-)	Lump Sum			22,000.00		20,000.00
0095	8126000000-N	414	CULV EXCAV @ ***** (16+34.00 -L-)	Lump Sum			54,000.00		100,000.00
0096	8133000000-E	414	FND CONDIT MAT, BOX CULV (FOUNDATION COND. MAT'L.)	134	TON	75.00	10,050.00	150.00	20,100.00
0097	8175000000-E	420	CLASS AA CONC (BRIDGE)	11.2	CY	1,400.00	15,680.00	1,500.00	16,800.00
0098	8248000000-E	425	EPOXY COAT REINF STEEL	1,492	LB	3.50	5,222.00	4.00	5,968.00
0099	8804000000-N	SP	GENERIC CULVERT ITEM (LS) 31'-1" X 9'-2" ALUMINUM BOX CULVERT	Lump Sum			485,000.00		660,000.00
0100	8818000000-E	SP	GENERIC CULVERT ITEM (TON) CULVERT BACKFILL (#57 STONE)	1,163	TON	65.00	75,595.00	100.00	116,300.00
WALL ITEMS									
0101	8847000000-E	SP	GENERIC RET WALL ITEM (SF) GALVANIZED SHEET PILE RETAINING WALLS	16,327	SF	65.00	1,061,255.00	83.00	1,355,141.00
CONTRACT TOTAL						TOTAL	3,249,909.20	TOTAL	4,379,860.75
ROADWAY						SUB-TOTAL	1,521,107.20	SUB-TOTAL	2,085,551.75
CULVERT						SUB-TOTAL	667,547.00	SUB-TOTAL	939,168.00
WALL ITEMS						SUB-TOTAL	1,061,255.00	SUB-TOTAL	1,355,141.00
BIDDERS IN ORDER						CONTRACT TOTAL			
TRADER CONSTRUCTION CO						1	3,249,909.20		
MOUNTAIN CREEK CONTRACTORS INC						2	4,379,860.75		