

PROJECT: BR2.R020 REFERENCE: BP-025-2050

SEE SHEET 3 FOR PLAN SHEET LAYOUT
AT TIME OF INVESTIGATION

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	BP-025-2050	1	19

ROADWAY SUBSURFACE INVESTIGATION

COUNTY CRAVEN
PROJECT DESCRIPTION CULVERT ON SR 1700
(ADAMS CREEK RD.) OVER CLUBFOOT CREEK

INVENTORY

CONTENTS

<u>LINE</u>	<u>STATION</u>	<u>PLAN</u>
-L-	10+80 TO 21+60	4
-DETI-	10+00 TO 15+16	4
-DET2-	10+00 TO 16+26	4

CROSS SECTIONS

<u>LINE</u>	<u>STATION</u>	<u>SHEETS</u>
-L-	11+00	5
-L-	13+00	6
-L-	14+00 TO 18+50	7-16
-L-	20+00	17
-L-	21+00	18

CULVERT

<u>LINE</u>	<u>STATION</u>	<u>SHEETS</u>
-L-	16+34	19

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTES:

1. THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
2. BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

S.N. ZIMARINO

R.E. SMITH

C.M. WALKER


INVESTIGATED BY T.C. BOTTOMS

DRAWN BY T.C. BOTTOMS

CHECKED BY D.N. ARGENBRIGHT

SUBMITTED BY D.N. ARGENBRIGHT

DATE APRIL 2022



DocuSigned by:

Tyler Bottoms

05/04/2022

48A2D3BD08CF4A6
SIGNATURE

DATE

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS GEOTECHNICAL ENGINEERING UNIT SUBSURFACE INVESTIGATION SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

SOIL DESCRIPTION SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (ASTM T 206, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6

SOIL LEGEND AND AASHTO CLASSIFICATION TABLE with columns for GENERAL CLASS., GRANULAR MATERIALS (≤ 35% PASSING #200), SILT-CLAY MATERIALS (> 35% PASSING #200), ORGANIC MATERIALS, and SYMBOL. Includes sub-tables for PERCENTAGE OF MATERIAL and GROUP INDEX.

CONSISTENCY OR DENSENESS TABLE with columns for PRIMARY SOIL TYPE, COMPACTNESS OR CONSISTENCY, RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE), and RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT²).

TEXTURE OR GRAIN SIZE TABLE with columns for U.S. STD. SIEVE SIZE OPENING (MM), BOULDER (BLDR.), COBBLE (COB.), GRAVEL (GR.), COARSE SAND (CS.E. SD.), FINE SAND (F. SD.), SILT (SL.), and CLAY (CL.).

SOIL MOISTURE - CORRELATION OF TERMS TABLE with columns for SOIL MOISTURE SCALE (ATTERBERG LIMITS), FIELD MOISTURE DESCRIPTION, and GUIDE FOR FIELD MOISTURE DESCRIPTION.

PLASTICITY TABLE with columns for PLASTICITY INDEX (PI), NON PLASTIC, SLIGHTLY PLASTIC, MODERATELY PLASTIC, and HIGHLY PLASTIC, along with DRY STRENGTH.

COLOR DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.

GRADATION WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.

ANGULARITY OF GRAINS THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED.

MINERALOGICAL COMPOSITION MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.

COMPRESSIBILITY SLIGHTLY COMPRESSIBLE LL < 31 MODERATELY COMPRESSIBLE LL = 31 - 50 HIGHLY COMPRESSIBLE LL > 50

PERCENTAGE OF MATERIAL TABLE with columns for ORGANIC MATERIAL, GRANULAR SOILS, SILT - CLAY SOILS, and OTHER MATERIAL.

GROUND WATER WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING. STATIC WATER LEVEL AFTER 24 HOURS. PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA. SPRING OR SEEP.

MISCELLANEOUS SYMBOLS including ROADWAY EMBANKMENT (RE), SOIL SYMBOL, ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT, INFERRER SOIL BOUNDARY, INFERRER ROCK LINE, ALLUVIAL SOIL BOUNDARY, DIP & DIP DIRECTION OF ROCK STRUCTURES, TEST BORING, AUGER BORING, CORE BORING, MONITORING WELL, PIEZOMETER INSTALLATION, SLOPE INDICATOR INSTALLATION, CONE PENETROMETER TEST, SOUNDING ROD, TEST BORING WITH CORE, SPT N-VALUE.

RECOMMENDATION SYMBOLS including UNDERCUT, SHALLOW UNDERCUT, UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE, UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK, UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL.

ABBREVIATIONS TABLE with columns for AR - AUGER REFUSAL, BT - BORING TERMINATED, CL - CLAY, CPT - CORE PENETRATION TEST, CSE - COARSE, DMT - DILATOMETER TEST, DPT - DYNAMIC PENETRATION TEST, e - VOID RATIO, F - FINE, FOSS. - FOSSILIFEROUS, FRAC. - FRACTURED, FRACTURES, FRAGS. - FRAGMENTS, HI. - HIGHLY, MED. - MEDIUM, MICA - MICACEOUS, MOD. - MODERATELY, NP - NON PLASTIC, ORG. - ORGANIC, PMT - PRESSUREMETER TEST, SAP. - SAPROLITIC, SD. - SAND, SANDY, SL. - SILT, SILTY, SLI. - SLIGHTLY, TCR - TRICONE REFUSAL, w - MOISTURE CONTENT, V - VERY, VST - VANE SHEAR TEST, WEA. - WEATHERED, u - UNIT WEIGHT, g - DRY UNIT WEIGHT, SAMPLE ABBREVIATIONS: S - BULK, SS - SPLIT SPOON, ST - SHELBY TUBE, RS - ROCK, RT - RECOMPACTED TRIAXIAL, CBR - CALIFORNIA BEARING RATIO.

EQUIPMENT USED ON SUBJECT PROJECT DRILL UNITS: CME-45C, CME-55, CME-550, VANE SHEAR TEST, PORTABLE HOIST. ADVANCING TOOLS: CLAY BITS, 6" CONTINUOUS FLIGHT AUGER, 8" HOLLOW AUGERS, HARD FACED FINGER BITS, TUNG-CARBIDE INSERTS, CASING w/ ADVANCER, TRICONE 2 1/16" STEEL TEETH, TRICONE * TUNG-CARB., CORE BIT. HAMMER TYPE: AUTOMATIC, MANUAL. CORE SIZE: B, H, N. HAND TOOLS: POST HOLE DIGGER, HAND AUGER, SOUNDING ROD, VANE SHEAR TEST.

ROCK DESCRIPTION HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED, AN INFERRER ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:

WEATHERED ROCK (WR), CRYSTALLINE ROCK (CR), NON-CRYSTALLINE ROCK (NCR), COASTAL PLAIN SEDIMENTARY ROCK (CPS) with corresponding symbols and descriptions.

WEATHERING FRESH ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE. VERY SLIGHT (V SLI.) ROCK GENERALLY FRESH, JOINTS STAINED. SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.

SLIGHT (SLI.) ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS. MODERATE (MOD.) SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED. SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.

MODERATELY SEVERE (MOD. SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. IF TESTED, WOULD YIELD SPT REFUSAL.

SEVERE (SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. IF TESTED, WOULD YIELD SPT N VALUES > 100 BPF.

VERY SEVERE (V SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE THAT ONLY MINOR VESTIGES OF ORIGINAL ROCK FABRIC REMAIN. IF TESTED, WOULD YIELD SPT N VALUES < 100 BPF.

COMPLETE ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.

ROCK HARDNESS VERY HARD CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK. HARD HARD CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.

MODERATELY HARD CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.

MEDIUM HARD CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.

SOFT CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.

VERY SOFT CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.

TERMS AND DEFINITIONS ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC.

ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE.

CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL.

DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLOADED FROM PARENT MATERIAL.

FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT.

LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK.

ROCK QUALITY DESIGNATION (ROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS.

SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE.

STRATA ROCK QUALITY DESIGNATION (SROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.

BENCH MARK: BP2.R020.1.is.tin.tin DATED 9/15/21

ELEVATION: FEET

NOTES: FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC. FRIABLE RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE. MODERATELY INDURATED GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER. INDURATED GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER. EXTREMELY INDURATED SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.

09/08/99

See Sheet 1A For Index of Sheets


STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

CRAVEN COUNTY



**LOCATION: CULVERT ON SR 1700 (ADAMS CREEK RD.) OVER
CLUB FOOT CREEK**
TYPE OF WORK: DRAINAGE, GRADING, PAVING, & CULVERT

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	BP2.R020.1	3	19
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
BP2.R020.1		P.E.	

TIP PROJECT: BP2.R020.1



25% PLAN SUBMITTAL




THERE IS NO CONTROL OF ACCESS ON THIS PROJECT.
THIS PROJECT IS NOT WITHIN MUNICIPAL BOUNDARIES.
CLEARING ON THIS PROJECT SHALL BE PERFORMED TO LIMITS ESTABLISHED BY METHOD ____.

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

INCOMPLETE PLANS
DO NOT USE FOR R/W ACQUISITION

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

CONTRACT:



DESIGN DATA

ADT 2018 =	3,000
ADT 2040 =	N/A
K =	N/A %
D =	N/A %
T =	N/A % *
V =	50 MPH
* TTST =	N/A, DUAL = N/A
FUNC CLASS =	
MINOR COLLECTOR	
SUBREGIONAL TIER	

PROJECT LENGTH

LENGTH ROADWAY PROJECT BP2.R020.1	=	0.201 MILES
LENGTH STRUCTURE PROJECT BP2.R020.1	=	0.004 MILES
TOTAL LENGTH OF PROJECT BP2.R020.1	=	0.205 MILES

PLANS PREPARED BY:
wood.
4021 STIRRUP CREEK DRIVE
DURHAM, NC 27703
NC ENG. E-1253
2018 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
APRIL 15, 2022

LETTING DATE:
AUGUST 24, 2022

PLANS PREPARED FOR:
DIVISION OF HIGHWAYS
DIVISION 2
1037 W.H. SMITH BLVD.
GREENVILLE, NC 27835

CHRISTOPHER H. LEE, PE
PROJECT ENGINEER


MICHAEL AMAN, PE
NCDOT CONTACT
DIV 2 BRIDGE PROGRAM MANAGER

HYDRAULICS ENGINEER

SIGNATURE: _____ P.E.

ROADWAY DESIGN ENGINEER

SIGNATURE: _____ P.E.



31-MAR-2022 08:31
\\BP2R0201.RD\TSH-LGD.dgn
\$\$\$\$\$USERNAME\$\$\$\$\$



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

ERIC BOYETTE
SECRETARY

April 11, 2022

State Project: BP2.R020.1 (BP-025-0250)
F.A. Project: N/A
County: Craven
Description: Culvert on SR 1700 (Adams Creek Rd.) over Clubfoot Creek

Subject: Geotechnical Inventory Report

Project Description

This project begins outside Harlowe in Craven County on Adams Creek Road just north of the intersection with NC 101. The project consists of raising Adams Creek Rd. to accommodate replacing the existing pipes with a culvert. The geotechnical investigation was confined to the areas of proposed construction.

Fieldwork was conducted in March of 2022. Standard Penetration Tests, hand auger borings and push probes were completed at various offsets along the project corridor. Representative soil samples were collected for visual classification in the field and for laboratory analysis by the Materials and Tests Unit.

The following alignments were investigated. Selected cross sections of these alignments are included in this report.

<u>Line</u>	<u>Station(±)</u>
-L-	10+80 to 21+60
-DET1-	10+00 to 15+16
-DET2-	10+00 to 16+26

Areas of Special Geotechnical Interest

- 1) The entire project was found to exhibit seasonal high groundwater.
- 2) The following section contained organic soils which have the potential to cause embankment/subgrade and or slope stability problems during construction:

<u>Line</u>	<u>Station(±)</u>
-L-	15+90 to 17+75

- 3) The entire project contained cohesive soils which have the potential to cause embankment/subgrade and or slope stability problems during construction:

Physiography and Geology

This project corridor is located within the Coastal Plain Physiographic Province. Topography along the project is nearly flat to gently sloping. Natural ground elevations ranged from 0± to 7± feet above sea level.

Surficial soils in this area are generally classified as Undivided Coastal Plain.

Ground Water

Ground water data was collected in January of 2022. Ground water elevations ranged from 0 to 4± feet above sea level.

Soils

Soils encountered within this project area have been divided into four categories: Roadway Embankment, Artificial Fill, alluvial and Undivided Coastal Plain.

Roadway embankment soils were found along the existing Adams Creek Rd. Where encountered it was composed of 1± to 4± feet of very loose to dense sand and silty sand (A-2-4).

Artificial fill soils were found along and beneath the existing Adams Creek Rd. alignment near the existing pipe location. Where encountered, it was composed of 1± to 3± feet of loose sand.



Soils identified as alluvial are composed of 2± to 5± feet of very soft moderately organic silt and muck and 2± to 7± feet of very loose to loose sand. Moisture samples collected within the organic unit returned natural moisture contents between 128% and 183% and organic contents between 16.1% and 33.4%. Vane shear tests varied from 292 to 1503 psf.

Soils identified as Undivided Coastal Plain are composed of 2± to 6± feet loose to very dense sand, silty sand and clayey sand (A-2-6) and 2± to 5± feet of very soft to medium stiff sandy silt and sandy and silty clay (A-4, A-6, A-7-6).

CULVERT AT -L- STA. 16+34

The existing pipes are to be replaced with a culvert at -L- Sta. 16+34. SPT borings at the site show very loose to loose alluvial sand and very soft muck underlain by loose to very dense undivided coastal plain soils. A profile of these borings with a cross section of the proposed culvert is shown on Page 19 of this report.

SITE PLAN



-L- POT Sta. 10+00.00 = 10

-DET2- PC Sta. 10+00.00 =
-L- POC Sta. 13+81.71

-DET2- PRC Sta. 10+67.42

BEGIN TIP PROJECT BP2.R020J
-L- STA. 10+80.00

-DET1- PC Sta. 10+00.00 =
-EL- 13+63.60 (0.00)

-DET1- PT Sta. 10+88.07

-DET2- PT Sta. 12+07.20

-DET1- PC Sta. 13+93.77

-DET2- PT Sta. 16+26.21 =
-L- POC Sta. 20+10.13


-DET1- PT Sta. 15+16.80 =
-EL- 18+80.37 (0.00)


-DET2- PC Sta. 14+61.27

-L- POT
Sta. 22+73.05

END TIP PROJECT BP2.R020J
-L- STA. 21+60.00

N 20°14'50.1\"/>






(A) MEDIUM DENSE BROWN AND TAN SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)

4:1


3:1





03422
SOFT GRAY SANDY CLAY, WET (UNDIVIDED COASTAL PLAIN)


LOOSE GRAY SAND, SATURATED


13+00.00











3:1

MEDIUM DENSE TAN SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)

LOOSE GRAY SAND, MOIST TO SATURATED (UNDIVIDED COASTAL PLAIN)


SOFT GRAY AND GREN SANDY CLAY, WET

03/22

15+50.00

— L —

I:\APR-2022_07457
 S:\GEO\GREENVILLE_Investigation\TIP\BP2.R020.GEO.ROW\Y\CADD_GEO\TECH\asc\BP2.R.20.r.djv.XSL.14+00 TO 18+50.dgn
 \$\$\$USERNAME\$\$\$



- Ⓐ MEDIUM DENSE TAN SAND, MOIST (ROADWAY EMBANKMENT)
- Ⓒ SOFT GRAY SILTY CLAY, WET (UNDIVIDED COASTAL PLAIN)
- Ⓓ VERY SOFT BROWN MUCK, WET (ALLUVIAL)


SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
S-3	22' RT	16+00	0.0-4.5	A-4	-	NP	40.3	17.3	26.3	16.1	S-1	67	44	182.8	33.4

VANE SHEAR TESTS

STATION	OFFSET	DEPTH	(psf)
16+00	23' RT	0.5	751.68
16+00	23' RT	1.0	292.32
16+00	23' RT	1.5	396.72
16+00	23' RT	2.0	334.08
16+00	23' RT	2.5	375.84
16+00	23' RT	3.0	417.60
16+00	23' RT	3.5	375.84
16+00	23' RT	4.0	626.40
16+00	23' RT	4.5	709.92

16+00.00

—L—



- (C) SOFT GRAY SANDY CLAY, WET (UNDIVIDED COASTAL PLAIN)
- (D) VERY SOFT BROWN MUCK, WET (ALLUVIAL)
- (E) LOOSE BROWN, TAN AND GRAY SAND, MOIST TO SATURATED (ARTIFICIAL FILL)
- (F) VERY LOOSE TO LOOSE GRAY SAND AND SILTY SAND WITH WOOD FRAGMENTS, MOIST TO SATURATED (ALLUVIAL)

VERY LOOSE TO LOOSE TAN AND BROWN SILTY SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)

LOOSE TO VERY DENSE GRAY, TAN AND BLUE SAND WITH SHELL FRAGMENTS, SATURATED (UNDIVIDED COASTAL PLAIN)

16 + 50.00

-L-

75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75


45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

Ⓧ VERY SOFT BROWN MUCK, MOIST TO WET (ALLUVIAL)

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
S-2	32' LT	17+00	0.0-4.5	A-4	-	NP	20.9	35.9	27.1	16.1	97	83	45	136.8	26.3

S-2



LOOSE TAN SILTY SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)

LOOSE GRAY AND TAN SILTY SAND WITH WOOD FRAGMENTS, MOIST TO SATURATED (UNDIVIDED COASTAL PLAIN)

SOFT GRAY SANDY CLAY, WET (UNDIVIDED COASTAL PLAIN)

LOOSE TO MEDIUM DENSE GRAY SAND, SATURATED

17+00.00

—L—

75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

VANE SHEAR TESTS



STATION	OFFSET	DEPTH	(psf)
17+50	28' LT	0.5	668.16
17+50	28' LT	1.0	542.88
17+50	28' LT	1.5	1503.36
17+50	28' LT	2.0	960.48
17+50	28' LT	2.5	709.92
17+50	28' LT	3.0	709.92
17+50	28' LT	3.5	501.12
17+50	28' LT	4.0	835.20
17+50	28' LT	4.5	709.92

① VERY SOFT BROWN MODERATELY ORGANIC SILT, MOIST TO WET (ALLUVIAL)

SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
S-1	28' LT	17+50	0.0-4.5	A-4	-	NP	18.1	35.9	29.9	16.1	93	82	47	128.5	16.1

S-1




LOOSE TAN SILTY SAND, MOIST (ROADWAY EMBANKMENT)
 LOOSE GRAY SAND, MOIST TO SATURATED (UNDIVIDED COASTAL PLAIN)
 SOFT GRAY SANDY CLAY, WET (UNDIVIDED COASTAL PLAIN)

17 + 50.00

— L —

75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75



(A) LOOSE TO DENSE BROWN AND TAN SAND WITH GRAVEL, MOIST TO SATURATED (ROADWAY EMBANKMENT)
 (B) LOOSE TO MEDIUM DENSE GRAY SAND, MOIST TO SATURATED (UNDIVIDED COASTAL PLAIN)

PAVEMENT


30
18
2
4
4
3
7

SOFT GRAY SANDY CLAY, MOIST TO WET


VERY LOOSE TO LOOSE GRAY SILTY SAND, SATURATED


18 + 00.00

— L —




18 + 50.00
 -L-






75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75



- (A) LOOSE TAN AND BROWN SAND, MOIST (ROADWAY EMBANKMENT)
- (B) LOOSE GRAY SAND, MOIST TO SATURATED (UNDIVIDED COASTAL PLAIN)

SOFT TO MEDIUM STIFF GRAY AND TAN SANDY CLAY, WET (UNDIVIDED COASTAL PLAIN)

21+00.00




75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

PROFILE THROUGH BORINGS PROJECTED ALONG -L-

CL INV ELEV=-5.4'
s=0.30%
STA 16+34 -L-
3'-3" x 9'-3" ABC w/HW & EW
SKEW=90
CL ROAD ELEV=6.26'

VE: 2



LOOSE TO VERY DENSE GRAY AND TAN SAND,
SILTY SAND AND CLAYEY SAND,
SATURATED (UNDIVIDED COASTAL PLAIN)

- (A) LOOSE TO MEDIUM DENSE TAN AND BROWN SAND AND SILTY SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)
- (B) LOOSE GRAY SAND, MOIST TO SATURATED (UNDIVIDED COASTAL PLAIN)
- (C) SOFT GRAY AND GREEN SANDY CLAY, WET (UNDIVIDED COASTAL PLAIN)
- (D) VERY SOFT BROWN MUCK, WET (ALLUVIAL)
- (E) VERY LOOSE GRAY SAND, SATURATED (ARTIFICIAL FILL)
- (F) VERY LOOSE TO LOOSE GRAY SAND AND SILTY SAND WITH WOOD FRAGMENTS, MOIST TO SATURATED (ALLUVIAL)

NOTE: GROUNDLINE PROFILE ALONG -L- DRAWN BY HAND REFERENCING CULVERT SURVEY AND HYDRAULIC DESIGN REPORT DATED 1/13/2022

NOTE: INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE PROFILE