COMPUTED BY: E. Stewart	DATE: 03-28-2016
CHECKED BY: _____	DATE: _____

(2-22-16)

PROJECT NO.	SHEET NO.
W-5203W	3G-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF SUBSURFACE DRAINAGE

LINE	Station	Station	Location LT/RT/CL	Drain Type* UD/BD/SD	LF
CONTINGENCY					500
				TOTAL LF:	500

*UD = Underdrain
*BD = Blind Drain
*SD = Subsurface Drain

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

LINE	Station	Station	Aggregate Type* ASU/AST	Aggregate Thickness INCHES	Shallow Undercut CY	Class IV Subgrade Stabilization TONS	Geotextile for Soil Stabilization SY	Stabilizer Aggregate TONS	Class IV Aggregate Stabilization TONS
-L-	18+00	22+25					475		
-L-	23+75	24+25					475		
	25+25	34+25					475		
-L-	35+75	36+75					475		
CONTINGENCY					100	190	500		
			TOTAL CY/TONS/SY:		100	190	2400**	0	0

*ASU = Aggregate Subgrade
*AST = Aggregate Stabilization
**Total square yards of "Geotextile for Soil Stabilization" is only the estimated quantity for ASU/AST and may only represent a portion of the geotextile quantity shown in the Item Sheets of the Proposal.