

SUMMARY OF QUANTITIES

COUNTY	WBS ELEMENT.	MAP NO.	ROUTE	TERMINI	DESCRIPTION	PROJECT LENGTH	WIDTH	TYPICAL SECTION
PENDER	3CR.20711.141	1	SR 1518	NC 210 to EOP	RESURFACING	1.50	20	1
PENDER	3CR.20711.141	2	SR 1520	SR 1526 TO NC 50	OVERLAYS AT VARIOUS LOCATIONS	2.80	18	2
PENDER	3CR.20711.141	3	SR 1526	DUPLIN CO. LINE TO NC 50	MILL PATCH	3.70	18	3
PENDER	3CR.20711.141	4	SR 1553	NC 50 TO NC 50	MAT WITH 78M & RESURFACE	0.66	18	4
PENDER	3CR.20711.141	5	SR 1555	SR 1558 TO NC 50	MAT WITH 78M & RESURFACE	0.73	18	4
PENDER	3CR.20711.141	6	SR 1557	SR 1154 TO SR 1555	MAT WITH 78M & RESURFACE	0.06	18	4
PENDER	3CR.20711.141	7	SR 1558	SR 1554 TO SR 1554	MAT WITH 78M & RESURFACE	0.34	18	4
PENDER	3CR.20711.141	8	SR 1559	NC 50 TO SR 1558	MAT WITH 78M & RESURFACE	0.73	18	4
PENDER	36249.3203	9	BORYK AVE.(CITY STREET)	OCEAN BLVD TO CUL-DE-SAC	MILL, PAVE & RESURFACE	0.22	18	5
ON SLOW	3CR.20671.141	10	SR 1583	NC 210 TO END OF MAINTENANCE	MAT WITH NO. 6 STONE & RESURFACE	1.00	18	4
TOTALS						11.74		

MAP NO.	MOBILIZATION (%)	COMPRENSIVE GRADING (LS)	INCIDENTAL STONE BASE (TONS)	MILLING ASPHALT PAVEMENT 1 " DEPTH (SY)	ACBC TYPE B25.0 B (TONS)	ACSC TYPE S 9.5 B (TONS)	ACSC TYPE SF 9.5 A (TONS)	ASPHALT BINDER FOR PLANT MIX (TONS)
1	0.1278		25				1010	66
2	0.2385		20				915	62
3	0.3152							
4	0.0562		20			255		15
5	0.0622		20			680		41
6	0.0051		20			55		3
7	0.0290		25			310		19
8	0.0622		25			240		15
9	0.0187			533.3			254	17
10	0.0852	1	50				920	62
TOTALS	1.0000	1	205	533.3	0	1,540	3,099	300

MAP NO.	PATCHING EXISTING PAVEMENT (MILL) (TONS)	TEMPORAR Y SILT FENCE (LF)						
1								
2								
3	615							
4								
5								
6								
7								
8								
9								
10		5280						
TOTALS	615	5280						