



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

April 29, 2019

**To: Prospective Bidders**

**From: Jonathan W. Mitchell**  
**Division Contracts and Proposals Engineer**

<sup>DS</sup>  
A blue ink signature of Jonathan W. Mitchell, enclosed in a blue rectangular box with rounded corners.

**Contract ID#: DC00223**

**WBS Element: 17BP.3.R.76**

**Subject: Addendum #1: GRADING, DRAINAGE, PAVING, AND STRUCTURE**

The Subject contract proposal contains the following addendum:

- 1- Replace the bid sheet with the attached. Line item # 74 has been changed to reflect the dimensions in the structure plan set.

**\*\*\*An Addendum has been added to the Bid Express.**

JWM/jwm

*Mailing Address:*  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
5501 BARBADOS BOULEVARD  
CASTLE HAYNE, NC 28429-5647

*Telephone:* (910) 341-2000  
*Fax:* (910) 675-0143  
*Customer Service:* 1-877-368-4968

*Website:* [www.ncdot.gov](http://www.ncdot.gov)

*Location:*  
5501 BARBADOS BOULEVARD  
CASTLE HAYNE, NC 28429-5647

County : Duplin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** -L- STA. 16+15	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	300 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	300 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	25 SY		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	24 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	44 LF		
0013	0995000000-E	340	PIPE REMOVAL	20 LF		
0014	1330000000-E	607	INCIDENTAL MILLING	265 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	460 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	370 TON		
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	45 TON		
0018	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		

County : Duplin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	200 SY		
0020	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	34 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0022	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE	6 LF		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0025	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0026	2556000000-E	846	SHOULDER BERM GUTTER	30 LF		
0027	3030000000-E	862	STEEL BEAM GUARDRAIL	50 LF		
0028	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0029	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0030	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4 EA		
0031	3628000000-E	876	RIP RAP, CLASS I	3 TON		
0032	3635000000-E	876	RIP RAP, CLASS II	135 TON		
0033	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	185 SY		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	715 SF		
0035	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0036	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,800 LF		
0037	6000000000-E	1605	TEMPORARY SILT FENCE	931 LF		
0038	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	45 TON		

County : Duplin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	15 TON		
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	35 TON		
0041	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1 TON		
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0045	6030000000-E	1630	SILT EXCAVATION	70 CY		
0046	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,655 SY		
0047	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0048	6071012000-E	SP	COIR FIBER WATTLE	20 LF		
0049	6071014000-E	SP	COIR FIBER WATTLE BARRIER	230 LF		
0050	6071020000-E	SP	POLYACRYLAMIDE (PAM)	5 LB		
0051	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0052	6087000000-E	1660	MOWING	3 ACR		
0053	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0054	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0055	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0056	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0057	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0058	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		

County : Duplin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0059	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0060	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** STA. 16+15.50 -L-	Lump Sum	L.S.	
0061	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0062	8112730000-N	450	PDA TESTING	1 EA		
0063	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** STA. 16+15.50 -L-	Lump Sum	L.S.	
0064	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	28.8 CY		
0065	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** STA. 16+15.50 -L-	Lump Sum	L.S.	
0066	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,230 LB		
0067	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES HP 12X53	14 EA		
0068	8364000000-E	450	HP12X53 STEEL PILES	770 LF		
0069	8393000000-N	450	PILE REDRIVES	8 EA		
0070	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	140.25 LF		
0071	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	160 TON		
0072	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	180 SY		
0073	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0074	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		