

PROJECT	FEDERAL PROJECT NUMBER	FED ITEM	CONT SEC	WORK TYPE	LOCATION
17BP.3.R.33	17BP.3.R.33			RURAL/GRAD'G & DRAINAGE STRUC & SURF PRO	Bridge No. 45 over Tuckahoe Branch on S ZONE: ROUTE:

BREAKDOWN ID 0001

WORK ITEM DESCRIPTION	CATG	SEQUENCE	ITEM	QUANTITY	UNIT
MOBILIZATION	0001	0001	0000100000-N	1.00	LS
CONSTRUCTION SURVEYING	0001	0002	0000400000-N	1.00	LS
GRADING	0001	0003	0043000000-N	1.00	LS
ASPHALT CONC BASE COURSE, TYPE B25.0B	0001	0004	1489000000-E	300.00	TON
ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	0001	0005	1525000000-E	180.00	TON
ASPHALT BINDER FOR PLANT MIX	0001	0006	1575000000-E	30.00	TON
STEEL BM GUARDRAIL	0001	0007	3030000000-E	225.00	LF
ADDITIONAL GUARDRAIL POSTS	0001	0008	3150000000-N	5.00	EA
GUARDRAIL ANCHOR UNITS, TYPE 350	0001	0009	3270000000-N	4.00	EA
WORK ZONE SIGNS (STATIONARY)	0001	0010	4400000000-E	330.00	SF
WORK ZONE SIGNS (BARRICADE MOUNTED)	0001	0011	4410000000-E	79.00	SF
BARRICADES (TYPE III)	0001	0012	4445000000-E	88.00	LF
PAINT PAVEMENT MARKING LINES (4")	0001	0013	4810000000-E	1,950.00	LF
TEMPORARY SILT FENCE	0001	0014	6000000000-E	950.00	LF
STONE FOR EROSION CONTROL, CLASS B	0001	0015	6009000000-E	5.00	TON
SEDIMENT CONTROL STONE	0001	0016	6012000000-E	40.00	TON
TEMPORARY MULCHING	0001	0017	6015000000-E	0.50	ACR
SEED FOR TEMPORARY SEEDING	0001	0018	6018000000-E	50.00	LB
FERTILIZER FOR TEMPORARY SEED-ING	0001	0019	6021000000-E	0.25	TON
SAFETY FENCE	0001	0020	6029000000-E	160.00	LF
SPECIAL STILLING BASINS	0001	0021	6070000000-N	2.00	EA
COIR FIBER WATTLE	0001	0022	6071012000-E	40.00	LF
SEEDING & MULCHING	0001	0023	6084000000-E	0.50	ACR
SEED FOR REPAIR SEEDING	0001	0024	6090000000-E	50.00	LB
FERTILIZER FOR REPAIR SEEDING	0001	0025	6093000000-E	0.25	TON
SEED FOR SUPPLEMENTAL SEEDING	0001	0026	6096000000-E	50.00	LB
FERTILIZER TOPDRESSING	0001	0027	6108000000-E	0.25	TON
IMPERVIOUS DIKE	0001	0028	6111000000-E	40.00	LF
RESPONSE FOR EROSION CONTROL	0001	0029	6117000000-N	13.00	EA
REMOVAL OF EXISTING STRUCTURE AT STATION *****	0001	0030	8035000000-N	1.00	LS

-L- STA 12+65.50

PROJECT	FEDERAL PROJECT NUMBER	FED ITEM	CONT SEC	WORK TYPE	LOCATION
17BP.3.R.33	17BP.3.R.33			RURAL/GRAD'G & DRAINAGE STRUC & SURF PRO	Bridge No. 45 over Tuckahoe Branch on S ZONE: ROUTE:

BREAKDOWN ID 0001

WORK ITEM DESCRIPTION	CATG	SEQUENCE	ITEM	QUANTITY	UNIT
CULVERT EXCAVATION, STA ***** -L- STA 12+65.50	0001	0031	8126000000-N	1.00	LS
FOUNDATION CONDITIONING MATER-IAL, BOX CULVERT	0001	0032	8133000000-E	149.00	TON
CLASS A CONCRETE (CULVERT)	0001	0033	8196000000-E	105.90	CY
REINFORCING STEEL (CULVERT)	0001	0034	8245000000-E	11,001.00	LB
RIP RAP, CLASS ** Class I, (In Barrel only)	0001	0035	8590000000-E	29.00	TON
RIP RAP, CLASS I	0001	0036	3628000000-E	45.00	TON
GEOTEXTILE FOR DRAINAGE	0001	0037	3656000000-E	165.00	SY