

### SUMMARY OF QUANTITIES

COUNTY	WBS ELEMENT.	MAP NO.	ROUTE	TERMINI	DESCRIPTION	PROJECT LENGTH	WIDTH	TYPICAL SECTION
PENDER	3CR.20711.149	1	SR 1114	MM 1.97 to SR 1113	FROM MM1.97 SAND PIT DRIVEWAY TO SR 1113 WIDEN 1' EACH SIDE	1.02	20	1
PENDER	3CR.20711.149	2	SR 1114	MM 1.97 to NC 210	RESURFACE WITH 1.5" S 9.5 B	3.75	22	2
PENDER	3CR.20711.149	3	SR 1412	SR 1411 to HAYES ST (CITY STREET)	MILL PATCH WITH 1.5" S 9.5 B	3.37	20	3
PENDER	3CR.20711.149	4	SR 1211	US 421 to SR 1209	1" OVERLAYS AS MARKED WITH SF 9.5 A	4.22	20	4
<b>TOTALS</b>						12.36		
MAP NO.	MOBILIZATION (%)	INCIDENTAL STONE BASE (TONS)	ACBC TYPE B25.0 B (TONS)	ACSC TYPE S 9.5 B (TONS)	ACSC TYPE SF 9.5A (OVERLAYS) (TONS)	ASPHALT BINDER FOR PLANT MIX (TONS)	MILL PATCH (TONS)	PERMANENT RAISED PAVEMENT MARKERS (EACH)
1	0.083	50	430			19		
2	0.303	75		4,415.0		262		248
3	0.273	50					520	
4	0.341	75			1055	71		
<b>TOTALS</b>	1.0000	175	430	4,415	1055	281.0	520	248
MAP NO.	SILT FENCE (LF)	COIR FIBER WADDLES (LF)	PAM (LB)					
1	200	80	1					
2								
3								
4								
<b>TOTALS</b>	200	80.00	1					