



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

October 11, 2021

**To: Prospective Bidders**

**From: Jonathan W. Mitchell**  
**Division Contract Engineer**

DocuSigned by:  
*Jonathan W Mitchell*  
02B404268BC84C2...

**Contract ID: DC00316**  
**WBS#: 50138.3.113**  
**F.A. #: HSIP-0017(54)**  
**TIP#: W-5601DH**  
**COUNTY: NEW HANOVER**

**Subject: Addendum #1: W-5601DH Third & Dock Street Re-let**

The Subject contract proposal contains the following addendum:

1. The EBSX file goal percentage has been changed to 7% DBE to reflect the goals in the proposal and invitation to bid form.
2. Two additional Curb Ramps have been added to the bid form to account for the concrete pedestrian refuge/ truncated domes as seen on Plan Sheet 4. See the attached revised bid form.
3. The concrete for the granite curb concrete anchor and 2'6" concrete curb & gutter shall be 3,500 PSI minimum. Reference the special provision in the proposal.
4. The lump sum Planting Soil line item includes the 6" of topsoil referenced in the specifications for Grass for Sod Median.
5. There is not an approved producer/ supplier list for Sod and Planting Soil. Follow the Specifications in the proposal.
6. The StreetPrint line item will be installed between the 8" Thermoplastic Lines at the crosswalks along Dock Street (-Y-).

**\*\*\*An Addendum has been added to Bid Express.**

*Mailing Address:*  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
5505 BARBADOS BOULEVARD  
CASTLE HAYNE, NC 28429-5647

*Telephone:* (910) 341-2001  
*Fax:* (910) 675-0143  
*Customer Service:* 1-877-368-4968

*Website:* [www.ncdot.gov](http://www.ncdot.gov)

*Location:*  
5505 BARBADOS BOULEVARD  
CASTLE HAYNE, NC 28429-5647

County : New Hanover

| Line #               | Item Number  | Sec # | Description  | Quantity  | Unit Cost | Amount |
|----------------------|--------------|-------|--|-----------|-----------|--------|
| <b>ROADWAY ITEMS</b> |              |       |  |           |           |        |
| 0001                 | 0000100000-N | 800   | MOBILIZATION   | Lump Sum  | L.S.      |        |
| 0002                 | 0000400000-N | 801   | CONSTRUCTION SURVEYING   | Lump Sum  | L.S.      |        |
| 0003                 | 0000900000-N | SP    | GENERIC MISCELLANEOUS ITEM<br>PLANTING SOIL                                  | Lump Sum  | L.S.      |        |
| 0004                 | 0000920000-E | SP    | GENERIC MISCELLANEOUS ITEM<br>SETTING SAND FOR PAVERS                        | 2.3<br>CY |           |        |
| 0005                 | 0000960000-E | SP    | GENERIC MISCELLANEOUS ITEM<br>BRICK PAVERS FOR CURB RAMP<br>LANDING AREAS    | 80<br>SY  |           |        |
| 0006                 | 0000960000-E | SP    | GENERIC MISCELLANEOUS ITEM<br>GEOTEXTILE FABRIC FOR PAVERS                   | 80<br>SY  |           |        |
| 0007                 | 0000960000-E | SP    | GENERIC MISCELLANEOUS ITEM<br>StreetPrint XD CROSSWALKS<br>(ASPHALT SURFACE) | 130<br>SY |           |        |
| 0008                 | 0000995000-E | SP    | GENERIC MISCELLANEOUS ITEM<br>AGGREGATE BASE COURSE FOR PAVE<br>RS           | 20<br>TON |           |        |
| 0009                 | 0043000000-N | 226   | GRADING  | Lump Sum  | L.S.      |        |
| 0010                 | 0318000000-E | 300   | FOUNDATION CONDITIONING MATE-<br>RIAL, MINOR STRUCTURES                      | 10<br>TON |           |        |
| 0011                 | 0320000000-E | 300   | FOUNDATION CONDITIONING GEO-<br>TEXTILE                                      | 30<br>SY  |           |        |
| 0012                 | 0448000000-E | 310   | ***** RC PIPE CULVERTS, CLASS<br>IV<br>(12")                                 | 12<br>LF  |           |        |
| 0013                 | 0448200000-E | 310   | 15" RC PIPE CULVERTS, CLASS IV   | 8<br>LF   |           |        |
| 0014                 | 0448300000-E | 310   | 18" RC PIPE CULVERTS, CLASS IV   | 40<br>LF  |           |        |
| 0015                 | 0986000000-E | SP    | GENERIC PIPE ITEM<br>18" CIPP  | 75<br>LF  |           |        |
| 0016                 | 0995000000-E | 340   | PIPE REMOVAL   | 13<br>LF  |           |        |
| 0017                 | 1121000000-E | 520   | AGGREGATE BASE COURSE  | 43<br>TON |           |        |

County : New Hanover

| Line # | Item Number  | Sec # | Description  | Quantity    | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0018   | 1297000000-E | 607   | MILLING ASPHALT PAVEMENT, ****<br>DEPTH<br>(1.5")            | 2,730<br>SY |           |        |
| 0019   | 1491000000-E | 610   | ASPHALT CONC BASE COURSE, TYPE<br>B25.0C                     | 40<br>TON   |           |        |
| 0020   | 1503000000-E | 610   | ASPHALT CONC INTERMEDIATE<br>COURSE, TYPE I19.0C             | 20<br>TON   |           |        |
| 0021   | 1519000000-E | 610   | ASPHALT CONC SURFACE COURSE,<br>TYPE S9.5B                   | 260<br>TON  |           |        |
| 0022   | 1575000000-E | 620   | ASPHALT BINDER FOR PLANT MIX                                 | 20<br>TON   |           |        |
| 0023   | 2286000000-N | 840   | MASONRY DRAINAGE STRUCTURES                                  | 6<br>EA     |           |        |
| 0024   | 2374000000-N | 840   | FRAME WITH GRATE & HOOD, STD<br>840.03, TYPE **<br>(TYPE E)  | 4<br>EA     |           |        |
| 0025   | 2396000000-N | 840   | FRAME WITH COVER, STD 840.54                                 | 6<br>EA     |           |        |
| 0026   | 2549000000-E | 846   | 2'-6" CONCRETE CURB & GUTTER                                 | 380<br>LF   |           |        |
| 0027   | 2591000000-E | 848   | 4" CONCRETE SIDEWALK   | 10<br>SY    |           |        |
| 0028   | 2605000000-N | 848   | CONCRETE CURB RAMPS  | 8<br>EA     |           |        |
| 0029   | 2752000000-E | SP    | GENERIC PAVING ITEM<br>(GRANITE CURB)                        | 325<br>LF   |           |        |
| 0030   | 2830000000-N | 858   | ADJUSTMENT OF MANHOLES                                       | 2<br>EA     |           |        |
| 0031   | 2893000000-N | 859   | CONVERT EXISTING CATCH BASIN<br>TO JUNCTION BOX WITH MANHOLE | 2<br>EA     |           |        |
| 0032   | 3656000000-E | 876   | GEOTEXTILE FOR DRAINAGE                                      | 95<br>SY    |           |        |
| 0033   | 4072000000-E | 903   | SUPPORTS, 3-LB STEEL U-CHANNEL                               | 121<br>LF   |           |        |
| 0034   | 4102000000-N | 904   | SIGN ERECTION, TYPE E  | 10<br>EA    |           |        |
| 0035   | 4108000000-N | 904   | SIGN ERECTION, TYPE F  | 2<br>EA     |           |        |

County : New Hanover

| Line # | Item Number  | Sec # | Description  | Quantity    | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0036   | 4155000000-N | 907   | DISPOSAL OF SIGN SYSTEM, U-CHANNEL                                       | 5<br>EA     |           |        |
| 0037   | 4400000000-E | 1110  | WORK ZONE SIGNS (STATIONARY)   | 128<br>SF   |           |        |
| 0038   | 4405000000-E | 1110  | WORK ZONE SIGNS (PORTABLE)   | 192<br>SF   |           |        |
| 0039   | 4410000000-E | 1110  | WORK ZONE SIGNS (BARRICADE MOUNTED)                                      | 64<br>SF    |           |        |
| 0040   | 4415000000-N | 1115  | FLASHING ARROW BOARD   | 2<br>EA     |           |        |
| 0041   | 4420000000-N | 1120  | PORTABLE CHANGEABLE MESSAGE SIGN   | 2<br>EA     |           |        |
| 0042   | 4435000000-N | 1135  | CONES  | 100<br>EA   |           |        |
| 0043   | 4445000000-E | 1145  | BARRICADES (TYPE III)  | 64<br>LF    |           |        |
| 0044   | 4455000000-N | 1150  | FLAGGER  | 120<br>DAY  |           |        |
| 0045   | 4685000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)                       | 1,329<br>LF |           |        |
| 0046   | 4695000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)                       | 425<br>LF   |           |        |
| 0047   | 4725000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)                          | 19<br>EA    |           |        |
| 0048   | 4891000000-E | 1205  | GENERIC PAVEMENT MARKING ITEM (24" 90 MILS)                              | 22<br>LF    |           |        |
| 0049   | 4895000000-N | SP    | GENERIC PAVEMENT MARKING ITEM NON CAST IRON SNOWPLOWABLE PAVEMENT MARKER | 25<br>EA    |           |        |
| 0050   | 6000000000-E | 1605  | TEMPORARY SILT FENCE   | 100<br>LF   |           |        |
| 0051   | 6006000000-E | 1610  | STONE FOR EROSION CONTROL, CLASS A                                       | 35<br>TON   |           |        |
| 0052   | 6009000000-E | 1610  | STONE FOR EROSION CONTROL, CLASS B                                       | 5<br>TON    |           |        |
| 0053   | 6012000000-E | 1610  | SEDIMENT CONTROL STONE   | 40<br>TON   |           |        |

County : New Hanover

| Line # | Item Number  | Sec # | Description  | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0054   | 6015000000-E | 1615  | TEMPORARY MULCHING   | 0.25     | ACR       |        |
| 0055   | 6018000000-E | 1620  | SEED FOR TEMPORARY SEEDING   | 50       | LB        |        |
| 0056   | 6021000000-E | 1620  | FERTILIZER FOR TEMPORARY SEEDING   | 0.25     | TON       |        |
| 0057   | 6029000000-E | SP    | SAFETY FENCE   | 100      | LF        |        |
| 0058   | 6030000000-E | 1630  | SILT EXCAVATION  | 5        | CY        |        |
| 0059   | 6036000000-E | 1631  | MATTING FOR EROSION CONTROL  | 100      | SY        |        |
| 0060   | 6042000000-E | 1632  | 1/4" HARDWARE CLOTH  | 200      | LF        |        |
| 0061   | 6084000000-E | 1660  | SEEDING & MULCHING   | 0.25     | ACR       |        |
| 0062   | 6087000000-E | 1660  | MOWING   | 0.1      | ACR       |        |
| 0063   | 6090000000-E | 1661  | SEED FOR REPAIR SEEDING  | 25       | LB        |        |
| 0064   | 6093000000-E | 1661  | FERTILIZER FOR REPAIR SEEDING  | 0.1      | TON       |        |
| 0065   | 6096000000-E | 1662  | SEED FOR SUPPLEMENTAL SEEDING  | 25       | LB        |        |
| 0066   | 6102000000-E | 1664  | SODDING<br>GRASS SOD FOR MEDIAN  | 210      | SY        |        |
| 0067   | 6108000000-E | 1665  | FERTILIZER TOPDRESSING   | 0.1      | TON       |        |
| 0068   | 6114500000-N | 1667  | SPECIALIZED HAND MOWING  | 10       | MHR       |        |
| 0069   | 6117000000-N | SP    | RESPONSE FOR EROSION CONTROL   | 13       | EA        |        |
| 0070   | 6117500000-N | SP    | CONCRETE WASHOUT STRUCTURE   | 1        | EA        |        |
| 0071   | 6132000000-N | SP    | GENERIC EROSION CONTROL ITEM<br>FABRIC INSERT INLET PROTECTION<br>DEVICE | 9        | EA        |        |

County : New Hanover

---

| Line # | Item Number  | Sec # | Description  | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0072   | 6132000000-N | SP    | GENERIC EROSION CONTROL ITEM<br>FABRIC INSERT INLET PROTECTION<br>DEVICE<br>CLEANOUT | 9        | EA        |        |

---

---

1042/Oct11/Q8023.35/D254654695000/E72

Total Amount Of Bid For Entire Project :

---