



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

DANIEL H. JOHNSON
SECRETARY

November 26, 2025

To: Prospective Bidders

From: Jonathan W. Mitchell
Division Contract Engineer

Signed by:

Jonathan Mitchell

02B404268BC84C2...

Contract ID#: DC00494
TIP#: HS-2403C
WBS Element: 50975.3.4

Subject: Addendum #1: Duplin County Sinusoidal Rumble Strips

The Subject contract proposal contains the following addendum:

- 1- Pay item quantities have been modified for Shoulder Borrow, Asphalt Binder for Plant Mix, and Asphalt Conc. Intermediate Course, Type I19.0C. Replace the bid form with the attached.
- 2- Replace plan sheet 8 with the attached.

*****An Addendum has been added to Bid Express & the NCDOT Letting Site.**

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
5501 BARBADOS BOULEVARD
CASTLE HAYNE, NC 28429-5647

Telephone: (910) 341-2000
Fax: (910) 675-0143
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
5501 BARBADOS BOULEVARD
CASTLE HAYNE, NC 28429-5647

County: DUPLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1231000000-E	560	SHOULDER BORROW	375 CY		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	5.26 SMI		
0004	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,387 TON		
0005	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	67 TON		
0006	1881000000-E	SP	GENERIC PAVING ITEM SINUSOIDAL MILLED RUMBLE STRIPS, CENTERLINE (14")	102,538 LF		
0007	1881000000-E	SP	GENERIC PAVING ITEM SINUSOIDAL MILLED RUMBLE STRIPS, SHOULDER (8")	205,075 LF		
0008	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	3,250 SF		
0009	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0010	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	543,579 LF		
0011	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	177,830 LF		

1141/Nov24/Q1034108.26/D27724100000/E11

Total Amount Of Bid For Entire Project :

ADDENDUM #1 ISSUED: 11/26/2025

PROJECT NO.	SHEET NO.
HS2403C	8
50975.3.4	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	BEGIN MP	END MP	1231000000-E	1245000000-E	1575000000-E	1880000000-E	1881000000-E	1881000000-E
											SHOULDER BORROW	SHOULDER RECONSTRUCTION	ASPHALT BINDER FOR PLANT MIX	INTERMEDIATE, I19.0C	14" SINUSOIDAL RUMBLE	8" SINUSOIDAL RUMBLE
											MI	SMI	TON	TON	LF	LF
HS2403C	Duplin	1	NC-111	FROM ONSLOW COUNTY LINE TO NC 41		2	2WU	8.42	0.00	8.42						
TOTAL FOR MAP NO. 1							8.42									
HS2403C	Duplin	2	NC-111	FROM BEULAVILLE CITY LIMITS TO SR 1703 CABIN ST	1,2	2	2WU	5.80	15.20	21.00	375	5.26	67	1,387	30,624	61,248
TOTAL FOR MAP NO. 2							5.80				375	5.26	67	1,387	30,624	61,248
HS2403C	Duplin	3	NC-111	FROM SR 1703 CABIN ST TO NC 11	2	2	2WU	4.38	21.00	25.38					23,127	46,253
TOTAL FOR MAP NO. 3							4.38								23,127	46,253
HS2403C	Duplin	4	NC-111	FROM NC 11 TO WAYNE COUNTY LINE	2	2	2WU	9.24	25.74	34.98					48,787	97,574
TOTAL FOR MAP NO. 4							9.24								48,787	97,574
TOTAL FOR PROJ NO. HS2403C							27.84				375	5.26	67	1,387	102,538	205,075
GRAND TOTAL							27.84				375	5.26	67	1,387	102,538	205,075