

TIP NO
 FED AID NO STATE FUNDED
 MILLING & RESURFACING
 VARIOUS PRIMARY AND SECONDARY ROUTES IN HALIFAX COUNTY

26.570 MI

				FSC II LLC DBA ROSE BROTHERS PAVING COMPANY	BARNHILL CONTRACTING CO	ADAMS CONSTRUCTION COMPANY	
				RALEIGH, NC	ROCKY MOUNT, NC	ROANOKE, VA	
ROADWAY ITEMS							
0001	0000100000-N	800	MOBILIZATION	Lump Sum	135000.00	92420.00	73287.29
0002	1297000000-E	607	MILL ASP PVMT ***** DTH (1.5")	118,057 SY 0.90	106251.30	1.10 129862.70	1.10 129862.70
0003	1308000000-E	607	MILLN ASPHALT PVMT ***** - ***** (1.5" - 3.0")	38,526 SY 1.20	46231.20	2.60 100167.60	1.65 63567.90
0004	1330000000-E	607	INCIDENTAL MILLING	2,620 SY 3.95	10349.00	9.70 25414.00	3.00 7860.00
0005	1491000000-E	610	ASP CONC BASE CRS B25.0C	2,637 TON 40.00	105480.00	40.00 105480.00	61.80 162966.60
0006	1519000000-E	610	ASP CONC SURF CRS S9.5B	19,600 TON 34.00	666400.00	38.00 744800.00	43.21 846916.00
0007	1523000000-E	610	ASP CONC SURF CRS S9.5C	13,627 TON 39.00	531453.00	39.00 531453.00	46.00 626842.00
0008	1524000000-E	SP	ASP CONC SURF CRS S9.5C LEVEL	30 TON 55.00	1650.00	185.00 5550.00	175.00 5250.00
0009	1575000000-E	620	ASP FOR PLANT MIX	2,252 TON 335.00	754420.00	350.00 788200.00	432.20 973314.40
0010	1704000000-E	SP	PATCHING EXIST PAVEMENT	60 TON 230.00	13800.00	160.00 9600.00	130.00 7800.00
0011	2549000000-E	846	2'-6" CONC CURB & GUTTER	20 LF 80.00	1600.00	60.00 1200.00	100.00 2000.00
0012	2591000000-E	848	4" CONCRETE SIDEWALK	25 SY 80.00	2000.00	100.00 2500.00	85.00 2125.00
0013	2613000000-N	848	REM & REP CURB RAMPS	5 EA 2300.00	11500.00	2650.00 13250.00	2800.00 14000.00
0014	2830000000-N	858	ADJ MANHOLES	13 EA 550.00	7150.00	650.00 8450.00	1200.00 15600.00
0015	2845000000-N	858	ADJ METER OR VALVE BOXES	17 EA 550.00	9350.00	650.00 11050.00	995.00 16915.00
0016	4413000000-E	SP	WORK ZONE ADV/GEN WARN SIGN	1,552 SF 5.75	8924.00	4.95 7682.40	4.95 7682.40
0017	4447000000-E	SP	PED CHANNEL DEVICES	32 LF 30.00	960.00	75.00 2400.00	29.00 928.00
0018	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum	124000.00	15000.00	57444.00
0019	4685000000-E	1205	THERMO PVT MKG LINES 4"90	93,807 LF 0.53	49717.71	0.53 49717.71	0.40 37522.80
0020	4688000000-E	1205	THERMO PVT MKG LINES,6"90 MILS	51,700 LF 0.80	41360.00	0.80 41360.00	0.54 27918.00
0021	4695000000-E	1205	THERMO PVT MKG LINES 8"90 MILS	420 LF 3.00	1260.00	3.00 1260.00	1.40 588.00
0022	4700000000-E	1205	12"WIDE THERMO 90 MILS	250 LF 3.50	875.00	3.50 875.00	2.25 562.50
0023	4720000000-E	1205	THERMO PVT MKG CHARACTER 90	10 EA 85.00	850.00	85.00 850.00	100.00 1000.00
0024	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	91 EA 130.00	11830.00	130.00 11830.00	100.00 9100.00
0025	4770000000-E	1205	4" COLD APPL PLSTIC LINES TYPE ** (TYPE 2)	1,120 LF 2.35	2632.00	2.35 2632.00	5.00 5600.00
0026	4775000000-E	1205	6" COLD APPL PLSTIC LINES TYPE ** (TYPE 2)	1,860 LF 2.90	5394.00	2.90 5394.00	6.25 11625.00
0027	4850000000-E	1205	LINE REMOVAL 4" WIDE	2,980 LF 0.75	2235.00	0.75 2235.00	1.00 2980.00
0028	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM (LF) 4" HOT SPRAY THERMOPLASTIC PM LINES (50 MILS)	345,667 LF 0.30	103700.10	0.30 103700.10	0.23 79503.41
0029	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM (LF) THERMOPLASTIC PM LINES (16", 90 MILS)	250 LF 9.00	2250.00	9.00 2250.00	6.00 1500.00
0030	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM (LF) THERMOPLASTIC PM LINES (24", 90 MILS)	501 LF 9.00	4509.00	9.00 4509.00	9.00 4509.00
0031	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM (EA) NON-CAST IRON SNOWFLOWABLE PAVEMENT MARKERS	800 EA 37.00	29600.00	37.00 29600.00	45.00 36000.00
0032	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,300 LF 6.25	20625.00	7.35 24255.00	7.10 23430.00
CONTRACT TOTAL				TOTAL	2813356.31	TOTAL 2874947.51	TOTAL 3256200.00

TIP NO
FED AID NO STATE FUNDED
MILLING & RESURFACING
VARIOUS PRIMARY AND SECONDARY ROUTES IN HALIFAX COUNTY

26.570 MI

ROADWAY ITEMS		SUB-TOTAL	2813356.31	SUB-TOTAL	2874947.51	SUB-TOTAL	3256200.00
BIDDERS IN ORDER				CONTRACT TOTAL			
FSC II LLC DBA ROSE BROTHERS PAVING COMPANY	1		2813356.31				
BARNHILL CONTRACTING CO	2		2874947.51				
ADAMS CONSTRUCTION COMPANY	3		3256200.00				