



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

DANIEL H. JOHNSON
SECRETARY

February 17, 2026

Addendum No. 1

RE: **DD00479**
Wayne County

To Whom It May Concern:

Reference is made to the above-mentioned project. The following changes/additions/deletions have been made:


1. Per the Bill of Materials for the Structure, the HP14x73 piles should be galvanized. This will change the Pile Drive Equipment Setup item and the Steel Pile item. This has been corrected on the Proposal Item Sheet.
2. The Bill of Materials also shows a column for PDA testing, however, there was no line item for it. This testing is now Dynamic Pile Testing and it has been added to the Proposal Item Sheet.

Please replace the Proposal Item Sheets in the proposal with the attached sheets dated Feb 16, 2026 to correct both errors.

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

DocuSigned by:

BD9FE36C1AA642B... 02/17/2026

Vickie P. Gardner
Division Four Contract Engineer

VPG/
Attachments

County: WAYNE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	140 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0009	0248000000-N	SP	GENERIC GRADING ITEM GENERIC GRADING ITEM - REINFORCED BRIDGE APPROACH FILL TYPE 1	Lump Sum	L.S.	
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0011	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	30 SY		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	32 LF		
0013	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	44 LF		
0014	0995000000-E	340	PIPE REMOVAL	44 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	180 SY		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	150 TON		

County: WAYNE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	210 TON		
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	25 TON		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0021	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	200 SY		
0022	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0024	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE	6 LF		
0026	2556000000-E	846	SHOULDER BERM GUTTER	30 LF		
0027	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
0028	2619000000-E	850	4" CONCRETE PAVED DITCH	12 SY		
0029	3030000000-E	862	STEEL BEAM GUARDRAIL	125 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0032	3287000000-N	862	GUARDRAIL END UNITS, TYPE TL-3	4 EA		
0033	3628000000-E	876	RIP RAP, CLASS I	60 TON		
0034	3635000000-E	876	RIP RAP, CLASS II	290 TON		

County: WAYNE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	3649000000-E	876	RIP RAP, CLASS B	20 TON		
0036	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,030 SY		
0037	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (TYPE E)	117 SF		
0038	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	200 LF		
0039	4102000000-N	904	SIGN ERECTION, TYPE E	20 EA		
0040	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8 EA		
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	529 SF		
0042	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0044	4435000000-N	1135	CONES	20 EA		
0045	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0046	4455000000-N	1150	FLAGGER	4 DAY		
0047	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,680 LF		
0048	6000000000-E	1605	TEMPORARY SILT FENCE	715 LF		
0049	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	65 TON		
0050	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	135 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	90 TON		

County: WAYNE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0053	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0054	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0055	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0056	6029000000-E	SP	SAFETY FENCE	460 LF		
0057	6030000000-E	1630	SILT EXCAVATION	180 CY		
0058	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
0059	6037000000-E	1629	COIR FIBER MAT	160 SY		
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	95 LF		
0061	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0062	6071002000-E	1642	FLOCCULANT	35 LB		
0063	6071010000-E	1642	WATTLE	50 LF		
0064	6071013000-E	1642	WATTLE BARRIER	330 LF		
0065	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0066	6087000000-E	1660	MOWING	0.5 ACR		
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0068	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County: WAYNE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0070	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0071	6111000000-E	SP	IMPERVIOUS DIKE	194 LF		
0072	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0073	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	13 EA		
0074	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1 EA		
0075	6123000000-E	1670	REFORESTATION	1 ACR		
0076	6132000000-N	SP	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT	3 EA		
STRUCTURE ITEMS						
0077	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+15.00 -L-)	Lump Sum	L.S.	
0078	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0079	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15+15.00 -L-)	Lump Sum	L.S.	
0080	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	55.7 CY		
0081	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+15.00 -L-)	Lump Sum	L.S.	
0082	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,654 LB		
0083	8328400000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** GALVANIZED STEEL PILES (14X73)	8 EA		

County: WAYNE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0084	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP12X53)	14 EA		
0085	8364000000-E	450	HP 12 X 53 STEEL PILES	770 LF		
0086	8384200000-E	450	HP 14 X 73 GALVANIZED STEEL PILES	600 LF		
0087	8393000000-N	450	PILE REDRIVES	11 EA		
0088	8475000000-E	460	TWO BAR METAL RAIL	184.6 LF		
0089	8517000000-E	460	1'*** X ***** CONCRETE PARAPET (1'-2" X 2'-8 3/4")	200 LF		
0090	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	257 TON		
0091	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	286 SY		
0092	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0093	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,100 LF		
0094	8860000000-N	SP	GENERIC STRUCTURE ITEM EPOXY COATING	Lump Sum	L.S.	
0095	8394000000-N	450	DYNAMIC PILE TESTING	2 EA		

1623/Feb16/Q22310.7/D440686725000/E95

Total Amount Of Bid For Entire Project :