

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

March 31, 2022

Addendum No. 1

RE: **DD00383**

Wayne County

To Whom It May Concern:

Reference is made to the above-mentioned project. The following changes/additions have been made:

- 1. The ICT 3 for Day and Time and Holiday and Holiday Lane Restrictions were inadvertently omitted from the Proposal. Please add the attached sheet 7A and 7B to include this ICT.
- 2. The plan sheet 2A-1 and quantities have been updated to include the proposed asphalt driveway at -Y2- 10+75 Rt. Please use the updated Plan Set and Proposal Item Sheets dated Mar 31, 2022.

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

Vickie P. Yardner

----BD9FE36C1AA642B...

03/31/2022

Vickie P. Gardner Division Four Contract Engineer

Attachments

Website: www.ncdot.gov

INTERMEDIATE CONTRACT TIME NUMBER 3 AND LIQUIDATED DAMAGES:

SP1 G14 A

The Contractor shall complete the required work of installing, maintaining, and removing the traffic control devices for lane closures and restoring traffic to the existing traffic pattern. The Contractor shall not close or narrow a lane of traffic on US-13 (Berkeley Blvd) during the following time restrictions:

DAY AND TIME RESTRICTIONS

Monday thru Friday, 7A.M. to 9:00 A.M. and 4:00 P.M. to 6:00 P.M.

In addition, the Contractor shall not close or narrow a lane of traffic on US-13 (Berkeley Blvd), detain and/or alter the traffic flow on or during holidays, holiday weekends, special events, or any other time when traffic is unusually heavy, including the following schedules:

HOLIDAY AND HOLIDAY WEEKEND LANE CLOSURE RESTRICTIONS

- 1. For **unexpected occurrence** that creates unusually high traffic volumes, as directed by the Engineer.
- 2. For New Year's Day, between the hours of 6:00 A.M. December 31st and 7:00 P.M January 2nd. If New Year's Day is on a Friday, Saturday, Sunday or Monday, then until 7:00 P.M the following Tuesday.
- 3. For **Easter**, between the hours of **6:00 A.M.** Thursday and **7:00 P.M** Monday.
- For Memorial Day, between the hours of 6:00 A.M. Friday and 7:00 P.M Tuesday. 4.
- 5. For **Independence Day**, between the hours of **6:00 A.M.** the day before Independence Day and 7:00 P.M. the day after Independence Day.
 - If **Independence Day** is on a Friday, Saturday, Sunday or Monday, then between the hours of 6:00 A.M. the Thursday before Independence Day and 7:00 P.M. the Tuesday after Independence Day.
- 6. For Labor Day, between the hours of 6:00 A.M. Friday and 7:00 P.M Tuesday.
- 7. For **Thanksgiving Day**, between the hours of **6:00 A.M.** Tuesday and **7:00 P.M** Monday.
- For Christmas, between the hours of 6:00 A.M. the Friday before the week of Christmas 8. Day and 7:00 P.M the following Tuesday after the week of Christmas Day.

Holidays and holiday weekends shall include New Year's, Easter, Memorial Day, Independence Day, Labor Day, Thanksgiving, and Christmas. The Contractor shall schedule his work so that lane closures will not be required during these periods, unless otherwise directed by the Engineer.

The time of availability for this intermediate contract work shall be the time the Contractor begins to install all traffic control devices for lane closures according to the time restrictions listed herein.

The completion time for this intermediate contract work shall be the time the Contractor is required to complete the removal of all traffic control devices for lane closures according to the time restrictions stated above and place traffic in the existing traffic pattern.

The liquidated damages are Two Hundred Fifty Dollars (\$250.00) per hour.

County: Wayne

Line Item Number Description Quantity **Unit Cost Amount** # # **ROADWAY ITEMS** 0001 0000100000-N 800 **MOBILIZATION** Lump Sum L.S. 801 CONSTRUCTION SURVEYING L.S. 0002 0000400000-N Lump Sum 0003 0050000000-E 226 SUPPLEMENTARY CLEARING & GRUB-1 BING **ACR** 0004 0057000000-E 226 UNDERCUT EXCAVATION 100 CY 0005 0063000000-N SP GRADING Lump Sum L.S. 0006 0106000000-E 230 **BORROW EXCAVATION** 9,250 CY 0007 0196000000-E GEOTEXTILE FOR SOIL STABILIZA-600 TION SY 0008 0318000000-E 300 FOUNDATION CONDITIONING MATE-60 RIAL, MINOR STRUCTURES TON 0009 0320000000-E 300 FOUNDATION CONDITIONING GEO-160 **TEXTILE** SY 0010 0335200000-E 305 15" DRAINAGE PIPE 216 LF 0011 0335300000-E 305 18" DRAINAGE PIPE 32 LF 18" RC PIPE CULVERTS, CLASS 0012 0372000000-E 310 12 LF 0013 0396000000-E 310 42" RC PIPE CULVERTS, CLASS 12 Ш LF 0014 0448500000-E 310 30" RC PIPE CULVERTS, CLASS IV 36 LF 0015 0448600000-E 310 36" RC PIPE CULVERTS, CLASS IV 96 LF 0016 0448700000-E 42" RC PIPE CULVERTS, CLASS IV 76 310 LF 0017 0995000000-E 340 PIPE REMOVAL 57 LF 0018 SHALLOW UNDERCUT 1099500000-E 505 200 CY CLASS IV SUBGRADE STABILIZA-0019 1099700000-E 505 400 TION TON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1220000000-E	545	INCIDENTAL STONE BASE	340 TON		
0021	1330000000-E	607	INCIDENTAL MILLING	660 SY		
0022	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,500 TON		
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,000 TON		
0024	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	185 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	27 TON		
0026	2000000000-N	806	RIGHT-OF-WAY MARKERS	20 EA		
0027	2209000000-Е	838	ENDWALLS	10.5 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0029	2355000000-N	840	FRAME WITH GRATE, STD 840.29	1 EA		
0030	2612000000-E	848	6" CONCRETE DRIVEWAY	150 SY		
0031	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	100 SY		
0032	3628000000-E	876	RIP RAP, CLASS I	35 TON		
0033	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0034	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	267 SY		
0035	4025000000-Е	901	CONTRACTOR FURNISHED, TYPE *** SIGN TYPE E	65.25 SF		
0036	4025000000-Е	901	CONTRACTOR FURNISHED, TYPE *** SIGN TYPE F	28.5 SF		
0037	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	163 LF		
0038	4102000000-N	904	SIGN ERECTION, TYPE E	8 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4108000000-N	904	SIGN ERECTION, TYPE F	3		
				EA 		
0040	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	4 EA		
0041	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	34 DAY		
0042	4457000000-N	 SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0043	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING	12,153		
			LINES (4", 90 MILS)	LF		
0044	4700000000-E	 1205	THERMOPLASTIC PAVEMENT MARKING	130		
0044	4700000000-L	1200	LINES (12", 90 MILS)	LF		
0045	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	14		
			STINDOL (90 INILS)	EA		
0046	4850000000-E	 1205	REMOVAL OF PAVEMENT MARKING	 156		
			LINES (4")	LF		
0047	4890000000-E	 SP	GENERIC PAVEMENT MARKING ITEM	100		
			THERMOPLASTIC PM LINES (24", 90 MILS)	LF		
0048	4895000000-N	 SP	GENERIC PAVEMENT MARKING ITEM	90		
			NON-CAST IRON SNOW- PLOWABLE PVMT MARKERS	EA		
0049	4915000000-E	 1264	7' U-CHANNEL POSTS	3		
				EA		
0050	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3		
				EA		
0051	6000000000-E	1605	TEMPORARY SILT FENCE	2,005		
				LF 		
0052	6006000000-Е	1610	STONE FOR EROSION CONTROL, CLASS A	125		
			CLAGG A	TON		
0053	6009000000-E	 1610	STONE FOR EROSION CONTROL,	 185		
	200700000	.0.0	CLASS B	TON		
0054	6012000000-E	 1610	SEDIMENT CONTROL STONE	210		
				TON		
0055	6015000000-E	 1615	TEMPORARY MULCHING	2.5		
-				ACR		
0056	6018000000-Е	 1620	SEED FOR TEMPORARY SEEDING	200		
				LB		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6021000000-Е	1620	FERTILIZER FOR TEMPORARY SEED- ING	1 TON		
0058	6024000000-Е	1622	TEMPORARY SLOPE DRAINS	200 LF		
0059	6029000000-Е	SP	SAFETY FENCE	200 LF		
0060	6030000000-Е	1630	SILT EXCAVATION	270 CY		
0061	6036000000-Е	1631	MATTING FOR EROSION CONTROL	2,185 SY		
0062	6037000000-Е	SP	COIR FIBER MAT	100 SY		
0063	6042000000-Е	1632	1/4" HARDWARE CLOTH	595 LF		
0064	6071010000-Е	SP	WATTLE	400 LF		
0065	6071020000-Е	SP	POLYACRYLAMIDE (PAM)	60 LB		
0066	6071030000-Е	1640	COIR FIBER BAFFLE	50 LF		
0067	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0068	6087000000-E	1660	MOWING	3 ACR		
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0070	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0073	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0074	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0075	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0076	7060000000-E	1705	SIGNAL CABLE	570 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	6 EA		
0078	7252000000-E	1710	MESSENGER CABLE (1/4")	130 LF		
0079	7264000000-E	1710	MESSENGER CABLE (3/8")	290 LF		
0800	7300000000-E	1715	UNPAVED TRENCHING (********) (1)(2")	660 LF		
0081	7300000000-E	1715	UNPAVED TRENCHING (*********) (3)(2")	30 LF		
0082	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	9 EA		
0083	7360000000-N	1720	WOOD POLE	4 EA		
0084	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0085	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0086	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0087	7444000000-Е	1725	INDUCTIVE LOOP SAWCUT	270 LF		
0088	7456000000-E	1726	LEAD-IN CABLE (************) (14-2 SHIELDED)	1,310 LF		
0089	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0090	7696000000-N	1751	CONTROLLERS WITH CABINET (************************************	1 EA		
0091	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	3 EA		
0092	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
0093	7948000000-N	1757	TRAFFIC SIGNAL REMOVAL	1 EA		