

TIP NO

10.650 MILES

FED AID NOSTATE FUNDED

MILLING RESURFACING, AND CONCRETE CURB RAMPS

1 SECTION OF NC-42 AND 8 SECTIONS OF SECONDARY ROUTES

					BARNHILL CONTRACTING CO		FSC II LLC DBA FRED SMITH COMPANY	
					ROCKY MOUNT, NC		RALEIGH, NC	
ROADWAY ITEMS								
0001	0000100000-N	800	MOBILIZATION	Lump Sum		89,500.00		111,111.00
0002	0106000000-E	230	BORROW EXCAVATION	150 CY	17.00	2,550.00	15.00	2,250.00
0003	1220000000-E	545	INCIDENTAL STONE BASE	90 TON	80.00	7,200.00	80.00	7,200.00
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	3 SMI	2,500.00	7,500.00	3,250.00	9,750.00
0005	1297000000-E	607	MILL ASP PVMT ***** DTH 1-1/2"	40,608 SY	0.75	30,456.00	1.00	40,608.00
0006	1330000000-E	607	INCIDENTAL MILLING	5,100 SY	10.00	51,000.00	10.00	51,000.00
0007	1503000000-E	610	ASP CONC INTR CRS I19.0C	590 TON	65.00	38,350.00	64.00	37,760.00
0008	1519000000-E	610	ASP CONC SURF CRS S9.5B	11,448 TON	58.00	663,984.00	51.50	589,572.00
0009	1523000000-E	610	ASP CONC SURF CRS S9.5C	3,867 TON	53.00	204,951.00	61.00	235,887.00
0010	1575000000-E	620	ASP FOR PLANT MIX	1,001 TON	450.00	450,450.00	525.00	525,525.00
0011	2549000000-E	846	2'-6" CONC CURB & GUTTER	50 LF	53.00	2,650.00	55.00	2,750.00
0012	2591000000-E	848	4" CONCRETE SIDEWALK	30 SY	83.00	2,490.00	90.00	2,700.00
0013	2605000000-N	848	CONCRETE CURB RAMPS	4 EA	2,100.00	8,400.00	2,100.00	8,400.00
0014	2612500000-N	848	REM & REP CONC CURB RAMP	17 EA	2,450.00	41,650.00	2,450.00	41,650.00
0015	2815000000-N	858	ADJ DROP INLETS	5 EA	1,000.00	5,000.00	1,000.00	5,000.00
0016	2830000000-N	858	ADJ MANHOLES	24 EA	750.00	18,000.00	750.00	18,000.00
0017	2845000000-N	858	ADJ METER OR VALVE BOXES	12 EA	650.00	7,800.00	650.00	7,800.00
0018	4413000000-E	SP	WORK ZONE ADV/GEN WARN SIGN	1,208 SF	6.35	7,670.80	5.00	6,040.00
0019	4447000000-E	SP	PED CHANNEL DEVICES	20 LF	20.00	400.00	20.00	400.00
0020	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum		11,100.00		19,792.96
0021	4688000000-E	1205	THERMO PVT MKG LINES,6"90 MILS	40,772 LF	0.70	28,540.40	0.70	28,540.40
0022	4700000000-E	1205	12"WIDE THERMO 90 MILS	2,550 LF	2.98	7,599.00	2.98	7,599.00
0023	4704000000-E	1205	THERMO LINES 16" 90MILS	90 LF	16.00	1,440.00	16.00	1,440.00
0024	4709000000-E	1205	24"WIDE THERMO 90 MILS	170 LF	18.00	3,060.00	18.00	3,060.00
0025	4720000000-E	1205	THERMO PVT MKG CHARACTER 90	26 EA	110.00	2,860.00	110.00	2,860.00
0026	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	23 EA	110.00	2,530.00	125.00	2,875.00
0027	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM (LF) THERMOPLASTIC PAVEMENT MARKING LINES (4" X 60 MILS)	202,849 LF	0.36	73,025.64	0.36	73,025.64
0028	4894900000-E	SP	GENERIC PAVEMENT MARKING ITEM (EA) POLYCARBONATE H-SHAPE MARKERS	145 EA	66.00	9,570.00	75.00	10,875.00
0029	6000000000-E	1605	TEMPORARY SILT FENCE	125 LF	3.99	498.75	2.00	250.00
0030	6071010000-E	1642	WATTLE	80 LF	15.25	1,220.00	12.00	960.00
0031	6084000000-E	1660	SEEDING AND MULCHING	3 ACR	2,850.00	8,550.00	2,500.00	7,500.00
0032	6117000000-N	1675	RESPONSE FOR EROS CONTROL	1 EA	1,250.00	1,250.00	2,500.00	2,500.00
CONTRACT TOTAL					TOTAL	1,791,245.59	TOTAL	1,864,681.00
ROADWAY ITEMS					SUB-TOTAL	1,791,245.59	SUB-TOTAL	1,864,681.00

TIP NO

10.650 MILES


FED AID NO STATE FUNDED

MILLING RESURFACING, AND CONCRETE CURB RAMPS

1 SECTION OF NC-42 AND 8 SECTIONS OF SECONDARY ROUTES

BIDDERS IN ORDER		CONTRACT TOTAL
BARNHILL CONTRACTING CO	1	1,791,245.59
FSC II LLC DBA FRED SMITH COMPANY	2	1,864,681.00

DocuSigned by:



BD9FE36C1AA642B...