



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

DANIEL H. JOHNSON
SECRETARY

August 31, 2026

Addendum No. 2

RE: **DD00529**
Wilson County

To Whom It May Concern:


Reference is made to the above-mentioned project. The following changes/additions have been made:

1. The item for the Type 1A Bridge Approach Fill was inadvertently omitted from the proposal item sheets. Please replace the proposal item sheets with the attached dated Aug. 31, 2026.
2. The completion date for the Intermediate Contract Time Number 1 has been changed. Please replace page G-2 in the proposal with the attached.

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

DocuSigned by:

BD9FE36C1AA642B... 08/31/2026

Vickie P. Gardner
Division Four Contract Engineer

VPG/
Attachments

County: WILSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	300 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0007	0223000000-E	275	ROCK PLATING	1,510 SY		
0008	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0009	1330000000-E	607	INCIDENTAL MILLING	880 SY		
0010	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	390 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	420 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	400 TON		
0013	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	65 TON		
0014	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0015	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	200 SY		
0016	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	34 CY		
0017	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		

County: WILSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0019	2077000000-E	815	6" OUTLET PIPE	6 LF		
0020	2556000000-E	846	SHOULDER BERM GUTTER	60 LF		
0021	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
0022	2619000000-E	850	4" CONCRETE PAVED DITCH	20 SY		
0023	3030000000-E	862	STEEL BEAM GUARDRAIL	1,225 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0025	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0026	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,310 LF		
0027	3635000000-E	876	RIP RAP, CLASS II	395 TON		
0028	3649000000-E	876	RIP RAP, CLASS B	6 TON		
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	770 SY		
0030	4082000000-E	903	SUPPORTS, WOOD	38 LF		
0031	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) TYPE B	1 EA		
0032	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	2 EA		
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	4 EA		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	424 SF		

County: WILSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	169 SF		
0036	4445000000-E	1145	BARRICADES (TYPE III)	112 LF		
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,120 LF		
0038	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	2 EA		
0039	4905100000-N	1253	NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKER	8 EA		
0040	6000000000-E	1605	TEMPORARY SILT FENCE	2,600 LF		
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	40 TON		
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	110 TON		
0044	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0045	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0046	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0048	6029000000-E	SP	SAFETY FENCE	660 LF		
0049	6030000000-E	1630	SILT EXCAVATION	50 CY		
0050	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,775 SY		
0051	6037000000-E	1629	COIR FIBER MAT	100 SY		

County: WILSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	220 LF		
0053	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	55 SY		
0054	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0055	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0056	6087000000-E	1660	MOWING	3 ACR		
0057	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0058	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0059	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0060	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0061	6111000000-E	SP	IMPERVIOUS DIKE	407 LF		
0062	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0063	6114800000-N	SP	MANUAL LITTER REMOVAL	2 MHR		
0064	6114900000-E	SP	LITTER DISPOSAL	1 TON		
0065	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	75 EA		
0066	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1 EA		
0067	6123000000-E	1670	REFORESTATION	0.1 ACR		
0068	6132000000-N	SP	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT	3 EA		

County: WILSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	0248000000-N	SP	GENERIC GRADING ITEM TYPE 1A BRIDGE APPROACH FILL, STA. 15+05.00 -L-	Lump Sum	L.S.	
STRUCTURE ITEMS						
0069	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** 15+05.00 -L-	Lump Sum	L.S.	
0070	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0071	8108000000-E	411	***_*** DIA DRILLED PIERS 3'-6"	148.5 LF		
0072	8111400000-E	411	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	51 LF		
0073	8114000000-N	411	SPT TESTING	1 EA		
0074	8115000000-N	411	CSL TESTING	1 EA		
0075	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** 15+05.00 -L-	Lump Sum	L.S.	
0076	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,330 SF		
0077	8161000000-E	420	GROOVING BRIDGE FLOORS	6,205 SF		
0078	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	114.7 CY		
0079	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** 15+05.00 -L-	Lump Sum	L.S.	
0080	8217000000-E	425	REINFORCING STEEL (BRIDGE)	26,178 LB		
0081	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,681 LB		
0082	8278000000-E	430	FIB *** PRESTRESSED CONCRETE GIRDERS 36"	605.83 LF		

County: WILSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0083	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES HP 12x53	10 EA		
0084	8364000000-E	450	HP 12 X 53 STEEL PILES	500 LF		
0085	8394000000-N	450	DYNAMIC PILE TESTING	1 EA		
0086	8503000000-E	460	CONCRETE BARRIER RAIL	246.5 LF		
0087	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	434 TON		
0088	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	385.6 SY		
0089	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0090	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+05+/- -L-)	Lump Sum	L.S.	

1443/Aug31/Q63447.73/D455135000000/E91

Total Amount Of Bid For Entire Project :

INTERMEDIATE CONTRACT TIME NUMBER 1 AND LIQUIDATED DAMAGES:

(7-1-95) (Rev. 2-21-12)

108

SP1 G13 A

Except for that work required under the Project Special Provisions entitled *Planting, Reforestation* and/or *Permanent Vegetation Establishment*, included elsewhere in this proposal, the Contractor will be required to complete all work included in this contract and shall place and maintain traffic on same.

The date of availability for this intermediate contract time is **November 2, 2026**.

The completion date for this intermediate contract time is **July 29, 2027**.

The liquidated damages for this intermediate contract time are **One Thousand Six Hundred Dollars (\$1,600.00)** per calendar day.

Upon apparent completion of all the work required to be completed by this intermediate date, a final inspection will be held in accordance with Article 105-17 and upon acceptance, the Department will assume responsibility for the maintenance of all work except *Planting, Reforestation* and/or *Permanent Vegetation Establishment*. The Contractor will be responsible for and shall make corrections of all damages to the completed roadway caused by his planting operations, whether occurring prior to or after placing traffic through the project.

PERMANENT VEGETATION ESTABLISHMENT:

(2-16-12)(Rev. 1-16-24)

104

SP1 G16

Establish a permanent stand of the vegetation mixture shown in the contract. During the period between initial vegetation planting and final project acceptance, perform all work necessary to establish permanent vegetation on all erodible areas within the project limits, as well as, in borrow and waste pits. This work shall include erosion control device maintenance and installation, repair seeding and mulching, supplemental seeding and mulching, mowing, and fertilizer topdressing, as directed. All work shall be performed in accordance with the applicable section of the *Standard Specifications*. All work required for initial vegetation planting shall be performed as a part of the work necessary for the completion and acceptance of the Intermediate Contract Time (ICT). Between the time of ICT and Final Project acceptance, or otherwise referred to as the vegetation establishment period, the Department will be responsible for preparing the required National Pollutant Discharge Elimination System (NPDES) inspection records.

Once the Engineer has determined that the permanent vegetation establishment requirement has been achieved at an 80% vegetation density (the amount of established vegetation per given area to stabilize the soil) and no erodible areas exist within the project limits, the Contractor will be notified to remove the remaining erosion control devices that are no longer needed. The Contractor will be responsible for, and shall correct any areas disturbed by operations performed in permanent vegetation establishment and the removal of temporary erosion control measures, whether occurring prior to or after placing traffic on the project.

Payment for *Response for Erosion Control, Seeding and Mulching, Repair Seeding, Supplemental Seeding, Mowing, Fertilizer Topdressing, Silt Excavation, and Stone for Erosion Control* will be made at contract unit prices for the affected items. Work required that is not represented by