



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

DANIEL H. JOHNSON
SECRETARY

August 31, 2026

Addendum No. 1

RE: **DD00531**
Johnston County

To Whom It May Concern:


Reference is made to the above-mentioned project. The following changes have been made:

1. The full description for the Hot Spray and IMP pavement markings were not listed on the Proposal Item Sheets, only on the Summary of Quantities. Also, the Hot Spray should be 60 MILS instead of 50 MILS as shown on the Summary of Quantities. Please replace Page 2 of 2 Thermoplastic and Paint Quantities and Proposal Item Sheets in the proposal with the attached sheets.

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

DocuSigned by:

BD9FE36C1AA642B... 08/31/2026

Vickie P. Gardner
Division Four Contract Engineer

VPG/
Attachments

PROJECT NO.	SHEET NO.	TOTAL NO.
2027CPT.04.08.20511	2	2

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	WORK ZONE ADVANCE/GE NERAL WARNING SIGNING	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	TEMPORARY TRAFFIC CONTROL	4413000000-E	4422000000-N	4457000000-N	4695000000-E		4704000000-E	4709000000-E	4720000000-E			4725000000-E			4810000000-E		4890000000-E				
															8" X 90 M YELLOW THERMO	8" X 90 M WHITE THERMO	THERMOPLAS TIC PAVEMENT MARKING LINES (16", 90 MILS)	THERMOPLAS TIC PAVEMENT MARKING LINES (24", 90 MILS)	THERMO MSG STOP 90 M	THERMO MSG AHEAD 90 M	THERMO RXR 90 M	THERMO STR ARROW 90 M	THERMO RT ARROW 90 M	THERMO MERGE ARROW LEFT (90 MILS)	THERMO LT ARROW 90 M	THERMO STR & RT ARROW 90 M	4" YELLOW PAINT	4" WHITE PAINT	THERMOPLAS TIC PAVEMENT MARKING LINES - 4"X60 MILS HOT SPRAY - YELLOW	THERMOPLAS TIC PAVEMENT MARKING LINES - 4"X60 MILS HOT SPRAY - WHITE	INTEGRATED MULTIPOLYMER (WHITE) PAVEMENT MARKINGS 4" X 90 MILS	INTEGRATED MULTIPOLYMER (YELLOW) PAVEMENT MARKINGS 4" X 90 MILS		
								MI	FT			SF	DAY	LS	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
2027CPT.04.08.20511	Johnston	1	SR-1934 / OLD BEULAH RD	FROM SR-2127 SHOEHEEL ROAD TO SR-1003 BUFFALO ROAD	1	2	2WU	9.9	22	3.93	13.83	1,112	14	0.34	250					8	10							99,317	104,544	99,317	104,544			
TOTAL FOR MAP NO. 1								9.9				1,112	14	0.34	250				8	10							99,317	104,544	99,317	104,544				
2027CPT.04.08.20511	Johnston	2	SR-1330 / RALEIGH RD	FROM SR 1354 CAMELLA ROAD TO US HIGHWAY 301	2	2		1.32	22	13.2	14.52	148	4	0.04						4							13,242	13,939	13,242	13,939	400	400		
TOTAL FOR MAP NO. 2								1.32				148	4	0.04						4							13,242	13,939	13,242	13,939	400	400		
2027CPT.04.08.20511	Johnston	3	SR-1560 / RANCH RD	FROM SR 1561 LEE ROAD TO EXISTING PAVEMENT JOINT ~600 LF SOUTH OF SR 1563 LITTLE CREEK CHURCH ROAD	1	2	2WU	2.72	22	0	2.72	316	6	0.12	300						150							28,090	29,568	28,090	29,568	400	400	
TOTAL FOR MAP NO. 3								2.72				316	6	0.12	300						150							28,090	29,568	28,090	29,568	400	400	
2027CPT.04.08.20511	Johnston	4	SR-1204 / S MARKET ST	FROM NC HIGHWAY 50 TO END OF PAVEMENT	3	2	2WU	1.126	20	0.161	1.287	144	4	0.04														12,841	13,517	12,841	13,517			
TOTAL FOR MAP NO. 4								1.126				144	4	0.04														12,841	13,517	12,841	13,517			
2027CPT.04.08.20511	Johnston	5	SR-1756 / S LOMBARD ST	FROM SR 1004 MAIN STREET TO US 70 ALT	3	2	2WU	0.47	36	0	0.47	56	4	0.03		100												4,715		4,715				
TOTAL FOR MAP NO. 5								0.47				56	4	0.03		100												4,715		4,715				
2027CPT.04.08.20511	Johnston	6	SR-2517 / SHORT CREECH RD	FROM SR 2516 PRESTON ROAD TO SR 2310 STEVENS CHAPEL ROAD	1	2	2WU	0.4	20	0	0.4	48	4	0.01														8,026	8,448	4,013	4,224			
TOTAL FOR MAP NO. 6								0.4				48	4	0.01														8,026	8,448	4,013	4,224			
2027CPT.04.08.20511	Johnston	7	SR-1553 / SHOTWELL RD	FROM US HIGHWAY 70 BUSINESS TO SR 1700 COVERED BRIDGE ROAD	3	2	2WU	1.13	36	0.6	1.73	128	6	0.07	150	125	150	200									30	4	22,672	11,933	22,672	11,933		
TOTAL FOR MAP NO. 7								1.13				128	6	0.07	150	125	150	200									30	4	22,672	11,933	22,672	11,933		
2027CPT.04.08.20511	Johnston	8	SR-2310 / STEVEN'S CHAPEL RD	FROM SR 1007 BRODGEN ROAD TO US HIGHWAY 70 ALT	1	2	2WU	5.649	20	0	5.649	636	6	0.17	300								1			3	2	56,671	59,653	57,121	59,653			
TOTAL FOR MAP NO. 8								5.649				636	6	0.17	300								1			3	2	56,671	59,653	57,121	59,653			
2027CPT.04.08.20511	Johnston	9	SR-1161 / THOMAS RD	FROM SR 1264 HOCKADAY RD TO NC HIGHWAY 96	1	2	2WU	0.757	20	0	0.757	88	2	0.02														7,594	7,994	7,594	7,994			
TOTAL FOR MAP NO. 9								0.757				88	2	0.02														7,594	7,994	7,594	7,994			
2027CPT.04.08.20511	Johnston	10	SR-2379 / TILGHMAN ST	FROM SR 2347 N RAILROAD ST TO DEAD END	1	2	2WU	0.46	20	0	0.46	52	2	0.01																				
TOTAL FOR MAP NO. 10								0.46				52	2	0.01																				
2027CPT.04.08.20511	Johnston	11	SR-1534 / TWO CLAUDE RD	FROM SR 1533 MT PLEASANT ROAD TO SR 1536 HONEYCUT ROAD	1	2	2WU	1.39	20	0	1.39	156	2	0.04														13,944	14,678	13,944	14,678			
TOTAL FOR MAP NO. 11								1.39				156	2	0.04														13,944	14,678	13,944	14,678			
2027CPT.04.08.20511	Johnston	12	SR-1574 / WILSON JONES RD	FROM SR 1573 COLE ROAD TO SR 1563 LITTLE CREEK CHURCH ROAD	1	2	2WU	0.96	20	0	0.96	108	2	0.01				75										9,631	10,138	9,631	10,138			
TOTAL FOR MAP NO. 12								0.96				108	2	0.01				75										9,631	10,138	9,631	10,138			
2027CPT.04.08.20511	Johnston	13	SR-2526 / WOODARD RD	FROM SR 2523 BAKERS CHAPEL ROAD TO SR 1007 BRODGEN ROAD	1	2	2WU	3.23	20	0	3.23	364	6	0.10														32,403	34,109	32,403	34,109			
TOTAL FOR MAP NO. 13								3.23				364	6	0.100														32,403	34,109	32,403	34,109			
TOTAL FOR PROJ NO. 2027CPT.04.08.20511								29.512				3,356	62	1.000	1,000	225	270	725	8	10	4	15	8	5	33	6	309,146	308,521	305,583	304,297	800	800		
															1,225				22			15	8	67			617,667			611,480				
GRAND TOTAL								29.512				3,356	62	1.000	1,000	225	270	725	8	10	4	15	8	5	33	6	309,146	308,521	305,583	304,297	800	800		
															1,225				22			15	8	67			617,667			611,480				

County: JOHNSTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	180 TON		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH 1-1/2"	67,848 SY		
0004	1330000000-E	607	INCIDENTAL MILLING	7,105 SY		
0005	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	31,821 TON		
0006	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,479 TON		
0007	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2,227 TON		
0008	1704000000-E	SP	PATCHING EXISTING PAVEMENT	1,510 TON		
0009	2815000000-N	858	ADJUSTMENT OF DROP INLETS	5 EA		
0010	2830000000-N	858	ADJUSTMENT OF MANHOLES	13 EA		
0011	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	7 EA		
0012	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	3,356 SF		
0013	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	62 DAY		
0014	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0015	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,225 LF		
0016	4704000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 90 MILS)	270 LF		
0017	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	725 LF		

County: JOHNSTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4720000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MILS)	22 EA		
0019	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	67 EA		
0020	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	617,667 LF		
0021	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES (4", 60 MILS)	609,880 LF		
0022	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM INTEGRATED MULTIPOLYMER (IMP) PAVEMENT MARKINGS (4", 90 MILS)	1,600 LF		

1500/Aug31/Q1347071/D70093100000/E22

Total Amount Of Bid For Entire Project :